

# Calibration: Design Status

Jelena Maricic, Kendall Mahn

# Calibration Scope

Calibration of the ND LAr TPC with photoelectron laser that also includes calibration of the light readout system: calibrate position and charge throughout LAr TPC fiducial volume with precision better than 4 mm and energy resolution better than FD.


Calibration system is composed of the following parts:

- Photoelectric targets on the cathode
- 266 nm Nd:Yag laser that provides light for target illumination
- Laser beam to optical fiber interface
- Multiplexer used to switch between fibers for light injection into different modules
- Optical fibers to guide light from multiplexer into cryostat and behind anode tile
- Light illumination via optical fibers through small holes in the anode plane




Scope table can be found at:

[https://docs.google.com/spreadsheets/d/14UJ-33KGB6XQvI4PmmUwzkGBmTfmMh\\_QHRmioHTEeNg/edit?usp=sharing](https://docs.google.com/spreadsheets/d/14UJ-33KGB6XQvI4PmmUwzkGBmTfmMh_QHRmioHTEeNg/edit?usp=sharing)

# CAD drawings



Light injection locations



# Scope table

Task/Item	Qty	Spares	Institutions	Funding Source	Funding Status	Detailed description
Laser	7	1	University of Hawaii	DUNE-US Project	Allocated	1 laser is allocated from R&D funds, but additional funds will be required for procurement of a spare laser
Laser safety enclosure box	7	0	University of Hawaii	DUNE-US Project	Not-allocated	Custom made box to enclose the beam
Powermeter	7	1	University of Hawaii	DUNE-US Project	Not-allocated	Commercial device used to monitor the pulse-to-pulse variation between laser pulses and overall power stability
Multiplexer	7	1	University of Hawaii	DUNE-US Project	Not-allocated	Multiplexer provides an interface between the laser/fiber and multiple optical fibers leading to TPC module in sequential order. Available from a vendor.
Flanges	70	1	University of Hawaii	DUNE-US Project	Not-allocated	One flange with 3 optical feedthroughs for each side of each TPC module.
Quartz fibers (600 um core)	210	10	University of Hawaii	DUNE-US Project	Not-allocated	Quartz fiber 600 um (8 m long); 3 fibers per volume; 6 per module \$47/m
Fiber holder	210	10	University of Hawaii	DUNE-US Project	Not-allocated	Custom-made holders to attach fibers inside TPC
Lenses and other optical elements	210	10	University of Hawaii	DUNE-US Project	Not-allocated	Focusing elements for laser beam - fiber interface
Photoelectric targets	10500	100	MSU	DUNE-US Project	Not-allocated	Photoelectric target design, production and assembly
Fiber routing between flange and TPC			MSU	DUNE-US Project	Not-allocated	Assembly
Wheel for fiber routing on TPC backplate	70	5	University of Hawaii/MSU	DUNE-US Project	Not-allocated	Design, fabrication and assembly
Assembly			University of Hawaii/MSU	DUNE-US Project	Not-allocated	Assembly
Packaging and Shipping			University of Hawaii/MSU	DUNE-US Project	Not-allocated	
Support during ND A&T			University of Hawaii/MSU	DUNE-US Project	Not-allocated	Technical/scientific support during TPC Module assembly and test program at the MATF, including travel.
Support during ND I&I			University of Hawaii/MSU	DUNE-US Project	Not-allocated	Technical/scientific support during TPC Module installation and integration at the DUNE Near Detector Site including travel.

[https://docs.google.com/spreadsheets/d/14UJ-33KGB6XQvI4PmmUwzkGBmTfmMh\\_QHRmioHTEeNg/edit?usp=sharing](https://docs.google.com/spreadsheets/d/14UJ-33KGB6XQvI4PmmUwzkGBmTfmMh_QHRmioHTEeNg/edit?usp=sharing)

# Documents

Document	Status	Notes	Location
Requirements	Fairly developed	Needs update	Google drive
Manufacturing and Procurement	Immature	Technology selection dependent	EDMS
QA & QC	Immature	Basic information only	EDMS
Interface Charge Readout	Started/Immature	Target goals set, additional info pending	Google doc
Interface Light Readout	Started/Immature	Scope discussed, need to iterate	Google doc
Interface module structure	Started/Immature	CAD drawings exist, document needs to be compiled	N/A
Interface with cryostat	Lacking	Discussion initiated	N/A

# Risk updates

Risk is described in detail in the risk registry document.

Some of the risk registry updates will be updated after calibration test run at SLAC single cube.

# Prototyping plans

Run at SLAC Single Cube to:

- Establish quantum efficiency of the selected targets
- Verify whether the electron yield is sufficient to be registered by cold electronics
- Test laser - fiber interface
- Test operation and light distribution in LAr
- Addition of the radioactive targets for the extended scope study

# Prototyping Plan Status

Expect to run the tests at SLAC Single Cube after the current test of the field cage are complete (approximately end of January)

In the meantime:

- Testing various photoelectric targets from MSU and made in-house in vacuum with 266 nm light: different materials, surface treatment, angles of illumination
- Manufacture targets attached to cathode + metalized cathodes for test
- Developing laser box for laser-fiber interface
- Investigation of the efficient light injection and R&D how to overcome, sparking, burning and damage to the fiber tip when focusing laser beam to fiber tip at full power
- Developed fiber holder for the SLAC CUBE
- Investigation of the quartz rods for the fiber-quartz rod interface
- Testing for light losses due to efficiency of light injection in the fiber, attenuation losses in the fiber, losses through flange, etc.
- Ordering parts in preparation for the SLAC CUBE (laser box partially assembled, laser ordered, fibers to be ordered)