Cavity Test Stands for Project X


Andy Hocker

Fermilab - Technical Division
Project X Collaboration Meeting, LBNL, 11-APR-2012

Additional material provided by Camille Ginsburg (FNAL), Robyn Madrak (FNAL), Prashant Khare (RRCAT)

Project X PX Linac SRF Cavities





Project X Vertical Cavity Test Facility



- Vertical testing purpose:
 - qualify cavities for dressing
 - fast (I-2 days) turnaround
 - tools for diagnosing bad cavities





- e.g. thermometry/2nd sound for quench localization
- VCTF located in FNAL Industrial Building I (IBI)
 - VTSI: operational since 2007
 - I.3 GHz (I- or 9-cell), 650 MHz (I- or 5-cell),
 SSR I
 - VTS2 & 3: installed, to be commissioned
 - all of above, plus SSR2
 - I25 W @ 2 K refrigeration capacity
 - variety of RF systems



Project X VTSI ops: 1.3 GHz and SSRI







~80 cavity tests/ year (CY2010)

Project X VTSI ops: 650 MHz



- 650 MHz beta=0.61 single-cell tested at VTSI to commission mechanics and RF system
- Six beta=0.9 single-cells now at FNAL to be tested soon
- Two beta=0.9 five-cells on order, to be tested this year


JLab β =0.61 1-cell






VTS2 and VTS3





- VTS2 cryostat prior to installation

- Two new cryostats, slightly larger
 - Enables SSR2 testing
 - Enables simultaneous cooldown of up to 6 1.3 GHz cavities
- Cryostats installed, awaiting connection to infrastructure and commissioning



Project X Horizontal Test Stands




- Located in Meson Detector Building (MDB)
 - "HTS" = pulsed 1.3 GHz cavities
 - "STC" = 325 MHz spoke resonators
 - "HTS2" (2014) = CW 650 MHz, pulsed 1.3 GHz
 - 60-80 W @ 2 K refrigeration available
- Horizontal facilities serve two purposes
 - Performance validation of dressed cavities at intermediate point between VT, CM
 - R&D for cavity auxiliary components (couplers, tuners, etc.)



MDB Layout









HTS(-I)








- Operational for ~4 yrs
 - 1.3 GHz and 3.9 GHz cavities, ~1.5 ms RF pulses
 - Two 1.3 GHz tests w/ long (8-9 ms) RF pulses
 - Adopt long-pulse test as part of standard cavity run plan
- ~2 cavity/month throughput



STC







- Operational for ~1.5 yrs
- One SSR1 cavity test (extensive)
 - Resonance control expts, magnet cooling expts
 - 4.5 K operation --- upgrade for 2 K capability to begin soon

Project X SSRI results from STC



HINS Jacketed SSR1-01 - Q₀ vs E






Design: Q_0 at 10 MV/m = 5e8

T = 4.7 K



HTS-2





- Under design at RRCAT in India
 - Finish this FY, deliver to FNAL in mid-FY14
- 650 MHz CW, I.3 GHz pulsed
- Two cavities cooled simultaneously for better throughput



Conclusions



- FNAL has (or will have) infrastructure for testing all flavors of PX cavities (excluding HWR)
 - Both bare and dressed
- Future upgrades
 - Increased facility throughput
 - 2K capability for dressed spoke resonators
 - New cavity capabilities
 - Dressed 650 MHz
 - Bare SSR2