



Fermilab's Muon Campus: Status, Experiments, and Future


Steven Boi

NuFact 2022: WG4 Muon Physics

August 5th, 2022


Fermilab's Muon Campus

- Originally the Antiproton Source during the Tevatron-era, the Muon Campus makes use of much of the existing infrastructure.
- **Booster** provides 8 GeV protons.
- The 120 GeV Main Injector is now the **Recycler**, forming 8 GeV proton bunches.
- **Target Station** was for \bar{p} production, now for μ production for **g-2**.
 - Mu2e-mode bypasses target.





Fermilab's Muon Campus

- The \bar{p} accumulator was removed.
- The \bar{p} debuncher is now the **Delivery Ring**.
 - Debuncher injection line repurposed as DR abort.
 - 505 m in length, 1.695 μ s revolution period.
- Two new transport lines were constructed, the M4 and M5, for beam delivery to **Mu2e** and **g-2**.



Muon Campus Experiments


- Muon g-2
 - Precision measurement of the anomalous magnetic moment of the muon: $a_\mu = \frac{g_\mu - 2}{2}$
 - Where g_μ is the gyromagnetic ratio of the muon: $\vec{\mu} = g_\mu \frac{e\hbar}{2m_\mu c} \vec{S}$




Muon Campus Experiments

- Muon-to-Electron Conversion Experiment (Mu2e)
 - Searching for neutrino-less muon to electron conversion in the presence of an aluminum nucleus.

$$R_{\mu e} = \frac{\Gamma(\mu^- + (A, Z) \rightarrow e^- + (A, Z))}{\Gamma(\mu^- + (A, Z) \rightarrow \nu_\mu + (A, Z - 1))}$$



- Will be one of the most intense muon beams in the world.




Muon Campus Beam Lines




Operating Mode Comparison

- ▶ Primary Proton Beam
- ▶ Secondary Beam


Nominal g-2 Operating Mode




Nominal Mu2e Operating Mode (slow extraction)



M4/M5 Beamlines



M4/M5 Beamlines



Beam Transport

M4 Beamline

- Resonant extraction from the DR.
- Transport:
 - 8.9 GeV/c, 8kW proton beam
 - $\epsilon = 30 \text{ } \pi\text{-mm-mrad}$ (95%)
 - Momentum spread ($\pm 1\%$ @ 95%)

M5 Beamline

- Extraction of μ^+ beam from the DR.
- Transport:
 - 3.1 GeV/c, <1W secondary μ^+ beam
 - Momentum spread ($\pm 2\%$ @ 95%)
 - Average polarization >90%
 - Yield of $>7 \times 10^{-7} \text{ } \mu/\text{POT}$

Muon Campus Status

- At the time of this presentation, g-2 completed its 'final' run.
 - It was anticipated that an additional μ^- run would take place after the accelerator complex summer shutdown, but this is not happening as of July 1st, 2022.
- HOT!** – Additional μ^+ run will take place (Run 6), with priority lower than Mu2e commissioning.
- The Muon Campus is unable to run g-2 and Mu2e simultaneously.
- Operations are currently shifting to Mu2e-mode, which involves commissioning the rest of the M4 beamline.
 - As of April 22nd, 2022, proton beam was successfully delivered to the Diagnostic Absorber.


Muon Campus Status: g-2 Mode

- 8 GeV proton bunches (10^{12} protons/bunch) are sent to the target station from the Recycler (15.4kW).
- From the target station, only 3.1 GeV/c particles are propagated.
 - Mostly p , some π , and few μ .
 - μ -beam comes from π decay.
- Proton contamination is removed by making 4 turns in the DR and sent to abort.
- μ^+ are extracted to g-2.




Muon Campus Status: g-2 Mode

- Better beam delivery than previous years for g-2 run 5.




Muon Campus Status: g-2 Mode

Integrated Decays in units of $\times \text{BNL}$



Muon Campus Status: g-2 Mode


Integrated Decays in units of $\times \text{BNL}$



Switching to Mu2e Operations

- Because Mu2e and g-2 are not able to run simultaneously, some operational changes must be made.
- Protons from the Recycler will bypass the Target Station and head straight into the Delivery Ring.
 - Protons are to be resonantly extracted from the Delivery Ring and sent to the Mu2e production target.
- Vertical bend magnet at the end of the shared M4/M5 line will be aligned with the M4 beamline.

M4/M5





M5

M4

- It is intended for the Muon Campus to be fully operating in Mu2e-mode in FY2024.


M4 Beamline Status

- Current Status:
 - First proton beam to Diagnostic Absorber on April 14th, 2022.
 - A Key Performance Parameter for Mu2e.



M4 Beamline Status

- Current Status:
 - Final Focus installation is nearing completion.
 - Commissioning studies to resume after 2022 Summer Shutdown.





M4 Beamline Challenges

- Challenges:
 - Commissioning 1/3-Integer Resonant Extraction.
 - Ensuring adequate beam extinction.
 - More...

Resonant Extraction

- Mu2e requires a pulsed beam structure, resonant extraction is employed to provide this.
- Continuous beam extraction is achieved by creating a resonance that destabilizes part of the beam in a controlled manner.
- The disturbed portion of the beam is pulled away by a narrow, high-potential field.
 - Electrostatic Septum (ESS)




S.Werkema

Resonant Extraction


- Resonant Extraction is not a clean process, which results in losses and scattering from the foil plane.
- The result is beam halo that enters the acceptance channel of the M4 beamline.

– This halo can be steered into the downstream acceptance channel by the extinction system.


V.Nagaslaev



$x' : x$



$y : x$




Extinction

- Mu2e requires a pulsed beam structure with no less than a 10^{-10} inter-pulse beam extinction.



$$\frac{\text{Out of time beam}}{\text{Total beam on target}} < 10^{-10}$$

- Natural beam extinction on the order of 10^{-5} is achieved by the extraction method from the DR.
 - Out-of-time beam may develop because of space charge, beam-gas interaction, or beam loading effects on the RF.
- An additional 10^{-7} can be achieved by the employing a resonant dipole extinction system.





Extinction

- An alternating current dipole located in a high-beta region will “sweep” out-of-time beam into a collimator (COL931), which is at a 90° phase advance downstream.
 - In-time beam should be fully transmitted.



- AC dipole is driven by two harmonics:
 - 300 kHz (half bunch frequency) to sweep out-of-time beam into the downstream collimator.
 - 4.5 MHz (15th harmonic) to maximize transmission of in-time beam.
- If extraction halo is not removed, it can be steered into the acceptance channel!




Single harmonic would hit collimator too soon.

Extinction & Collimation

- Two collimators in the M4 Line are used to remove the extraction halo before it reaches the extinction system.
- COL907: removes most of the extraction halo.
 - Placed as far upstream as possible.
- COL924: removes any remaining scattered particles.
 - Placed 90° in phase advance upstream of the AC dipole.
- The collimators have adjustable jaws to optimize collimation.

COL907



COL924



M4 Challenges

- Resonant Extraction faces mostly technical challenges.
 - Power supplies, vacuum controls, etc.
 - Delivery Ring was not designed for RE.
 - A lot of machine time needed for commissioning.
 - Need to reduce losses as DR was not designed for significant beam loss.
 - Currently the extraction septum is not installed and cannot be until fully finished with g-2.
- Extinction system needs to be installed and tuned to maximize in-time beam transmission while guaranteeing elimination of out-of-time beam to a $<10^{-10}$ level.
- Radiation from upstream extraction halo collimation requires additional shielding.

Final Remarks

- g-2 is quickly approaching its end of life after many successful years of running.
 - There will be an additional μ^+ run (Run 6).
- The muon campus cannot run Mu2e and g-2 simultaneously, so operations are now shifting towards Mu2e-mode.
- There are some challenges that must be met to successfully transition to Mu2e-mode:
 - Commission Resonant Extraction.
 - Commission extinction system.
- On 4/14/22, the first protons were sent down the M4 beamline to the diagnostic absorber.
 - Only a short section of the line, the Final Focus, will need to be assembled to transport beam to Mu2e.



Backup

Lab Schedule


Office of the CRO January 2022

DRAFT LONG-RANGE PLAN


		FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30			
LBNF /	SANFORD				DUNE	DUNE	DUNE	DUNE	DUNE	DUNE	DUNE	DUNE	DUNE	DUNE	v		
PIP II	FNAL				LBNF	LBNF	LBNF	LBNF	LBNF	LBNF	LBNF	LBNF	LBNF	LBNF			
NuMI	MI	MINERvA	MINERvA	OPEN	OPEN	2x2	2x2	2x2	2x2	2x2	See Note 4						
		NOvA	NOvA	NOvA	NOvA	NOvA	NOvA	NOvA	NOvA	NOvA							
BNB	B	BooNE	BooNE	BooNE	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN	LONG SHUTDOWN						
		CARUS	CARUS	CARUS	CARUS	CARUS	CARUS	CARUS	CARUS	ICARUS							
		SBND	SBND	SBND	SBND	SBND	SBND	SBND	SBND	SBND							
Muon Complex		g-2	g-2	g-2	g-2	g-2	g-2					LONG SHUTDOWN				μ	
		Mu2e	Mu2e	Mu2e	Mu2e	Mu2e	Mu2e	Mu2e	Mu2e	Mu2e	Mu2e						
SY 120	MT	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	LONG SHUTDOWN				FTBF	FTBF	p
	MC	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF	FTBF					FTBF		
	NM4	OPEN	SpinQ	SpinQ	SpinQ	SpinQ	SpinQ	SpinQ	OPEN	OPEN					OPEN		
LINAC	MTA				ITA	ITA	ITA	ITA	ITA	ITA	LONG SHUTDOWN						
		FY18	FY19	FY20	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30			

	Construction / commissioning		Run		Subject to further review		Shutdown
	Capability ended		Capability unavailable				

M2/M3 Optical Functions



M4 Optical Functions




Dispersion in the vertical plane coming out of the extraction region.

High dispersion in the horizontal plane due to significant horizontal bend towards Mu2e.

Final focus before the Mu2e production target.


Large Beta function in horizontal plane in the Extinction region.

M5 Optical Functions



Timeline Changes

- g-2 Macro-time Structure, Recycler to Target



- Mu2e Macro-time Structure, Recycler to Delivery Ring

