

Report from STT Working Group

S. Di Falco

INFN Pisa, Italy

R. Petti

University of South Carolina, Columbia SC, USA

G. Sirri

INFN Bologna, Italy

*SAND technical meeting
10 May 2022*

- ◆ *Activities related to the **design and construction of the STT for SAND**, the assigned goals being the completion of the detector installation and its readiness for operation.*

- ◆ *Initial WG chairs: G. Sirri, S. Di Falco, R. Petti*


- ◆ *Dedicated **mailing list DUNE-ND-SAND-STT***
⇒ *Encourage any interested people to subscribe (if not done yet)*

- ◆ *Material presented and discussed during WG meetings available on Indico:
<https://indico.fnal.gov/category/1402/>*

- ◆ ***By-weekly regular meetings on Wednesday at 11am Central Time / US***
 - *First meeting 13 April 2022: overview of STT activities and schedule;*
 - *Meeting 27 April 2022: testbeam activities, prototype preparation;*
 - *Meeting 11 May 2022: testbeam activities, preliminary gas leak tests.*

STT ACTIVITIES & SCHEDULE

- ◆ *Defined scope of activities* required for the completion and installation of the STT.
- ◆ *Preliminary schedule and related deliverables:*
 - *Identified main tasks and tentative timeline (to be revised following inputs/developments);*
 - *Uncertainties on availability of ND site and current situation (covid19, conflict, supplies, etc.).*



Demonstrate all aspects of the STT design in increasing order of complexity:




- ☑ *Produce straws of required quality & maximal length with ultrasonic welding (UW)*
⇒ *Validation of model production lines at JINR (5m) and GTU (2m)*
- ☑ *Verify UW straws fulfill requirements from STT conceptual design & assembly procedure*
⇒ *Measurement of maximal internal pressure, radial and longitudinal deformations vs. pressure, relaxation vs. time and humidity, gas tightness, etc.*
- ☑ *Verify XXYY straw layer assembly*
⇒ *Gluing and pressure tests of 1m × 1m XXYY test assembly*
- ☐ *Verify assembly procedure of XXYY straws to frame, gas tightness, etc.*
⇒ *Mockup prototype(s) with plexiglass frame (in progress)*
- ☐ *Verify module design with C-composite frame and related performance*
⇒ *Complete 1.2m × 0.8m prototype with XXYY straws and actual STT frame design*
- ☐ *Verify full scale module (module 0) with maximal straw length and complete assembly*
⇒ *Complete 4m × 0.5m prototype with XXYY straws and C-composite frame*

Demonstrate readout performance:

- ☑ *Verify charge measurement with ^{55}Fe source & cosmics*
⇒ *Readout small STT prototype with Mu2e FE boards with VMM3/VMM3a ASICs*
- ☑ *Verify time measurement with signal generator*
- ☐ *Verify time and charge measurement at testbeam*
⇒ *Readout small STT prototype with FE boards with VMM3/VMM3a ASICs*

D. Bick (Hamburg)

*Plexiglass frame for the
mockup prototype
ready for assembly*



Start with minimal setup:

- One plane of 6 mm straws equipped with mu2e board (one VMM3 chip)
- Scintillator for trigger
- 3 MM trackers with APV read-out





Test beam schedule:

- 25 April – 3 May parasitic
- 18 Mai – 24 May main user
- 25 Mai – 8 June parasitic



First result with muon beam

We want to measure:
Possibility to measure T@Th
with VMM3
RT dependence and time
resolution if VMM3 hybrid
boards will be available



Tasks to be completed by *early summer 2022*:

- ◆ *Preparation for CD1RR review (July 2022)*
⇒ *Based on conceptual design, review resources and costs*
- ◆ *List of candidate sites for production of straws and/or STT modules*
⇒ *Required for resource planning and site preparation*
- ◆ *Completion of assembly and test of first mockup prototype*
⇒ *Required to finalize design of 1.2m × 0.8m prototype and for preliminary design of STT modules*
- ◆ *Testbeam exposure of small XX+YY prototype with VMM3 readout*
⇒ *Required to verify that VMM3 performance fulfills STT requirements*
- ◆ *Decision about VMM3 readout and need of ASIC revision*
⇒ *Validation of ASIC capabilities with testbeam exposure at CERN in May-June*


- ◆ *Contributing institutions (expressed interest / already working):*
 - *Georgia: Georgian Technical University;*
 - *Germany: University of Hamburg;*
 - *India: IIT Guwahati, NISER, Panjab University, University of Lucknow;*
 - *Italy: INFN/Univ. Bologna, Genova, Pisa; INFN/Lab. Frascati, INFN/Lab. Catania;*
 - *Joint Institute for Nuclear Research (JINR), Dubna;*
 - *USA: BNL, Duke University, University of South Carolina, Virginia Tech.*

- ◆ *Assign resources to various tasks identified*
⇒ *Organization of work along various tasks*


- ◆ *Preliminary survey indicates need of electronics experts for readout tasks.*

- ◆ *Evaluate impact of Russia-Ukraine conflict and possible mitigations*

Backup slides




1.1 m long straws produced by GTU for moekup assembly





5 m long straws produced at JINR for the gluing tests



Pressure tests (GTU)



Straws glued together with epoxy ELK5 (~ 20cm spacing)




*Cycled multiple times
complete glued XXYY assembly
from 1 bar to 5 bar:
no problems nor apparent damages
for the straw assembly*

DESIGN ACTIVITIES

WBS	Task	Start	Finish	2020					2021				2022				2023				2024				2025				
				Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	
		Jan 1, 2020	Dec 31, 2029	◆																									
1	STT selected as SAND tracker	Sep 2, 2021	Sep 2, 2021	◆ STT selected as SAND tracker																									
2	PDR (DOE CD1RR) TBD	Jul 12, 2022	Jul 12, 2022	◆ PDR (DOE CD1RR) TBD																									
3	TDR (DOE CD2) TBD	Jul 12, 2023	Jul 12, 2023	◆ TDR (DOE CD2) TBD																									
4	ND site available TBD	Jan 1, 2028	Jan 1, 2028																										
5	STT design and prototyping	Jan 1, 2020	Dec 31, 2024	STT design and prototyping																									
5.1	STT conceptual design	Jan 1, 2020	Sep 1, 2021	STT conceptual design ✓																									
5.2	STT preliminary design	Sep 2, 2021	Jan 31, 2023	STT preliminary design																									
5.2.1	Design straw tubes	Sep 2, 2021	Dec 31, 2022	Design straw tubes																									
5.2.2	Design mechanical wire fixtures	Sep 2, 2021	Dec 31, 2022	Design mechanical wire fixtures																									
5.2.3	Design C-composite frame	Sep 2, 2021	Dec 31, 2022	Design C-composite frame																									
5.2.4	Integration with readout electronics	Sep 2, 2021	Dec 31, 2022	Integration with readout electronics																									
5.2.5	Design mechanical support structure	Jun 1, 2022	Dec 31, 2022	Design mechanical support structure																									
5.2.6	Design polypropylene target	Jun 1, 2022	Dec 31, 2022	Design polypropylene target																									
5.2.7	Design graphite target	Jun 1, 2022	Dec 31, 2022	Design graphite target																									
5.2.8	Design radiator	Jun 1, 2022	Dec 31, 2022	Design radiator																									
5.2.9	Design gas system	Jun 1, 2022	Dec 31, 2022	Design gas system																									
5.2.10	Develop assembly procedure for STT modules	Sep 2, 2021	Dec 31, 2022	Develop assembly procedure for STT modules																									
5.2.11	Design 1.2m x 0.8m prototype	Sep 2, 2021	Sep 30, 2022	Design 1.2m x 0.8m prototype																									
5.2.12	Design 4m x 0.5m prototype	Nov 1, 2022	Dec 31, 2022	Design 4m x 0.5m prototype																									
5.2.13	Conduct preliminary design review	Jan 1, 2023	Jan 15, 2023	Conduct preliminary design review																									
5.2.14	Incorporate preliminary design review comments	Jan 16, 2023	Jan 31, 2023	Incorporate preliminary design review comments																									
5.3	STT final design	Feb 1, 2023	Jan 31, 2024	STT final design																									
5.3.1	Perform final design of STT modules	Feb 1, 2023	Dec 31, 2023	Perform final design of STT modules																									
5.3.2	Perform final design of polypropilene target	Feb 1, 2023	Dec 31, 2023	Perform final design of polypropilene target																									
5.3.3	Perform final design of graphite target	Feb 1, 2023	Dec 31, 2023	Perform final design of graphite target																									
5.3.4	Perform final design of radiator	Feb 1, 2023	Dec 31, 2023	Perform final design of radiator																									
5.3.5	Perform final design of mechanical support structure	Feb 1, 2023	Dec 31, 2023	Perform final design of mechanical support structure																									
5.3.6	Perform final design of gas system	Feb 1, 2023	Dec 31, 2023	Perform final design of gas system																									
5.3.7	Conduct final design review	Jan 1, 2024	Jan 15, 2024	Conduct final design review																									
5.3.8	Incorporate final design review comments	Jan 16, 2024	Jan 31, 2024	Incorporate final design review comments																									

WBS	Task	Start	Finish	2020				2021				2022				2023				2024				2025				2026				2027			
				Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
		Jan 1, 2020	Dec 31, 2029																																
5	STT design and prototyping	Jan 1, 2020	Dec 31, 2024	STT design and prototyping																															
5.1	STT conceptual design	Jan 1, 2020	Sep 1, 2021	STT conceptual design ✓																															
5.2	STT preliminary design	Sep 2, 2021	Jan 31, 2023	STT preliminary design																															
5.3	STT final design	Feb 1, 2023	Jan 31, 2024	STT final design																															
5.4	Fabrication/prototyping of straws	Sep 2, 2021	Dec 31, 2022	Fabrication/prototyping of straws																															
5.4.1	Fabrication of straws for initial prototyping & tests (UW)	Sep 2, 2021	Dec 31, 2021	Fabrication of straws for initial prototyping & tests (UW) ✓																															
5.4.2	Fabrication of straws (ultrasonic welding - UW)	Apr 1, 2022	Dec 31, 2022	Fabrication of straws (ultrasonic welding - UW)																															
5.4.3	Procure straw samples (winding technology - WT)	Apr 1, 2022	Jun 30, 2022	Procure straw samples (winding technology - WT)																															
5.5	Fabrication of STT prototypes	Jan 1, 2022	Oct 31, 2023	Fabrication of STT prototypes																															
5.5.1	Procure of components for XYYY test assembly	Jan 1, 2022	Feb 28, 2022	Procure of components for XYYY test assembly ✓																															
5.5.2	Fabrication of XYYY test assembly	Mar 1, 2022	Mar 15, 2022	Fabrication of XYYY test assembly																															
5.5.3	Procure components for 1st mockup prototype	Jan 1, 2022	Apr 15, 2022	Procure components for 1st mockup prototype																															
5.5.4	Fabrication of 1st mockup prototype	Apr 15, 2022	May 31, 2022	Fabrication of 1st mockup prototype																															
5.5.5	Procurement & fabrication of site mockup prototypes	Jun 1, 2022	Dec 31, 2022	Procurement & fabrication of site mockup prototypes																															
5.5.6	Procure components 1.2m x 0.8m prototype	Jun 1, 2022	Aug 31, 2022	Procure components 1.2m x 0.8m prototype																															
5.5.7	Fabrication 1.2m x 0.8m prototype	Aug 1, 2022	Oct 31, 2022	Fabrication 1.2m x 0.8m prototype																															
5.5.8	Procure components and tooling for 4m x 0.5m prototype	Jan 1, 2023	May 31, 2023	Procure components and tooling for 4m x 0.5m prototype																															
5.5.9	Fabrication 4m x 0.5m prototype	Jun 1, 2023	Oct 31, 2023	Fabrication 4m x 0.5m prototype																															
5.5.10	Radiator and target prototypes	Sep 1, 2022	Oct 31, 2023	Radiator and target prototypes																															
5.6	STT readout	Jan 1, 2021	Dec 31, 2024	STT readout																															
5.6.1	Procurement of VMM3a ASICs	Jan 1, 2021	Jun 1, 2021	Procurement of VMM3a ASICs ✓																															
5.6.2	Acceptance test of VMM3a ASICs	Sep 2, 2021	Oct 31, 2021	Acceptance test of VMM3a ASICs ✓																															
5.6.3	Validation of VMM3a readout	Sep 1, 2021	Aug 31, 2022	Validation of VMM3a readout																															
5.6.4	ASIC revision	Sep 1, 2022	Dec 31, 2024	ASIC revision																															
5.6.5	Design of FE readout	Sep 1, 2022	Dec 31, 2024	Design of FE readout																															
5.7	Test of straws and STT prototypes	Aug 1, 2021	Dec 31, 2023	Test of straws and STT prototypes																															
5.7.1	Test of straw properties (UW)	Aug 1, 2021	Dec 31, 2022	Test of straw properties (UW)																															
5.7.2	Test of straw properties (WT)	Jul 1, 2022	Dec 31, 2022	Test of straw properties (WT)																															
5.7.3	Gluing & pressure tests of XYYY assembly	Mar 15, 2022	Mar 31, 2022	Gluing & pressure tests of XYYY assembly																															
5.7.4	Test & instrumentation of XYYY assembly	Apr 1, 2022	May 31, 2022	Test & instrumentation of XYYY assembly																															
5.7.5	Test of 1st mockup prototype	May 1, 2022	May 31, 2022	Test of 1st mockup prototype																															
5.7.6	Test of 1.2m x 0.8m prototype	Nov 1, 2022	Dec 31, 2022	Test of 1.2m x 0.8m prototype																															
5.7.7	Test of 4m x 0.5m prototype	Oct 1, 2023	Dec 31, 2023	Test of 4m x 0.5m prototype																															
5.7.8	Beam tests of prototypes at CERN	Oct 25, 2021	Nov 1, 2022	Beam tests of prototypes at CERN																															
5.7.8.1	Small XX+YY with VMM3a readout at H4 RD51	Oct 25, 2021	Nov 7, 2021	Small XX+YY with VMM3a readout at H4 RD51																															
5.7.8.2	Small XX+YY with VMM3/VMM3a at GIF	Apr 25, 2022	May 3, 2022	Small XX+YY with VMM3/VMM3a at GIF																															
5.7.8.3	Small XX+YY at H4 RD51/GIF	May 18, 2022	Jun 7, 2022	Small XX+YY at H4 RD51/GIF																															
5.7.8.4	XX+YY & mockup at RD51/GIF	Jul 13, 2022	Jul 26, 2022	XX+YY & mockup at RD51/GIF																															
5.7.8.5	XX+YY & mockup at RD51/GIF	Oct 19, 2022	Nov 1, 2022	XX+YY & mockup at RD51/GIF																															
5.8	Simulation of STT modules	Jan 1, 2020	Dec 31, 2023	Simulation of STT modules																															
5.8.1	Finite element analysis	Jan 1, 2021	Dec 31, 2023	Finite element analysis																															
5.8.2	Thermal analysis	Jan 1, 2021	Dec 31, 2023	Thermal analysis																															
5.8.3	Simulation of drift properties (Garfield)	Jan 1, 2021	Mar 31, 2021	Simulation of drift properties (Garfield) ✓																															
5.8.4	Optimization of operating conditions (Garfield) & validation	Apr 1, 2022	Dec 31, 2022	Optimization of operating conditions (Garfield) & validation																															
5.8.5	Simulation of physics performance	Jan 1, 2020	Dec 31, 2023	Simulation of physics performance																															
5.8.6	Optimization of physics performance	Apr 1, 2022	Dec 31, 2023	Optimization of physics performance																															

INSTALLATION & COMMISSIONING




STT FOR SAND

*70 CH₂ modules
8 C modules
6 tracking modules*


*~220,000 straws
average straw length 3.2 m
maximal straw length 3.8 m
internal gas volume ~14 m³
nominal gas pressure ~2 bar*

FV mass:
~4.7 t CH₂
~600 kg C




STRAW PRODUCTION

- ◆ Production of straws with *ultrasonic welding technology*:
 - JINR line producing 5m long straws ~ 6 straws/hour;
 - GTU line producing $<2\text{m}$ long straws ~ 80 straws/day.
- ◆ Demonstrated double Al coating on inner and outer surfaces:
 - Protection against humidity for more reliable long term operation;
 - Improved gas tightness from reduction of diffusion through straw walls;
 - May simplify ground connections through external layer.
- ◆ Tested/compared different straw types (4.9 ± 0.05 mm):
 - Wall thickness $12\ \mu\text{m}$ with single Al metallization $70\ \text{nm}$;
 - Wall thickness $20\ \mu\text{m}$ with single Al metallization $70\ \text{nm}$;
 - Wall thickness $20\ \mu\text{m}$ with double Al metallization $70\ \text{nm} + 40\ \text{nm}$.



1.1 m long straws produced by GTU for moekup assembly




5 m long straws produced at JINR for the gluing tests

MEASUREMENTS OF STRAW PROPERTIES


- ◆ *Measurement of maximal internal pressure* achievable without plastic deformations.
- ◆ *Measurement of radial deformations* vs. *internal gas pressure (GTU)*:
 - *Straws with 4.9mm diameter, 20 μm walls, produced by both JINR and GTU;*
 - *Comparison of different types of mylar film and Al metallization.*
- ◆ *Measurements of straw elongation and tension* vs. *internal gas pressure (GTU)*:
 - *Straws with 4.9mm diameter, 12 μm & 20 μm walls;*
 - *Studied tension drop with increase of internal pressure starting from initial pre-tension.*
- ◆ *Measurement of straw relaxation* vs. *time and humidity* starting from initial tension.

<i>Production</i>	<i>Diameter</i>	<i>Wall</i>	<i>Metallization</i>	<i>Length</i>	<i>P_{max} tested</i>
<i>JINR</i>	<i>4.92 mm</i>	<i>20 μm</i>	<i>Single 70 nm</i>	<i>20 cm</i>	<i>6 bar</i>
<i>GTU</i>	<i>4.96 mm</i>	<i>20 μm</i>	<i>Double 70+40 nm</i>	<i>20 cm</i>	<i>6 bar</i>





Measurement of radial deformation vs. pressure for straws 1.1 m long



Measurement of elongation and tension vs. pressure for straws 1.0 m long

GLUING AND PRESSURE TESTS

- ◆ *Completed first gluing tests of a XXYY straw layer assembly (JINR):*
 - *Built test stand 1m × 1m allowing a variation of internal gas pressure in the glued straws;*
 - *Straws glued together with ELK5 (NA64) epoxy and internal overpressure;*
 - *Initial spacing left between glued points ~20 cm.*

⇒ *Validation of the concept of XXYY glued assembly*
- ◆ *Measurement of deformations of glued XXYY assembly vs. internal gas pressure.*
- ◆ *Additional measurements on XXYY glued assembly:*
 - *Gas leak test to verify damages to straw walls;*
 - *Straw resistivity to check metallization damage induced by pressure.*

MOCKUP PROTOTYPE(S)

- ◆ *Mockup prototype(s) 35cm × 35cm for preliminary validation tests:*
 - *Completed design of mock frame (Hamburg, UofSC);*
 - *Machining of first plexiglass mockup frame being completed in Hamburg;*
 - *Required straws produced by GTU (4.9mm diameter, 20 μm walls);*
 - *End-plugs machined from simplified design;*
 - *Assembly of first mockup prototype at JINR.*

- ◆ *Main goals of mockup prototype(s):*
 - *Validate assembly procedure using same geometry/frame as in STT;*
 - *Test the connection/gluing of straws to the frame;*
 - *Test sealing and gas leaks vs. internal pressure;*
 - *Evaluate different design options.*

- ◆ *Additional mockup prototypes expected to be built at various collaborating institutions following the completion of the first one at JINR.*

TESTS OF VMM3 READOUT

- ◆ *Tests and calibration of FE boards from Mu2E (BNL) with VMM3 at JINR:*
 - *Timing calibration using signal generator and timing resolution;*
 - *Readout of small straw tracker and tests with ^{55}Fe source & cosmics.*




- ◆ *Testbeam exposure of small straw tracker with VMM3 readout in RD51 at CERN:*
 - *Two double layers $XX+YY$ with straws staggered by half diameter ($20\text{cm} \times 20\text{cm}$ active area);*
 - *Independent tracking system with 3 GEM detectors ($\sigma \sim 50\mu\text{m}$) equipped with VMM3 readout;*
 - *Setup installed in H4 beamline (JINR) and exposed to μ, π with $E \sim 160$ GeV;*
 - *Usable data taken in Oct.-Nov. 2021 (JINR, PNPI, UofSC).*

- ◆ *Ongoing analysis of testbeam data:*
 - *DAQ instability found at high rates in Time-over-Threshold mode being investigated;*
 - *Stable data taking when operated with peaking time.*


⇒ *New testbeam exposure with VMM3 readout at CERN in May 2022*

TIMING CALIBRATION


Vitalii Bautin (JINR)




M. Demichev (JINR)



Beam profile seen by GEM 3 tracker




Spatial correlation between GEM and straws



VMM3A TESTING

- ◆ Procedure to test and validate VMM3a ASICs used for 42,000 chips in ATLAS NSW



- ◆ Automatized VMM3a test stand
- ◆ Optical system to read serial numbers of the VMM3a chips being tested
- ◆ VMMT: multi-functional test board for testing and characterization of VMM3 ASICs developed by Tomsk State University (Russia) for ATLAS

- ◆ All VMM3a chips procured by UofSC tested at CERN using ATLAS NSW procedure: average yield about 70% for best selection (green) for a total of 150 chips.

PREPARATION FOR 1.2m × 0.8m PROTOTYPE


- ◆ *Prototype 1.2m × 0.8m based on design & parts as in full scale STT modules:*
 - *Build at JINR with help from GTU & other institutions;*
 - *Maximal size compatible with existing tooling & similar to NA64 detectors recently built at JINR;*
 - *4 straw layers XYYX: 672 straws total, no target, no radiator;*
 - *C-composite frame and assembly as in STT modules.*

⇒ *Aim to build the prototype in 2022 (summer?)*




- ◆ *FE analysis of deformations induced by gas pressure, wire and straw tension:*
 - *Removable lids giving access to gas manifolds and FE boards, gas tightness (O-rings, etc.);*
 - *Connection of individual straws to C-composite frame and related gas sealing;*
 - *Study interplay between internal overpressure and wire/straw tension.*

- ◆ *Evaluating options for procurement of required components.*

- ◆ *Contributing institutions:*
JINR, GTU, IIT Guwahati, Panjab, Duke, INFN, Hamburg, UofSC.




Applied pressure:
0.092 MPa
Applied Force:
100N (for 336 wires)




Gas pressure only:

- +Z 0.032 mm
- Z 0 mm



Gas pressure + wire tension:


- +Z 0.02mm
- Z 0.0002mm





Gas pressure + wire tension

+ tension from straw walls:

- +Z 0.005mm
- Z 0.004mm





1.2 m x 0.8 m prototype