



ACE – Accelerator Capabilities Enhancement – MI RF

Joseph E. Dey

January 30, 2023


PIP-II – Accelerator Upgrades - Main Injector

Table 9.12: Power calculations of current RF cavities.

	PIP-II	Main Injector - Present Capability
Beam Intensity	7.5×10^{13} protons	6.24×10^{13} protons
Harmonic Number	588	588
Number of Filled Buckets	504	504
Frequency	52.808-53.104 MHz	52.808-53.104 MHz
Acceleration Ramp Slope	240 GeV/s	240 GeV/s
Beam Intensity	7.5×10^{13} protons	6.24×10^{13} protons
Main Injector Ramp Rate	1.2 s	1.2 s
Beam Power at 120 GeV	1.2 MW	998.8 kW
Beam Accelerating Power	2.88 MW	2.40 MW
Number of Accelerating Cavities	20	20
Cavity R/Q	104	104
Maximum Cavity Accelerating Voltage	235 kV/cavity	235 kV/cavity
Operating Peak Voltage	210 kV/cavity	210 kV/cavity
Accelerating Voltage Required: $V \sin \phi_2$	2.66 MV	2.66 MV
Total Accelerating Voltage Available	4.7 MV	4.7 MV
Total Operating Voltage	4.2 MV	4.2 MV
Cavity Power Loss	45.11 kW/cavity	45.11 kW/cavity
Total Apparent Power	240.5 kW/cavity	204.2 kW/cavity
Robinson Stability Factor	4	4


In table 9.12 of the PIP-II Final Design Report, it can be found that an individual Main Injector cavity needs to be able to supply 240 kW of power.

PIP-II – Accelerator Upgrades - Main Injector



Single Power Amplifier (PA) Main Injector (MI) cavity drawing. Coupling loop shows how cavity was always envisioned to be able to support dual PA operation.

PIP-II – Accelerator Upgrades - Main Injector



Station 5 of the Main Injector was upgraded to a Dual PA cavity and has operated in this mode for the last two years with beam intensities up to $5.4E13$. It can supply 400 kW of power. The two PAs operate in a push-pull mode and easily surpasses the 240 kW needed for PIP-II operations. All twenty MI cavities will be updated to Dual PA operation.

PIP-II – Accelerator Upgrades - Main Injector




Dual Series Tube Modulator

PIP-II will also upgrade all the modulators to Dual PA operation.



PIP-II – Accelerator Upgrades - Main Injector



Main Injector Power Amplifiers

PIP-II will build a total of 40 new power amplifiers for the twenty Dual PA cavities.

PIP-II – Accelerator Upgrades - Main Injector



8 kW 53 MHz Solid State Amplifier

Each PA will have it's own 8 kW solid state amplifier after the the PIP-II Upgrade.

Solid State RF Amplifier


PIP-II – Accelerator Upgrades - Main Injector



Cable Pull

Each Dual PA requires additional cables pulled from RF gallery to the tunnel for operation of the additional power amplifier.

PIP-II – Accelerator Upgrades - Main Injector



Operations of MI
Station #5

Excerpt from PIP-II
Final Design Report

Figure 9.51: Main Injector upgraded RF cavity signals. (Green) Main Injector beam intensity, (Red) total plate current with two PAs, (Blue) PA anode voltage, (Cyan) PA grid bias voltage.

ACE – Main Injector Enhancement

	ACE	PIP-II
Beam Intensity	7.5E13 Protons	7.5E13 Protons
Harmonic Number	588	588
Number of Filled Buckets	504	504
Frequency	52.808-53.104 MHz	52.808-53.104 MHz
Acceleration Ramp Slope	500 GeV/s	240 GeV/s
Beam Intensity	7.5e13 Protons	7.5e13 Protons
Main Injector Ramp Rate	0.65 s	1.2 s
Beam Power at 120 GeV	2.22 MW	1.2 MW
Beam Accelerating Power	6 MW	2.88 MW
Number of Accelerating Cavities	37	20
Cavity R/Q	104	104
Maximum Cavity Accelerating Voltage	240 kV/Cavity	235 kV/Cavity
Operating Peak Voltage	210 kV/Cavity	210 kV/Cavity
Accelerating Voltage Required: $V \sin \phi_s$	5.54 MV	2.66 MV
Total Voltage Available	8.9 MV	4.7 MV
Total Operating Voltage	7.8 MV	4.2 MV
Cavity Power Loss	45.11 kW/Cavity	45.11 kW/Cavity
Total Apparent Power	246.2 kVA/Cavity	240.5 kVA/Cavity
Robinson Stability Factor	4	4

Minimum bucket area after transition 1.8 eV-s

ACE – Main Injector Requirements

- Civil construction to add 17 Main Injector RF stations at MI-60
 - Additional chilled water capability
 - New electrical utilities
- Civil construction for three additional anode supplies
- Larger and improved cooling pond
- Removal of all NuMI items in the MI-60 tunnel straight section.
- 17 Main Injector cavities
- 34 200 kW power amplifiers
- 34 8 kW 53 MHz solid state amplifiers
- 17 dual series tube modulators
- 37 new bias supplies

ACE – Main Injector Requirements

- Four new MI Solid State Longitudinal Damper Amplifiers
- PiRM for each station (IRM replacement)
- All new cable pulled for the 17 new stations
- LLRF would need to be updated to ARRIA 10 FPGA

ACE – Main Injector Requirements



MI Bias Supply

50-year-old design and numerous parts are outdated.

ACE would need 37.



ACE – Main Injector Requirements



MI Anode Supplies


ACE would need an additional three.



ACE – Main Injector Requirements

17 Additional MI cavities

Arrangement between the quads in the tunnel.



ACE – Main Injector Requirements



MI-60 Electrical
Utilities

Additional 13.8 kV
utilities would need
to be added for the
anode supplies and
stations.



ACE – Main Injector Requirements



MI-60 cooling pond – larger and needs to be improved.

ACE – Summary

- We have the power to accelerate at 500 GeV/s.
- Will require an additional 17 MI RF stations to maintain the same bucket area.
- Civil construction for additional RF gallery, penetrations, anode supplies, and transformers will be needed.

Backup Slides

ACE – Initial M&S Cost Estimates


- Main Injector Bias Supply (41 @ \$220 k) \$9.02 M
- Main Injector Cavities (18 @ \$611 k) \$11 M
- Main Injector 200 kW Power Amplifiers (36 @ \$44.2 k) \$1.59 M
- CPI Eimac Y567B vacuum tube (72 @ \$27.76 k) \$2 M
- 8 kW 53 MHz Solid State Amplifier (56 @ \$186 k) \$10.42 M
- Dual Series Tube Modulator (18 @ \$142.9 k) \$2.57 M
- Solid State Amplifiers for Longitudinal Damper (4 @ \$324K) \$1.3 M
- LLRF update \$40k
- PiRM (45 @ \$2K) \$90k

ACE – Initial Labor Cost Estimates


• MI Cavites	161,500 hrs
• Station Racks	28,339 hrs
• MI Cavity Installation	11,340 hrs
• Anode Supplies	24,000 hrs
• Power Amplifier assembly	7,200 hrs
• Modulator assembly	31,720 hrs
• Bias Supply assembly	82,000 hrs
• LLRF	12,000 hrs
• 8 kW Solid State driver testing and installation	2,000 hrs
• NuMI Removal	4,000 hrs
• PiRM install	2,000 hrs
(1,768 hrs = 1 FTE)	Total of 366,099 hours = 207.1 FTE

ACE – Main Injector Enhancement – Beam Distribution

ACE Main Injector Beam Distribution



ACE – Main Injector Enhancement – 30 GeV Peak Current



ACE – Main Injector Enhancement – 30 GeV Robinson Stability

$\phi_s = 39.8701$ deg

Beam Current (I_p) = 2.11426 A

Number of Cavities = 36

R/Q = 104 Ω

Q = 4700

Cavity Voltage = 240. kV

Cavity Power Loss per Cavity = 58.9198×10^3 W

Total Apparent Power = 279.427×10^3 VA \angle 37.5416 degrees


Total Current = 2.32856 A \angle 37.5416 degrees

Percent of Induced Mode Compensated = 18.02 dB = 87.4397 %

Robinson Stable = 4.00762

ACE – Main Injector Enhancement – 30 GeV Vector Diagram

Robinson Stable = 4
 $x = 0.8743$



$$I_T = I_g + I_b$$


$$I_g = I_o + I_{acc} + I_{blc}$$

$$I_o = V_c / R$$


$$I_{acc} = I_b \sin(180 - \phi_s)$$

$$I_{blc} = j \times I_b \cos(180 - \phi_s)$$


ACE – Main Injector Enhancement – 30 GeV Vector Diagram




ACE – Main Injector Enhancement – Modulator




ACE – Main Injector Enhancement – Modulator



ACE – Main Injector Enhancement – Modulator



ACE – Main Injector Enhancement – BLC



Feedforward Beam Loading Compensation and Direct RF Feedback is used on each of the Main Injector stations to obtain a Robinson Stability factor of 4.