



HV system status, Module-3 run

Saba Parsa
University of Bern

HV system, Module-3




HV supply, Spellman



PFD-5



HV cable connection to the feedthrough



Overview of the HV system at Bern

HV ramp up

27-28 Jan cooldown and filling

28-31 Jan Subsystem bring up and optimization


1 Feb Ramp up of HV

Half nominal 8 kV @Cathode


8 hours of charge and light data

Nominal 15.1 kV @Cathode

Since 15:00 charge and light data




Spark signal observed by the light readout



Example of a spark event triggered by the light system


Spark signal

Single waveforms CH00



A healthy sum channel


Single waveforms CH05




Sum channel seeing sparks

Spark signal

ACL 4




ACL 7



Superimposed single waveforms from individual SiPMs subject to the spark

Sparks



Location of the ArCLights seeing sparks in Module3

Light Rate study

Raised HV to Nominal and observed 3.6 kHz trigger rate

Removed the sum signals of two ArCLights from the trigger OR

Reached stable trigger rate for Nominal field

14:00 Feb 1st 2023			
Spellmann setpo	Light trigger rate		
8	300 Hz		
16	2.5 kHz		
17	3.5 kHz		
17.9	3.6 kHz		
Ramp down to 8 kHz			
8	600 Hz		
Disabled trigger sum 4 and 6			
Sparks are localized at the cathode between two ArCLights			
Spellman [kV]	rate [Hz]		
8	300		
10	300		
12	300		
14	280		
16	270		
17.9	260		