



LBNF Beam in Phase II


John Back University of Warwick

on behalf of the DUNE collaboration

20-22 June 2023


Outline

- Accelerator Complex Evolution (ACE)
 - Upgrading proton beam power from 1.2 MW to > 2 MW
- Considerations for target & 3-horn focusing system
 - Design updates since TDR (2023 P5 assumes TDR design)
 - Physics impact of 1.2 MW design changes
 - Choices for > 1.2 MW running




Fermilab's ACE plan





LBNF beam scenarios




Beam Power Profile

Total Exposure

Courtesy Alexander Valishev (FNAL)

LBNF target & 3-horn system (1.2 MW design)



Horn A, B & C engineering design & construction by Fermilab


Graphite target design & construction by **RAL High Power Targets Group**: **Chris Densham (PI), Peter Loveridge (PM)**, Richard Cowan, Joe O'Dell, Michael Fitton, Eric Harvey-Fishenden, Andrew Lintern, Michael Parkin, Ben Suitters, Dan Wilcox

Target Conceptual Design Review (July 2019, FNAL)


| Courtesy RAL High Power Targets Group | Option 1:1x2m long | Option 2: 2x1m long | Option 3: intermediate cantilever |
|---|---|--|---|
| Instantaneous physics | Best instantaneous physics. | Needs an extra 19 days/yr to match option 1. | 1.5m needs an extra 19 days/yr (13 days/yr at 1.6m). |
| Engineering performance | High heat load. Unstable until supported. | High heat load but divided between 2 targets | Pushing at the limits on cantilever length. |
| Manufacturability | Difficult to make long tubes. DS support adds complexity. | 2 nd target low-mass manifold is complex. | Difficult to make long tubes. |
| Ease of remote maintenance | ≈3 weeks exchange time, DS support adds time and risk. | ≈2 weeks exchange time, 2 nd target adds some time and risk. | ≈1 week exchange time, lowest complexity and risk. |
| Cost and schedule impacts | DS support somewhat increases cost and time. | 2 nd target greatly increases cost and time. | Cheapest and fastest to produce. |

Target performance = physics x reliability \Rightarrow Consensus for option 3: cantilever with L = 1.5 m (minimum) up to 1.8 m (aspiration) 6

Cantilevered graphite target inside horn A (1.2 MW)





Horn B (& C) Modifications (1.2 MW) Courtesy Cory Crowley




Similar for Horn C, $L_c = 2.2m$ (essentially a mirror image)

Signal v flux changes since DUNE TDR (1.2 MW) IPAC'21, WEPAB212






CP sensitivity vs exposure



Since TDR: target length reduction 2.2 m (4.6 λ) to 1.5 - 1.8 m (3.1 - 3.8 λ) and reduced horn B & C outer conductor r = 63 to 60 cm \Rightarrow more exposure needed


Using GLoBES approximation of DUNE long-baseline analysis

CP sensitivity vs run time, 50% δ_{CP}



Assuming 57% run efficiency (208 run days per calendar year) Using GLoBES approximation of DUNE long-baseline analysis


CP sensitivity vs run time, 75% δ_{CP}



Assuming 57% run efficiency (208 run days per calendar year) Using GLoBES approximation of DUNE long-baseline analysis

Staged targetry upgrade path

Courtesy Patrick Hurh (FNAL)




Stage 1: Push and validate 1.2 MW target (RAL deliverable) up to 1.5 MW May need target & horn design changes for 1.5 MW, could reduce v flux/POT

Stage **2**: Design & build 2nd generation components, raising limits up to **1.8 MW**

Stage 3: Design & build next generation systems to take full advantage of 2.4 MW

LBNF target system readiness for 2.4 MW **Control**


Courtesy Patrick Hurh (FNAL)



Target reliability: thermal shock & radiation damage

Courtesy Patrick Hurh (FNAL)

Graphite Neutrino Targets Exploratory Map




Radiation Damage Severity (damage equivalent fluence, p/cm²)

Can cantilevered graphite target operate & survive at 2.4 MW?

Target He gas cooling considerations








2.4 MW: increase cooling by x2, raise system pressure to ~8 bar, mass flow to 80g/s

Titanium outer container needs thicker walls? Container thickness for 1.2 MW = 1 mm

Needs to satisfy Fermilab Environmental Safety & Health Manual (US DOE) requirements: American Society of Mechanical Engineers (ASME) Boiler & Pressure Vessel Code


Extra run days per year (1.2 MW) vs outer container thickness t_{oc}



Target thermal stress & horn pulse vibrations



Courtesy Peter Loveridge & Dan Wilcox (RAL)




Driving Frequency (Hz)

Should be effective for 2.4 MW (to be confirmed): same horn pulse current **I** = **300 kA** 18

Radiation damage: graphite & Ti fatigue





Need more irradiation DPA data: ongoing work of **RaDIATE** collaboration

Summary

- ACE beam scenario for $\geq 2 \text{ MW}$
 - Significantly reduces required run years for DUNE physics goals
 - Aiming to improve run-year efficiency beyond 57% (208 days/calendar yr)
- 1.2 MW target & horn focusing system updates since DUNE TDR
 - Target L = 1.5 m (& 1.8 m) reduced from 2.2 m (TDR & 2023 P5)
 - Horn B & C outer conductor radii reduced to fit inside target hall
 - Increases required runtime by ~1 to 2 years for 5 σ (3 σ) CP sensitivities for 50% (75%) δ_{CP}
- RAL High Power Targets group
 - Delivering 1^{st} production graphite target $L_{min} = 1.5$ m for 1.2 MW
 - Understand requests from ACE plan for higher beam power
 - Keeping path open to push target operation beyond 1.2 MW
 - Challenging to get pressure vessel safety code (welding) compliance: in progress for 1.2 MW
- Target & horn design changes needed for > 1.2 MW, will impact v flux/POT
 - Significantly more R&D required
 - Beam power compromises: target lifetime (& safety) vs physics goals

Backup

PIP-II & LBNF timeline

Courtesy Alexander Valishev (FNAL)

| May-22 | | FY2026 FY2027 | | FY2028 FY2029 | | FY2030 | | FY2031 | | | FY2032 | | | | | |
|------------------------|---|---------------------------|-------|-----------------|-------|------------------------|-------|---------------------------|-------|-------------------------|--------|-------|----------------------|------|-------|-----|
| | | Q2 Q3 Q4 | Q1 Q2 | 2 Q3 Q4 | Q1 Q2 | Q3 Q4 | Q1 Q2 | 2 Q3 Q4 | Q1 Q2 | 2 Q3 Q4 | 4Q10 | Q2 Q3 | Q4Q | 1 Q2 | Q3 Q | 4Q1 |
| Project/Division | Category | CY2026 Q1 Q2 Q3 | | CY2027 Q2 Q3 | | CY2028 Q2 Q3 | | CY202 9 1 Q2 Q3 | | CY203 1 Q2 Q3 | | | 2 031 Q3 Q | | CY203 | |
| Accelerator Complex | SY120 - SpinQUEST NOvA SBN ICARUS Mu2e | | 0000 | | | | | | | | | | | | | |
| PIP-II | Early CD4 Booster Shutdown START Booster Shutdown END Linac Complex construction Booster Connection CF Ph1 (12m) Booster Connection CF Ph2 (6m) Booster beam line connection WFE and Linac commissioning BTL Commissioning Booster commissioning | | | | | | | | | | | | | | | |
| LBNF/DUNE | MI Shutdown START MI Shutdown END Beamline beam checkout END NSCF Construction other than Extraction Beamline Installation other than Extraction Extraction Enclosure Construction Extraction Enclosure Installation | | | | | | | | | | | | • | | | |