

SURF Installation, CRP Factory, Cost and Schedule

Cheng-Ju Lin

Lawrence Berkeley National Lab

FD2 BDE Final Design Review

16 May 2023




FD2 BDE Installation

- A significant fraction of the BDE installation is done ahead time at the CRP Factories (Yale U. and U. of Chicago)
- BDE provides FEMBs, patch panels, short signal and power cables (connection from FEMB to the patch panels)
- BDE also provides the QC test-stand for testing the FEMBs after they installed on the FEMBs
- Full assembled CRU (half CRP) will be tested in LN2 at the CRP Factories
- Installation of the FEMBs and QC at the CRP Factories will be done by the CRP Consortium with technical support from BDE
- CRP Consortium is also responsible for the transportation of the CRUs from the factories to SURF
- Prior to installation in FD2, all CRPs will be tested again by BDE crew in the underground clean room (warm test only)

Bottom CRP Factories

FD2 CRP FDR <https://indico.fnal.gov/event/58650/>

Concept of bottom CRP factory site



CRP4 was assembled and tested at the Yale CRP Factory

SURF Installation

FDC Integration & Installation FDR <https://indico.fnal.gov/event/59023/>


- Target to have all BDE components arrive at SURF warehouse at least 6 months before the start of the installation
- BDE SURF installation has four main steps:
 - 1) Installation of the power supplies and safety interlock system in the rack on the detector mezzanine
 - 2) When the top of the FD2 cryostat is available for installation, install the penetration and warm electronics crates and boards
 - 3) When inside the cryostat is available, install the cable tray along with the long 27 m cables. Connect cables to the WIECs and test with FEMBs (on a cart). Cables are then temporarily stored under the false floor
 - 4) When CRPs are moved inside the cryostat, connect the long cables to the patch panels and perform QC test

- Detailed installation schedule and labor estimates are available in https://edms.cern.ch/document/2523457/LAST_RELEASED
- Division of responsibility between I&I and BDE, CRP and BDE, PDS and BDE are defined in the interface documents
- 1 working week is 6 days with 2 shifts per day


Summary		2027												2028																																									
WBS/Activity	Activity Description	SrT	I&I	SrMT	Tech	40		41		42		43		44		45		46		49		50		51																															
						Weld	MT	Hours	Hours	Weld	MT	Hours	Hours	Weld	MT	Hours	Hours	Weld	MT	Hours	Hours	Weld	MT	Hours	Hours	Weld	MT	Hours	Hours																										
						171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216				
						2	2	2	2	2	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
						13.5	25.5	23.8	26	14.5	44.3	44.8	38.5	22.9	25.3	22	30	24.5	28	27	20.8	19	7	6	4	11.3	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	
05.04.03	Detector R2 Installation					8820																																																	
05.04.03.02	FD2CleanCryostat,InstallFloorandCables,PDMembrane					980	6346																																																
	MT- Total FTE hours					6,346																																																	
	SrMT- Total FTE hours					980																																																	
	B_Elec Consortia- Total FTE hours					2,600																																																	
	PD Consortia- Total FTE hours					3,480																																																	
	Calci Consortia- Total FTE hours					320																																																	
	Step 1: Membrane Photon and Bottom Drift Electronics cables					420	900	830	840	420	860	860	860	290	66																																								
	Step 2: Top Charge Readout Planes (CRP) and Cathode					60	220	110	120	60	120	120	120	30	20																																								
	Step 3: Field Cage					80	40	120	120	120	410	270	360	420	480	460	360	360	300	0	160	60																																	
	Step 4: Bottom CRP					120	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240	240		
	Step 5: Close TCO					200	480	650	630	630	630	630	630	630	630	230																																							
	Final Installation, Close TCO, Prep for Filling					2,360																																																	
	MT- Total FTE hours					2,360																																																	
	SrMT- Total FTE hours					2,040																																																	
	B_Elec Consortia- Total FTE per shifts					1,280																																																	
	PD Consortia- Total FTE hours					1,040																																																	
	CRP Consortia- Total FTE hours					1,040																																																	
	HV Consortia- Total FTE hours					1,040																																																	
	TDE Consortia- Total FTE hours					2,400																																																	
	Calci Consortia- Total FTE hours					2,080																																																	

Cryostat Roof Installation


- 4 weeks are planned for the power supply and safety interlock installation in the detector racks
- 8 weeks are planned for the penetration and warm electronics installation



Bottom CRP Installation Inside Cryostat



CRP elevated on a supporting truss for long cable connection to the patch panels



Many aspects of the BDE SURF installation are exercised at CERN module-0

FD2 BDE Production/Procurements

Quantity listed does not include the typical 10% spare

- ASICs (see ASICs PRRs)
- 1920 x FEMBs
- 1920 x Cold cables (27 m): Samtec signal/clck, LV power cables, HV bias
- 1920 (2.5 m) x cold cables: miniSAS and LV power cables
- 320 x patch panels
- 40 x cryostat penetration assembly and cable strain relief
- 80 x Warm Interface Electronics Crates and mounting hardware
- 530 x Warm Interface Boards
- 80 x Power & Timing Cards
- DAQ fibers and ethernet cables
- 16 x PL506 LV power supplies and 80 LV warm power cables
- Beckhoff safety interlock system
- + many other smaller items (e.g. screws, gaskets, tools) that are needed for the production and installation

Procurement Strategy

- FD2 procurement largely follows the same strategy as FD1 procurement. Using the same vendor, etc.
- Due to resource constraints (both funding and people), most FD2 production/procurements start after the completion of the corresponding FD1 production. This logic relation is built into the P6 schedule
- For large procurements (e.g. cold cables, power supplies, etc.), plan to combine FD1 and FD2 into a single contract with firm order for FD1 and option to buy FD2 when FD2 funds are available
- Starting the procurement process >1 year before when we need to send out the POs
- Already having discussions with various procurement offices to start the process. Many items will need to go out for bids

Summary of FD2 BDE Production and Installation Schedule

(Taken from P6 Schedule as of May 2023)

- Start fabrication of FEMB PCBs (Aug 2025)
- Start fabrication of cryostat penetration (Oct 2025)
- Start production of WIB (Jan 2026)
- Start production of PTC (Jan 2026)
- Start production of WIEC (Jan 2026)
- Purchase low voltage power supplies (Jan 2026)
- Start production of cold cables (Mar 2026)


- Start installation of low voltage power supplies (May 2027)
- Start installation of CE safety interlock (May 2027)
- Start installation of penetration and warm electronics (Sep 2027)
- Start installation of cold cables inside cryostat (Jan 2028)
- Start installation of cold cables on CRP (Apr 2028)

BDE Cost Summary


Cost summary from CD-1RR (Jul 2022). Updated cost (for CD-2/3) is about 15% higher mostly due to higher costs of components

WBS 4	WBS 5	Actuals thru Mar-22	Budget-at-completion (BAC)	Estimate-to-completion (ETC)	Contingency (EUC)	Contingency% on ETC	ETC + EUC	WBS Total Cost
131.FDC.03.05 FD2 Bottom Drift Electronics (BDE)	FD2 Bottom Drift Electronics (BDE)	\$.3 M						
	Electronics bottom Management		\$3.3 M	\$3.2 M	\$.1 M	4%	\$3.3 M	
	ASICs		\$.6 M	\$.6 M	\$.1 M	20%	\$.7 M	
	FEMBs		\$1.6 M	\$1.6 M	\$.3 M	20%	\$1.9 M	
	Cold Cables		\$4.9 M	\$4.9 M	\$1.0 M	21%	\$5.9 M	
	Cryostat Penetrations		\$1.0 M	\$1.0 M	\$.5 M	50%	\$1.6 M	
	Warm-Interface Electronics Crates and Boards		\$3.5 M	\$3.5 M	\$1.4 M	40%	\$5.0 M	
	Power Supplies, Warm Cables, and Services to DAQ Racks		\$.7 M	\$.7 M	\$.2 M	36%	\$.9 M	
	Test Stands and Prototyping Supports		\$1.5 M	\$1.5 M	\$.6 M	42%	\$2.1 M	
	Installation at SURF for FD2		\$1.8 M	\$1.8 M	\$.9 M	50%	\$2.6 M	
	Total	\$.3 M	\$18.9 M	\$18.7 M	\$5.3 M	28%	\$24.0 M	\$24.2 M


Budget at Completion Labor vs. M&S



Labor at LBNL, SLAC, and Universities, \$2.9 M, 15%



ETC by Contingency Rule



MOU

- Institutional responsibilities for fabrication, QC testing, and installation are similar to FD1
- See <https://edms.cern.ch/document/2708334/> for the complete list

Subsystem	Description	Quantity (FD1)	Contributing Institutions	
LArASIC	FE amplifier, design and procurement	24,320	BNL	
LArASIC testing	QC process		BNL, Michigan State University, Stony Brook University, Iowa State University	
ColdADC	Digitizer ASIC, design and procurement	24,320	BNL, Fermilab, LBNL	
ColdADC testing	QC process		LBNL, Louisiana State University, Iowa State University, University of California Irvine	
COLDATA	Serializer ASIC, design and procurement	6,480	BNL, Fermilab	
COLDATA testing	QC process		Fermilab, University of California Irvine, Iowa State University	
FEMB	Front-End Motherboard, design and procurement	3,040	BNL	
FEMB testing	QC process		BNL, University of Florida, University of Cincinnati,	
			Fermilab, Stony Brook University, plus one additional institution (TBA)	
	FEMB mechanical supports	3,040	Colorado State University	
	Cold Signal Cables	3,040	BNL	
	Cold Low Voltage Power Cables	3,040	BNL	
	Cold Bias Voltage Cables	658	BNL	
	Cable Trays Systems inside the Cryostat	75	BNL	
	Temporary Cable Trays for Installation	10	BNL	
	Cryostat Penetrations, including Cross Shaped Spool Pieces, Crossing Tubes	75	BNL	
	CE flanges	150	BNL	
	Warm Interface Electronics Crates	150	BNL	
	Warm Interface Boards	750	BNL, University of Pennsylvania	
	Firmware and Software for the WIBs		University of Florida, University of Pennsylvania, BNL	
	Power and Timing Cards	150	University of Pennsylvania	
	Firmware and Software for the PTCs		University of Pennsylvania, University of Florida	
	Interface to the DUNE Detector Safety System	31 panels, includes hardware interlocks, power supplies for heaters and fans	Fermilab	
	Low voltage power supplies	25 modules	Fermilab	
	Bias voltage supplies	5 racks, with 45 HV modules, 45 fanout panels	Fermilab	
	Low voltage warm cables	25	Fermilab	
	Bias voltage warm cables	658	Fermilab	
	Readout fiber patch cords	150	Fermilab	
	Slow control patch cords	150	Fermilab	
	Clock distribution fibers	150	Fermilab	
	Integration test at BNL with the 40% APA prototype	<10 combinations of different FEMBs and WIBs	BNL	
	Integration tests at ICEBERG	<10 combinations of different FEMBs and WIBs	BNL, Fermilab, LBNL	
	Integration tests at NP04	1-2 tests	BNL, Fermilab, LBNL	
	Support for APA integration tests at CERN	System tests of final APA and FEMBs in the cold box of NP04	Up to 20 APAs	BNL, LBNL, Fermilab,
	Installation and Commissioning of ProtoDUNE-2	Integration of the FEMBs on the four APA, cold box testing, installation of the APAs inside the cryostat, cabling, and commissioning	4 APAs	BNL, Fermilab, LBNL, Louisiana State University
	ProtoDUNE-2 Operations	Maintenance of TPC electronics during operations	2 years of data taking	BNL, Fermilab, LBNL, Louisiana State University
	Installation of Detector Components on top of the Cryostat	Install cryostat penetrations, warm interface crates complete with WIBs and PTCs, all power and bias voltage supplies, connections; initial testing	75 cryostat penetrations and 150 warm interface crates with all the services	All institutions from the TPC Electronics consortium
	Integration of FEMBs on APAs and QC tests	Integrate FEMBs on APAs and perform tests in the cold boxes	3,000 FEMBs on 150 APAs	All institutions from the TPC Electronics consortium
	APA QC Tests during Installation	Final readout test of the FEMBs through the DUNE DAQ after installation of the APAs in the cryostat	150 APAs	All institutions from the TPC Electronics consortium

FD2 BDE Risk Registry

- Four BDE risks in the registry
- Mostly to cover personnel shortage concerns

RI-ID ▾	Title ↑ ▾	Probability ▾	Cost Impact ▾	Schedule Impact ▾
RT-131-FDC-FD2-022	[FD2] ASICs storage surcharge	30 %	70 k\$	0 months
RT-131-FDC-FD2-071	[FD2-BDE] FD2 CE damage to the FEMBs / cold cables during or after CRP installation at SURF	5 %	25 -- 70 k\$	0.25 -- 1 months
RT-131-FDC-FD2-019	[FD2-BDE] insufficient personnel for QC of cold electronic components during production	30 %	25 -- 50 -- 75 k\$	1 -- 2 -- 3 months
RT-131-FDC-FD2-007	[FD2-BDE] Insufficient un-costed labor at SURF for installation	30 %	97 -- 194 -- 292 k\$	0 months

- In addition, there are a number of risks for FD1 TPC electronics that are relevant for FD2 (e.g. single source vendor). Those risks are not included separately in FD2 to avoid double counting risks

Thank You !