

# Recommissioning MINERvA for 2x2




Jack Smedley  
ND-LAr Consortium Meeting  
Thursday, March 16, 2023




# MINER $\nu$ A 101

- A module has one or two planes of scintillator strips,  $\pm 60^\circ$ (U,V) and vertical (X)
- Read out in sets of four modules by daisy chains of PMTs
- Most of the detector is active tracker module sets
  - (UX, VX, UX, VX) configuration, 19 PMTs
- Downstream of the tracker region are ECAL sets, which have a thin layer of lead between modules
  - (PbUX, PbVX, PbUX, PbVX), 19 PMTs
- Most downstream is HCAL, with only one instrumented plane per module and iron between
  - (FeX, FeU, FeX, FeV), 11 PMTs



## 2x2 MINERvA


- ~40% of MINERvA is being repurposed for 2x2
- 12 tracker modules upstream of the cryostat for tagging rock muons
- 32 modules downstream for uncontained tracks
  - 8 tracker
  - 12 ECAL
  - 12 HCAL
- Original hardware was used wherever possible, and replacements are thoroughly documented



## 2x2 MINERvA

Photo taken during installation of final module set

- ~40% of MINERvA is being repurposed for 2x2
- 12 tracker modules upstream of the cryostat for tagging rock muons
- 32 modules downstream for uncontained tracks
  - 8 tracker
  - 12 ECAL
  - 12 HCAL
- Original hardware was used wherever possible, and replacements are thoroughly documented



# 2x2 MINERvA $\neq$ Original MINERvA

Hardware is matched to original electronics address, NOT to original module set! For example, the PMTs and FEBs on 2x2 MS11 are from MINERvA MS11, but the planes are from MINERvA MS26.

2x2 MS#	1	2	3	4	5	6	7	8	9	10	11
MINERvA MS#	5	6	7	8	9	20	21	22	23	25	26
Type	AT	AT	AT	AT	AT	AT/ECAL	ECAL	ECAL	HCAL	HCAL	HCAL

Upstream

Downstream



# Key Dates from the Installation

**June 6**

Passed ORC,  
installation begins in  
earnest



Smedley



UNIVERSITY of  
ROCHESTER



# Key Dates from the Installation

**June 6**

Passed ORC,  
installation begins in  
earnest

**October 26**

Downstream MINERvA  
completed



Smedley



# Key Dates from the Installation

**June 6**

Passed ORC,  
installation begins in  
earnest

**October 26**

Downstream MINERvA  
completed

**December 20**

Upstream MINERvA  
completed

**Now**


Commissioning phase



Smedley



UNIVERSITY OF CHICAGO





# Key Dates from the Installation

**June 6**

Passed ORC,  
installation begins in  
earnest

**October 26**

Downstream MINERvA  
completed

**December 20**

Upstream MINERvA  
completed

**Now**

Commissioning phase


NuMI Beam




Smedley





UNIVERSITY OF CHICAGO



# What do we need beam for?



- Without beam
  - Check PMT pedestals and light tightness
  - LED light injection into PMT
  - Monitor PMT HV stability
- With beam
  - Check optical connections between module and PMT
  - Calibration, calibration, calibration!



# Calibration Tasks

- MINERvA regularly performed a variety of calibrations
- Most can be reused or feasibly reperformed, with some geometry stitching

- What sort of work is required
  - Plex (matching old files to new geometry)
  - Pedestals (rewriting production code, implementing existing calibration code, uploading regularly to DB)
  - FEB correction (matching old files to new geometry)
  - Attenuation (matching old files to new geometry)
  - Alignment (rewriting rock muon production, implementing existing calibration code)
  - Strip to strip (implementing existing calibration code, uploading to DB)
  - Absolute energy (implementing existing calibration code or writing something simpler, uploading to DB)
  - Timing (implementing existing calibration code, uploading to DB)
  - Cross talk (matching old files to new geometry)

[See C. Marshall's talk from the 2x2 Analysis Workshop](#)

# Current Status: Plex

- The plex is a set of XML files that map electronics address (CROC, chain, board, pixel) to the physical detector (module, plane, strip)
- Used in calibration, reconstruction, basically everything. From Chris's talk, "Absolutely required for 2x2 for any tracking in MINERvA"
- Under development by Carlos Pernas, a graduate student at William & Mary
- Largely in working order, reviving an ancient no-reconstruction event display to check the fine details before we forge ahead





# Other Ongoing Work

- Improving DAQ stability
  - Several different DAQ bugs have plagued us through the installation, preventing us from running in the nearly-continuous state MINERvA did
  - I've been doing some archaeology to better understand the DAQ code and find the source(s) of crashes
- Resurrecting MINERvA nearline monitoring
  - During operation, MINERvA automatically generated real time data quality plots, available for shifters by webpage
  - Bringing this back requires understanding and adapting some old GAUDI code
  - Alysia Marino is trying to bring this back in a “lite” version

# BACKUP

# More Detector Hall Models



# MINER $\nu$ A Racks

