

Project X Collaboration meeting, November 27-28, 2012 FNAL

HWR Cryomodule Development

P.N. Ostroumov, Z.A. Conway, M.P. Kelly

Physics Division


November 28, 2012

Content

- SRF technology at ANL
- Status of current and future work on HWR cryomodule
- HWR development and fabrication
- RF coupler
- BPM
- SC solenoid
- Cryomodule vacuum vessel
 - Mechanical design
 - Engineering analysis
- Near future work

SRF Technology for PXIE HWR

- Recent progress at ANL with 72 MHz QWRs and cryomodule
- 2K testing: at 80 mT, $V_0=3.6$ MV, residual resistance is just ~ 2 n Ω
- Very low X-ray radiation below 80-100 mT
- Several cavities exceed the best ILC cavity performance in E_{PEAK}
- State-of-the-art design and fabrication technology is demonstrated



Gaining Experience with ATLAS Cryomodule Assembly

- Clean-room assembly of all components
- Fitting of vacuum, helium manifolds
- Alignment of cavities and solenoids - ± 0.25 mm is achievable
- Alignment of the strongback – shrinkage is as expected in all directions
- Engineering cold test of the cryostat at LN temperature
- Measurements of heat load to LN - 160 W




Activities Since April-12 Collaboration Meeting

- Mechanical design and engineering analysis of the HWRs are complete
- Pressure vessel safety analysis passed joint ANL-FNAL safety review and safety analysis documentation are complete
- Niobium parts for 2 HWRs are being fabricated
 - One cavity is being built with Wah Chang Nb, another one - with CABOT Nb
 - Fixturing for wire EDM and EBW is being fabricated
- SC solenoid includes return coil and 4 dipole coils
 - Prototype solenoid has been built at Cryomagnetics and jacketed at Meyer Tool
 - Will have ASME pressure vessel stamp
- High-power, 10-kW, RF coupler
 - Ready for cold testing in January-February 2013
- Beam Position Monitor
 - All components are finished, being welded and will be ready for cold testing in January-February 2013
- Cryomodule design is nearly complete
 - Vacuum vessel safety review is expected in March 2013


PXIE HWR - df/dP and Safety Analysis



Nb Cavity Stress Red > 5.5 ksi



Prototype Cavities
 $df/dP = + 5.4 \text{ kHz/atm}$




S.S. Helium Jacket
Stress; Red > 30.0 ksi



- Half-wave resonator design used for safety analysis – passed.
- Results shown here reflect the properties of the prototype resonator being fabricated.
- Results are excellent for RF amplitude/phase stabilization and will be confirmed with the prototype.

PXIE HWR - Slow Tuning

Cavity With Slow Tuner



S.S. Helium Jacket
Stress; Red > 20.0 ksi
Max = 35 ksi



- 310 kHz tuning range with 2,250 lb (10 kN) applied slow tuner with current models
- Figures shown use room temperature (RT) properties of cavity. At R.T. cannot use full slow-tuner stroke.


PXIE HWR - Fabrication Status Overview

Major cavity parts status:

- Reentrant nose and doubler plates – received.
- Toroids – To be delivered first week of December.
- Center conductors – @ ANL.
- Outer conductors – waiting on Al for forming die to arrive.


Two sets of parts are being formed to make two prototypes.

- One from ATI Wah Chang material.
- One from Cabot Supermetals material.
- Some Nb rod from Tokyo Denkai is being used.




Fixturing for Wire EDM and EBW is Being Built


- EDM trimming of the CC




Trimming of the CC length



- EDM trim of the OC-halves length



OC length



HWR Prototype - Reentrant Nose Assemblies


STEP 1: Cleaned & Inspected



STEP 2: Etched & Assembled in Clean Room



STEP 3: Electron Beam Welding



STEP 4: Cleaned & Inspected Again



P.N. Ostroumov, Z.A. Conway and M.P. Kelly "HWR Cryomodule Development meeting"

Project X Collaboration

November 28, 2012

HWR Prototype - Toroids



Toroid, inner conductor trimmed.

Branch pull hardware.

Finished toroids. Two more to go.
@ANL on Nov. 29.



HWR Prototype - Center Conductors



Center Conductor Pre-Forming




Center Conductor Post-Forming

Center Conductors Arrived
at ANL on Tuesday, Nov. 27.




Center Conductors Ready For EDM

RF Coupler ANSYS Mechanical and EM Model



<http://iopscience.iop.org/1748-0221/7/11/P11004>


0.006" Stainless bellows with 0.0007" (20 microns of copper)



RF Coupler

- A 15 kW RF-coupler appropriate 162 MHz cavities has been modeled
 - Reflections are low \sim -30 dB
 - No significant heating in bellows, ceramic, or center conductor
 - Heat flow to the liquid helium is calculated <100 mW
 - Any coupler multipacting could be mitigated by center conductor bias

ANSYS Temperature Map: 15 kW full reflection (overcoupled)



Software	ANSYS	CST
Frequency, MHz	162.5	
Input power, kW	15	
Total heat flow to 2K, W	0.078	0.165
Total heat flow to 5K, W	2.34	2.49
Total heat flow to 60K, W	11.2	11.8

Prototyping of the RF coupler

- A fabrication issue with adhesion of the 2" ceramic window has been resolved (controlled & slow furnace cool down to reduce stresses)
- Bellows plating completed in July 2012
- High power testing in January 2012 when cavity/rf amplifier are available



MYAT 2" to 1-5/8" adapter

20 microns of copper plating on a 150 micron thick stainless steel bellows

Cold window assembly



Cold window plus bellows assembly

SC Solenoid for PXIE HWR Cryomodule:

Magnet Specifications


Wire	Niobium-Titanium
Operating temperature	1.8-4.6 K
Magnetic field integral	$\int Bzdz = 0.75 \text{ T-m}$
Operating current	82 A
Inductance	1.1 H
Shielding	$B < 100 \text{ G}$: $z \geq 15 \text{ cm}$
Steering coils	0.2 T, 30 T-mm
Bore diameter	35 mm

Cryomagnetics 0.75 T-m SC solenoid




- Bare magnetic 'dunk test' in 4 K dewar at Cryomagnetics, Inc. in October 2012
- Main coil current tested up to 87.25 A (5 A above nominal)
- X,Y steering coil current tested up to 40 A
- All three coils successfully re-charged after an induced quench

Code-stamped Liquid Helium Jacket at Meyer Tool, November 2012




Cryomodule - Conductively Cooled Leads



- High-temperature conduction cooled leads have been ordered from HTS-110.
- The first pair to be delivered in January 2013 for testing.


Cryomodule BPM Fabrication Status




- BPM part machining is complete. Parts to be delivered to ANL between Nov 27-29.
- Next steps:
 - Clean & Inspect.
 - Send BPM body and SMA feedthroughs out for laser welding.
 - Electron beam weld the electrodes to SMA feedthrough center conductors.
 - Offline testing.
 - Online testing.

PXIE HWR Cryomodule

Parameter	Value
Length (gate-valve-to-gate-valve)	5.9 m
Length (overall)	6.3 m
Width	1.9 m
Height	2.0 m



PXIE HWR Cryomodule



- Cryomodule status update.
 - Design status.
 - BPM – parts made need to weld.
 - Conduction Cooled Leads – On order
- Half-Wave Resonator.
 - Due to time constraints discussing cavity RF design only.
 - df/dP .
 - Slow tuning.
 - Prototyping status.

PXIE Cryogenic Loads

- Dynamic Load: 6 nΩ cavity residual resistance.
- Other loads, e.g., radiative heating, come from Functional Requirements Specifications.

Changing Operating Voltage

Parameter	Components	+20%	Design	-20%
Operating Set Point (MV)	Cavities # 1 & # 2	1.2	1.0	0.8
	Cavities # 3 - # 8	2.0	1.7	1.4
2 K Dynamic Heat Load (W)	Cavities # 1 & # 2	1.5	1.1	0.7
	Cavities # 3 - # 8	12.5	8.7	5.7
Total 2 K Load	Everything	29	24	21



Estimates vs. Functional Requirements

Load	Total	FNAL FRS	Constraint	FRS Convention
2 K	24 W	25 W	70 -2 K Radiation	0.1 W/m ²
5 K	60 W	80 W	70 – 5 K Radiation	0.1 W/m ²
70 K	250 W	250 W	293 – 70 K Radiation	1.5 W/m ²

Strongback Hanger Thermal Analysis




- Improved hanger design based upon ATLAS upgrade experience.
- Using Grade 5 Titanium, Ti-6Al-4V.
- Structural loads have a factor of safety of 10.
- Low thermal conductivity and contraction.
- The modeling does not include the thermal contact impedance.



Thermal Transition	Heat Leak (ANSYS Simulated)
2 – 80 K	0.050 W
80 – 293 K	0.714 W




Strongback Structural Analysis




Strongback Deflections (w/ load)

- Min. = .0135 mm (red)
- Max. = .0867 mm (blue)
- Range = .0731 mm
- Std Dev. = .0270 mm



Alignment Target = ± 0.250 mm

Cryomodule Safety Analysis



Limit Load Results


- Top left, summed deflection.
- Bottom left, solver output. Results
- Converged.

Deflection Plots for 1 atm.

- Contours = blue <.11",
- .11" < green <.19", red > .25"

Results

- Maximum wall deflection = .248"
- Passes buckling and ratcheting analyses too.
- No show stoppers but still need to evaluate final design




Future Work

- The goal is to complete 2 HWRs by 4QFY13 and provide cold testing by the end of Q1FY2014
- Cold testing of the RF coupler up to 10 kW, SC solenoid and BPM in January-February 2013
- Due to funding constrains in FY13 we can not proceed with
 - Fabrication of Nb parts for production cavities, 7 HWRs
 - This work can be started immediately if funding is available
 - Procurement and fabrication of the cryostat vacuum vessel and other components of the cryomodule (strongback, magnetic and thermal shield, JT exchanger, gate valves, vacuum, helium manifolds,...)
 - This work can be started in April 2013
 - Purchase and fabrication of all SC solenoids, RF couplers, BPMs
 - This work can be started immediately if funding is available

PXIE Solenoid and Coupler 4 Kelvin Cold Testing

January 2013

- Planned testing with existing 72 MHz cavity and cryostat
- Coupler testing at 162 MHz at 10 kW in full reflection
 - 4 K at cavity flange
 - 80 K at cold window
 - Thermometry and calibration heaters at 4 K and 80 K
- Solenoid testing with main coil to 80 Amps
 - Lake Shore magnetic field probes to measure stray field and magnetization




Milestones


#	Milestone	Date
1	Place contract for niobium dies and forming of the prototype cavity	Q2FY12
2	Conceptual and Preliminary Design complete Niobium for production cavities is delivered and inspected	Q4FY12
3	Complete fabrication of prototypes of (a) 10-kW RF coupler; (b) SC solenoid; (c) BPM	Q1FY13
4	Complete fabrication drawings of the cryostat vessel including thermal and magnetic shields. Design review of the cryomodule. Cold testing of the RF coupler, SC solenoid and BPM.	Q2FY13
5	Fabrication of two prototype cavities complete	Q4FY13
6	Two prototype cavities tested. Start procurement of production cavities, its sub-systems and cryostat vessel if funding is available.	Q1FY14
7	Fabrication of the cryostat vessel complete	Q1FY15
8	Fabrication of production cavities and its sub-systems complete	Q2FY15
9	RF surface processing of HWRs. Cold testing of 50% of HWRs. Engineering cold testing of the cryostat vessel.	Q4FY15
10	Mock-up cavity string assembly	Q2FY16
11	Cryomodule off-line testing complete	Q4FY16
12	Cryomodule installed at PXIE beamline	Q2FY17

Backup Slides

CST Simulations: Multipacting Suppression using a DC bias voltage



The sapphire disk width should be 0.01 – 0.015” to make very small, $S_{11} \sim -30$ dB




Prototyping Critical Components: Cold RF Window

Half Section

Connection to bellows

LN2 or cold He gas 70-80 Kelvin


Connection to thermal transition



Status: Prior to final brazing at MPF; July 18, 2012

LN2 heat of vaporization	196 J/g
Typical flow	3 gm/s
Max. cooling capacity	588 Watts
Max. static+dynamic loss	20.9 Watts

PXIE HWR Cryomodule



PXIE Cryomodule 2 K Heat Load (24 W Total, 10 W Static)

Helium Manifold
20%

70 to 2 K Radiation
12%

BCS Resistance	Residual Resistance
0.2 nΩ	6 nΩ

High Current Leads
10%

2 K Load = 31 W if
 $R_{res} = 10 \text{ n}\Omega$

Instrumentation
8%

Strong Back Hangers
1%

Cooldown Lines
2%

Vacuum Manifold
2%

Gate Valves
1%

Slow Tuners
2%

Couplers (Static)
1%

Cavities 3 - 8
36%

Cavities 1 & 2
4%

PXIE Cryomodule 5 K Load

- 5 K Thermal intercepts on the:

- Beam Line Gate Valves.
- Slow Tuner Lines.
- Solenoid Leads.
- Helium System Cryogenic Penetrations.
- Couplers.
- Cryogenic Valves.

- No 5 K Thermal Intercepts on the:

- Strong-Back Hangers.
- Cool-Down Lines.
- Vacuum Manifold.
- Slow Tuner Gas Lines.

PXIE Cryomodule 5 K Heat Leak (60 W Total)

