KLOE to SAND Progress Report

Antonio Di Domenico Dipartimento di Fisica, Sapienza Università di Roma and INFN-Roma, Italy



on behalf of the SAND-ECAL and SAND-Magnet WGs



DUNE Collaboration Meeting – CERN – 23 January 2024



The SAND-ECAL working group



- Activities related to the extraction of the electromagnetic calorimeter (ECAL) from KLOE detector, ECAL refurbishment, transportation to FNAL, installation and commissioning at the DUNE ND cavern.
- In general, the activities at LNF of the whole KLOE-to-SAND project are followed and discussed inside the ECAL WG, including the SAND/MAGNET WG activities due to the high correlation of operation and planning of the two WGs.
- WG chairs: A. Di Domenico, D. Domenici
- Dedicated mailing list <u>DUNE-ND-SAND-ECAL@LISTSERV.FNAL.GOV</u>
- Regular weekly meeting every Monday 2:15 PM (CET) 7:15 AM (CT)
- Material presented and discussed during WG meeting available on Indico: <u>https://agenda.infn.it/category/1684/</u> (from 7-FEB to 26-APR-2022) <u>https://indico.fnal.gov/category/1413/</u> (since 2-MAY-2022)

KLOE-to-SAND: dismounting of KLOE





KLOE-to-SAND activities at LNF

Plan of operations:

- ✓ Removal of all cables and the FEE+HV racks
- ✓ Extraction of the Drift Chamber Calorimeter
- ✓ Laser tracker survey before ECAL dismounting
- Extraction of Barrel (24 modules)
 - original insertion/extraction machine completely refurbished and operational
 - platform construction is being completed
- Dismounting of EndCaps
 - original insertion/extraction/rotation machine is being refurbished and modified
- Operational test of ECAL modules
- Studies for the ECAL working point & FEE

ed (C

ed (OC

ilab

EndCap

Magnet an

- Installatio
- new Powe
- Power Ele
- Control system and tull support for magner. dismount/remount by ANSALDO ASG
- Cooling of co
- Operational t
- in preparation
- Extraction of
- Dismounting

Packaging &

ECAL geometry survey



Survey performed by a specialized company:









Measured distance between:

Cloud of points (10x10 mm² pitch matrix) measured on the ECAL internal surface

Bottom plane reconstructed by accessible points on the Aluminum backplane at both module ends

Nominal value should be 230 mm (Pb+SciFi height)+ 25 mm Al plate thickness = 255 mm

ECAL geometry survey

















Figure 11 Removal of module 5.

Figure 12 Removal of calorimeter module 4.





Figure 14 Removal of calorimeter module 3.



Figure 15 Removal of calorimeter module 2.



Figure 16 Removal of calorimeter module 1 at level 2458 mm.

Figure 17 Removal of module 15 at level 1468 mm.







All platform pieces have been built (soldering, milling, cleaning, painting etc.. completed) by Fantini Sud company (Anagni). Final tests and safety certifications are being completed.

Delivery and installation at LNF in the next 1-2 weeks.





Extraction of barrel modules: rollers and pillars











12 rollers mounted on pillars will be placed as a redundant safety support for the extraction of the upper 3 modules.

All pieces built and delivered at LNF, are being tested and mounted in KLOE.

F. Raffaelli – INFN Pisa

A. Di Domenico













cleaning the End-Cap iron yoke surface and positioning the cables integral with ECAL modules

before

after







Thanks to LNF technical support and additional technicians from INFN Bologna, Lecce, Pisa, Roma

Dismounting of End-cap modules











Tools are being revamped (non-destructive structural analysis done), some parts replaced.

F. Noto – INFN LNS

Dismounting of End-cap modules









Design of supports for handling and transportation of each half End-cap completed

Special tool for dismounting the smallest module built and ready.

F. Noto – INFN LNS

Dismounting of End-cap modules







Design of supports for handling and transportation of each half End-cap completed

Order done, construction started.

Dismounting End-Cap modules foreseen by April-May 2024 F. Noto – INFN LNS

ECAL module refurbishment and test



- After dismounting operation, the special protective adesive tape of all barrel modules has to be replaced
- light tightness to be checked
- test basic performance with cosmics rays
- test EEE prototypes





n.5 A8030P boards 48 ch. 3 kV/1 mA n.1 SY4527B mainframe n. 1 A2551 board 8 V / 12 A (to be purchsed)





DUNE





A new Power Supply (PS) is needed, with the same performances of the old one

to save procurement time, avoiding long EU calls for tenders, we are setting the procurement with 3 partners



Possibly still usable: busbars, contactors, dump resistor, transformers

Obsolete and/or aged components to be replaced: transistors banks, cooling pipe, water loss, elctrolitic capacitors, electronic boards

Estimated PS delivery time 6 months Possible delivery of PS in second half of 2024

> Possible PS+Magnet Test End od 2024





Power Unit on blanket order INFN-CAEN

8 TDK-Lambda Genesys+ (375A, 20V) in parallel with CAEN-REGUL8OR regulation unit customized with our interlock interface (all USA standard compliant)

Quench Detector	Dump resistor Filter	Bus bars Contactors	Power Unit Free wheels diodes						



Old PS dismounted from Kloe platform and delivered to OCEM for inspections of components possibly saved

OCEM could also provide its own PU but would not be part of a blanket order.

We asked a PU quotation for a comparison with CAENels



KLOE PS Dump resistor and contactors



KLOE PS delivered to OCEM



Coil cool-down

Before dismounting and shipping (but after new PS installation) an operational test of the magnet is foreseen to test integration of all parts (PS, Quench Detector, Control System, Software Interface)



Coil extraction and transportation



Magnet extraction procedure



A. Saputi – INFN LNS

Coil extraction and transportation



Main services, structures and tools for extraction



Crane = 22 t + 22 t



Extraction/Insertion Tool



Loading Dock



Trolley System



Cradle



Lugs

The existing loading dock will be refurbished and enlarged on purpose

A. Saputi – INFN LNS

Coil extraction and transportation



Main services, structures and tools for extraction





All workshop drawings are ready
Technical specification is ready





All workshop drawings are ready
Technical specification is ready
Holes centre spacing to be checked





Reverse engineering of vessel Design of all handling and transportation tools completed. Call for offers started. Certification EU and US compliant

A. Saputi – INFN LNS





1 month

ND-hall availability: 2028



Studies for the optimization of the ECAL working point and FEE

A. Di Domenico, V. Di Silvestre, P. Gauzzi, D. Truncali - INFN-RM1 A. Balla - INFN-LNF

Np.e. distributions



PE distribution



Np.e. distributions



PE distribution



Cell occupancy plots and hit probability







Beam power 1.2 MW 7.5 x 10^{13} protons extracted every 1.2 s at 120 GeV 1.1 x 10^{21} pot/year

Spill time structure

- 9.6 µs per spill
- 6 batches, 84 bunches/batch
- 2 empty bunches
- 1 bunch: $Gaus(\sigma = 1.5 ns)$
- Δt bunches = 19 ns



Event rates expected in SAND

- ~ 84 interactions/spill
- ≲1 interaction/spill in the SAND fiducial volume

(negligible rock muons and cavern background assumed)

Pile-up probability





Pile-up probability





PMT signal and discriminator threshold in KLOE





CUNE

Test of preamp saturation



In this specific case (negligible cable length) we expect: $V_{dis}(max) = V_{preamp}(max) \cdot 0.5 = 2.35 V$

Assuming to increase $V_{preamp}(max)$ by 15% while keeping linearity at an acceptable level, e.g. 1% (feasible - see next slide), we get:

```
V_{preamp}(max) = 5.4 V
V_{dis}(max) = V_{preamp}(max) \cdot 0.5 = 2.7 V
```

Preamp linearity test (1) using pulse generator



Test set-up



Signal amplitude varied with calibrated attenuators (pulse width ~ 30 ns)



Signal at a modified test input: preamp gain ~1





Preamp linearity test (1): linear and saturation regimes

Linearity test



Choice of the dynamic range



Assuming:

- to increase $V_{preamp}(max)$ by 15% => $V_{preamp}(max)$ = 5.4 V
- $(N_{pe} G_{PM})(max) = 95 \cdot 10^7$
- $V_{dis}(max) = V_{preamp}(max) \cdot 0.5 \cdot C_{ATT} = 2.0 V$ (12m long cable attenuation: $C_{ATT} = 0.74$)
- to have a very low noise environment as in KLOE => lowering (halving) the minimum discriminator/digitizer threshold to V_{TH}= 2.5 mV

G_{PM}	G_{tot}	$N_{pe}(\max)$	signal	$N_{pe}(\min)$	MeV
$(\times 10^5)$	$(\times 10^{6})$		amplitude	$V_{TH} = 2.5 \text{ mV}$	at module center
			(mV/pe)		
4.8	1.2	~ 2000	1.0	~ 3	3.0
6.4	1.6	~ 1500	1.3	~ 2	2.0
9.5	2.4	~ 1000	2.0	~ 1	1.0

 Different dynamic ranges can be implemented changing G_{PM} => the final choice should be a compromise between an affordable level of events with energy saturated cells, depending on N_{pe}(max), and an acceptable neutron detection efficiency, depending on N_{pe}(min).

Preamp linearity test (2) with PMT system test



PMT system test at LNF with

- CAEN LED driver SP5601 (wavelength \sim 400 nm) with fine tunable LED intensity
- scint. fiber splitter
- two PMTs (for relative QE meas.)



no preamplifier



with preamplifier



Preamp linearity test (2): results (i)



LED driver attenuation scale checked and calibrated with PMT response in linear region



Preamp linearity test (2): results (ii)

REF PMT1







HV=1900 V



HV=2100 V

preamp recovery time from saturation depends on input amplitude signal

fixed LED









with preamp PMT2





- The time baseline is distorted during saturation. The recovery time from saturation to linear regime depends on the input signal amplitude.
- The input information is not fully lost during the saturation regime. The "over-linearity" of the integrated charge or the signal width increase vs the input signal amplitude could be exploited to characterize signals beyond the preamp saturation regime.

Choice of FEE for SAND/ECAL



Three possible read-out schemes:



CAEN:

collaboration for a commercial (partly customized) solution keeping KLOE energy and time performance

Conclusions



Advances in all KLOE-to-SAND activities:

- movable platform for the barrel modules extraction is being built; ~ready to be installed.
- design of mechanical tools for the End-cap dismounting ready; construction started.
- design for the dismounting of the magnet coil ready; call for offer.
- the magnet test is being prepared; agreement with contractors is being finalized.

Studies for the optimization of the working point of the SAND calorimeter read-out electronics have been performed.

The dynamic range and pile-up of the signals have been studied with MC.

PMT preamplifiers have been tested for linearity and are well compatible with needed dynamic range and proposed FEE solutions, with the additional advantage of a lower gain and HV level, beneficial for PMTs lifetime.

The features of preamp saturation could be exploited to partially recover input signal information during saturation regime.

Possible solutions for the FEE that could constitute a good compromise between cost and performance are being investigated in collaboration with CAEN. (Very recent and preliminary results obtained by CAEN on ToT with picoTDC and walk correction appear promising.) In general, any solution must be integrated in the SAND DAQ scheme, with possible synergies with other detector electronics.