



Fermilab Underground Facilities


Enectali Figueroa-Feliciano Northwestern/Fermilab/QSC May 31, 2024





MINOS Underground Tunnel

- 5 min from Wilson Hall
- 107 m underground








NEXUS and QUIET @ FNAL


Two cryogenic facilities located in the MINOS hall at Fermilab

- 107 m (225 mwe)
 underground for cosmic
 radiation shielding
- Reduced muon flux of 7 muons/cm²/day, more than two orders of magnitude lower than surface muon rate











Northwestern Experimental Underground Site

- Dry dilution refrigerator from Cryoconcept with a base temperature 8 mK and cooling power of
- Only underground cryogenic facility fitted with a dedicated neutron calibration system.
- Lead inner and outer shields give a low gamma background environment of 500 evts/kg/day at 100 keV.
- 10 RF lines currently used for qubit and kinetic inductance detector work
- 8 DC SQUID channels used for neutrino and dark matter detector experiments, to be upgrades to 24 channels.








Northwestern Experimental Underground Site



- A standard way characterize detector response to nuclear recoils is with a neutron scattering setup
- $E_{\text{recoil}} = 2E_n \frac{M_n^2}{(M_n + M_T)^2} \left(\frac{M_T}{M_n} + \sin^2 \theta \cos \theta \sqrt{\left(\frac{M_T}{M_n}\right)^2 \sin^2 \theta} \right)$
- Precise knowledge of the scattering angle provides the recoil energy in the detector
- The detector signal can then be calibrated as a function of neutron recoil energy





Northwestern Experimental Underground Site












NEXUS DD Generator


Northwestern

Experimental
Underground Site
@Fermilab

- Adelphi DD-108
- Generates up to 10⁸ 2.4 MeV neutrons pers second in 4π through D(d,n)He reaction
- Borated and nominal poly shield around DD generator
- Collimated hole to produce beam toward NEXUS detectors











NEXUS Backing Array

- 9 concentric C-shaped bars of EJ200 scintillator with cross-section dimensions of 1.7 x 4 cm
- Each bar is wrapped in reflective material and has 8 SiPMs (Model S13360-6075PE) at each end for co-incidence tagging of events and efficient light collection.
- A central array of 8 horizontal and 8 vertical 0.7 x 0.7 cm bars will be used to center the beam.











NEXUS Backing Array

 9 concentric C-shaped bars of EJ200 scintillator with cross-section dimensions of 1.7 x 4 cm







R inner [cm]	6.65	8.85	11.05	13.25	15.45	17.65	19.85	22.05	24.25
R outer [cm]	8.35	10.55	12.75	14.95	17.15	19.35	21.55	23.75	25.95
θ inner [degrees]	1.73	2.30	2.88	3.45	4.02	4.59	5.16	5.72	6.29
θ outer [degrees]	2.17	2.75	3.32	3.89	4.46	5.03	5.59	6.16	6.73
Si [eV]	102	170	255	358	478	615	769	940	1128
Ge [eV]	40	66	99	139	186	239	299	366	439





NEXUS Cryostat

- Cryoconcept Hexadray 200 with Ultraquiet Technology
- Cold volume: 30 cm diameter × 65 cm height
- Cooling power:
 - 200uW @ 100mK
 - 6 uW @ 20 mK
 - Base temp < 10 mK
- Movable 10 cm external lead castle
- Internal Lead Shield:
 - 24 cm diam. x 10 cm
 - Between MC and Payload
- Magnetic shielding: both an external (METGLAS®) and an internal (AMUNEAL A4K) magnetic shield
- 8 DC SQUID channels used for neutrino and dark matter detector experiments, to be upgrades to 24 channels.













NEXUS Cryostat











Northwestern EXperimental Underground Site



Dark Matter Searches with SuperCDMS, KIDs, and QSC

detectors

now



Neutrino Physics with Ricochet and CUPID



- Developed new modular architecture for neutrino physics detectors
- Deploying at ILL nuclear reactor next year
- R&D for future CUPID upgrades



- Qubit testing underway underground at NEXUS
- Developing R&D program for low-background quantum architectures



• 2 eV energy resolution

KID LDRD wrapping up

TES-based 2cm x 2cm x

4mm athermal phonon









Quantum Underground Instrumentation Experimental Testbed



QUIET was built to significantly enhance our capabilities in underground quantum work, with the following advantages over NEXUS:

- NEXUS is very high-demand and not dedicated to qubit operations
- Dedicated qubit experimental volume is limited
- Once the DD neutron generator turns on, NEXUS will switch from being a low-background facility to a neutron-calibration (activated) facility

Need a low-background facility dedicated to RF and qubit operations → QUIET






Quantum Underground Instrumentation Experimental Testbed



This QSC facility is the first low background underground cryostat dedicated to superconducting qubit operation in the USA

- Oxford Proteox w/ up to 16 NbTi and 48 SS RF lines with removable RF insert.
- 250 ft² Class 10,000 clean room
- 50 ft² antechamber for gowning and material cleaning
- Design of the QUIET radiation shield and muon veto is underway in parallel
- Initial fridge test reached 8.9mK w/ no issues






Quantum Underground Instrumentation Experimental Testbed



Magnetic Shielding:

Will achieve a large low-magnetic field environment at base temp, allowing ease of mounting several packages without the need for individual magnetic shielding.










Significant volume above shield at base temperature for circulators and other magnetic components.






Quantum Underground Instrumentation Experimental Testbed

Planned Upgrades:

- Radiation (lead) shield
 - Proteox can hold hundreds of pounds at mixing chamber plate
 - Plan to integrate cold magnetic shielding around cold radiation shield inside of IR-tight qubit package (all inside of 10mK can)
- Muon tagging
 - Muon rate is 7 counts/cm2/day
 - Need to integrate systems to know when NuMI beam is active
- Full QICK Control
 - Three 216 QICK platforms purchased, with room to expand further
 - Includes RF companion board (first tested in NEXUS!) that consolidates all warm-side filtering and mixing
 - Plans to expand to capacity for up to 100 qubits across 10 feed lines








CosmiQ group fridge operations (systems engineering)

Notes	Completion Status	leek of 4/24	Week of 5/1	Week of 5/8	Week of 5/15	Week of 5/22	Week o
Completed by Kester + Dan	Done						
Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line	Done						
	Done.						
All complete	Done						
Kelly+Hannah. Can is off, immediately follow swapping in of new focuser	Done						
Dan + Kester	Done		x	X	X		
Identified correct hard drives. Dan placed order for drives.	Done		x	x	x		
Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method							
Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP	Done		x	×	x		
Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests	Done		x				
Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN?	Done		x	x	x	x	x
	Done		X	X	X	x	
	Done					X	X
Ryan - to be performed today	Done					X	
Tuesday? Perform after safety pause. Kester +	2002						,
Ryan will work on this							X
	Marie Committee						X
							X
Toot is inconclusive	Mark Williams						×
Likely to be performed and/or monitored	Done						×
	Completed by Kester + Dan Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Identified correct hard drives. Dan placed order for drives. Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Ryan - to be performed today Tuesday? Perform after safety pause. Kester + Ryan will work on this	Completed by Kester + Dan Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Identified correct hard drives. Dan placed order for drives. Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Done Done Ryan - to be performed today Tuesday? Perform after safety pause. Kester + Ryan will work on this Test is inconclusive Likely to be performed and/or monitored	Completed by Kester + Dan Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Identified correct hard drives. Dan placed order for drives. Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Done Ryan - to be performed today Tuesday? Perform after safety pause. Kester + Ryan will work on this Done Not possible In progress Test is inconclusive Likely to be performed and/or monitored	Completed by Kester + Dan Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Identified correct hard drives. Dan placed order for drives. Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Done Xy Done Not possible In progress Test is inconclusive Likely to be performed and/or monitored	Completed by Kester + Dan Sealed in can, installed on MCP. Output line: need to install missing NbTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Done Done X X Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, w/in Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Done Ryan - to be performed today Tuesday? Perform after safety pause. Kester + Ryan will work on this Done Not possible In progress Done Likely to be performed and/or monitored	Completed by Kester + Dan Sealed in can, installed on MCP Output line: need to install missing NDTi cable. But RF tests down the pump and input lines complete. DC checks down the flux line Done Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Done Done Done X X X X Identified correct hard drives. Dan placed order for drives. Year. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, wfin Qubit can, and then PT100 is in MCP Focuser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests Some combination of Dylan/Ryan/Dan/Tali/Chris. How do we query database for Grafana? Does Grafana allow outgoing alerts/alarms to be forwarded over the WAN/LAN? Done Done X X X X X X X X X X X X X X	Completed by Kester + Dan Sealed in can, installed on MCP Output line: need to install rissing NTD calle. But RF tests down the pump and input lines complete. DC checks down the flux line Done Done Done Done All complete Kelly+Hannah. Can is off, immediately follow swapping in of new focuser Dan + Kester Identified correct hard drives. Dan placed order for drives. Ryan. PT100 needs to be calibrated, and unsure where to get that curve. May need to calibrate using other method Leiden: KID, Sapphire can, wfin Qubit can, and then PT100 is in MCP Couser arrived, plan to install it ahead of Run 2. Plan to do abbreviated version of warm tests. Some combination of Dene XX XX XX Done XX XX XX Done XX XX XX Done XX XX XX Creating the complete XX XX XX XX Done XX XX XX Done XX XX XX Creating the complete XX XX





Quantum Underground Instrumentation Experimental Testbed



- Oxford Proteox MX
 - Removable secondary insert containing all RF lines (right)
- Cooling power:
 - Base temp < 10 mK
- Internal Magnetic Shield:
 - Thermally sunk to MCP
- 12(4) input(output) coaxial RF lines installed with room for expansion up to 48(16)

