

Coldbox Calibration

APC - 01/02/2023

Coldbox - LED calibration




The laser can be changed

275 nm (labeled #3) used for SPE

This is the configuration used to trigger the LED.

Ch1 -> LED

Ch2 -> digitizer/oscilloscope.



Trigger in (from source)

Coldbox - LED calibration

Using DAPHNE:

- Trigger rate could not be higher than 50 Hz:

Two configurations used:

1)

- LED and Trigger pulse set to 50 Hz

- Acquisition of 16 us waveform

Reliable method, but takes around 3 minutes to get 10k events

2)

- LED set to 50 kHz (one pulse each 20 us)


- Trigger pulse set to 50 Hz

- Acquisition of 100 us waveforms (5 led pulses in each waveform)

Still need to be fully tested, but takes around 40 seconds to get 10k events

Coldbox - LED calibration



- 1)
 - LED and Trigger pulse set to 50 Hz
 - Acquisition of 16 us waveformReliable method, but takes around 3 minutes to get 10k events



Coldbox - LED calibration

2)



- LED set to 50 kHz (one pulse each 20 us)
 - Trigger pulse set to 50 Hz
 - Acquisition of 100 us waveforms (5 led pulses in each waveform)
- Still need to be fully tested, but takes around 40 seconds to get 10k events



Coldbox - LED calibration

2)

- LED set to 50 kHz (one pulse each 20 us)
 - Trigger pulse set to 50 Hz
 - Acquisition of 100 us waveforms (5 led pulses in each waveform)
- Still need to be fully tested, but takes around 40 seconds to get 10k events



3)

Alternative to calibrate without external trigger:

- Two LEDs, with different intensities
- Flash first LED with low intensity and with a delay of ~ 1 us flash a high intensity LED
- Self triggering would be easy to spot second pulse, so we can use as reference for performing calibration same as (2)