

The best way to probe CP violation in the lepton sector is with long-baseline accelerator neutrino experiments in the appearance mode: the appearance of ν_e in predominantly ν_μ beams. Here we show that it is possible to discover CP violation with disappearance experiments only, by combining JUNO for electron neutrinos and DUNE or Hyper-Kamiokande for muon neutrinos. While the maximum sensitivity to discover CP is quite modest (1.6σ with 6 years of JUNO and 13 years of DUNE), some values of δ may be disfavored by $> 3\sigma$ depending on the true value of δ .

CP-Violation with Neutrino Disappearance

Peter B. Denton

DUNE LBL WG


March 4, 2024



Brookhaven[™]
National Laboratory



Speaking from [Setauket](#) land



Four known unknown in particle physics: all neutrinos

Atmospheric mass ordering

θ_{23} octant

Complex phase

Absolute mass scale

Four known unknown in particle physics: all neutrinos

Atmospheric mass ordering

θ_{23} octant

Complex phase

Absolute mass scale

Outline

1. Why CPV is interesting
2. Relationship between appearance, disappearance, CP, T, CPT
3. Three ways to see why there is CPV information in disappearance
 - 3.1 Degrees of freedom
 - 3.2 Direct analytic calculation
 - 3.3 Numerical test
4. Recommendation

Why is CPV interesting?

δ and CP violation

$$J_{CP} = s_{12}c_{12}s_{13}c_{13}^2s_{23}c_{23} \sin \delta$$

C. Jarlskog [PRL 55, 1039 \(1985\)](#)



δ and CP violation



$$J_{CP} = s_{12}c_{12}s_{13}c_{13}^2s_{23}c_{23} \sin \delta$$

C. Jarlskog [PRL 55, 1039 \(1985\)](#)

1. Strong interaction: no observed EDM \Rightarrow CP (nearly) **conserved**

$$\frac{\bar{\theta}}{2\pi} < 10^{-11}$$

J. Pendlebury, et al. [1509.04411](#)

2. Quark mass matrix: non-zero but **small** CP violation

$$\frac{|J_{CKM}|}{J_{\max}} = 3 \times 10^{-4}$$

CKMfitter [1501.05013](#)



3. Lepton mass matrix: ?

$$\frac{|J_{PMNS}|}{J_{\max}} < 0.34$$

[PBD](#), J. Gehrlein, R. Pestes [2008.01110](#)

$$J_{\max} = \frac{1}{6\sqrt{3}} \approx 0.096$$

δ : what is it really?



δ : what is it not?

$\delta \not\Rightarrow$ Baryogenesis

The amount of leptogenesis is a function of:

1. the heavy mass scale
2. δ
3. α, β (Majorana phases)
4. CP phases in the RH neutrinos
5. ...

C. Hagedorn, et al. [1711.02866](#)


K. Moffat, et al. [1809.08251](#)

Measuring $\delta = 0, \pi$	$\not\Rightarrow$	no leptogenesis
Measuring $\delta \neq 0, \pi$	$\not\Rightarrow$	leptogenesis

δ, J : current status

Maximal CP violation is already ruled out:

1. $\theta_{12} \neq 45^\circ$ at $\sim 15\sigma$
2. $\theta_{13} \neq \tan^{-1} \frac{1}{\sqrt{2}} \approx 35^\circ$ at many (100) σ
3. $\theta_{23} = 45^\circ$ allowed at $\sim 1\sigma$
4. $|\sin \delta| = 1$ allowed



When δ and when J ?

If the goal is **CP violation** the Jarlskog invariant should be used

however

If the goal is **measuring the parameters** one must use δ

Given θ_{12} , θ_{13} , θ_{23} , and J , I can't determine the sign of $\cos \delta$ which is physical

e.g. $P(\nu_\mu \rightarrow \nu_\mu)$ depends on $\cos \delta$

Appearance, disappearance, and CP

Appearance vs. Disappearance

Some oscillation experiments can do appearance or disappearance experiments

Disappearance

MINOS, $\text{NO}\nu\text{A}$, T2K

KamLAND, Daya Bay, RENO, Double CHOOZ

(Sort of) SNO, Borexino, SK-solar

Neither appearance nor disappearance


SK-atm, IceCube

Appearance

T2K, $\text{NO}\nu\text{A}$

OPERA

CP, T: Disappearance




Disappearance measurements are even eigenstates of CP

$$P(\nu_e \rightarrow \nu_e) = P(\bar{\nu}_e \rightarrow \bar{\nu}_e)$$

Assume that CPT is a good symmetry

CP, T: Appearance



Appearance measurements are not eigenstates of CP

Appearance and Disappearance, CPC and CPV

Disappearance:

$$\begin{aligned} P(\nu_\alpha \rightarrow \nu_\alpha) &= 1 - 4|U_{\alpha 1}|^2|U_{\alpha 2}|^2 \sin^2 \Delta_{21} \\ &\quad - 4|U_{\alpha 1}|^2|U_{\alpha 3}|^2 \sin^2 \Delta_{31} \\ &\quad - 4|U_{\alpha 2}|^2|U_{\alpha 3}|^2 \sin^2 \Delta_{32} \\ &= P_{\alpha\alpha}^{CPC} \end{aligned}$$

$$\Delta_{ij} \equiv \Delta m_{ij}^2 L/4E$$

Appearance and Disappearance, CPC and CPV

Disappearance:

$$\begin{aligned} P(\nu_\alpha \rightarrow \nu_\alpha) &= 1 - 4|U_{\alpha 1}|^2|U_{\alpha 2}|^2 \sin^2 \Delta_{21} \\ &\quad - 4|U_{\alpha 1}|^2|U_{\alpha 3}|^2 \sin^2 \Delta_{31} \\ &\quad - 4|U_{\alpha 2}|^2|U_{\alpha 3}|^2 \sin^2 \Delta_{32} \\ &= P_{\alpha\alpha}^{CPC} \end{aligned}$$

Appearance:

$$\begin{aligned} P(\nu_\alpha \rightarrow \nu_\beta) &= -4\Re[U_{\alpha 1}U_{\beta 1}^*U_{\alpha 2}^*U_{\beta 2}] \sin^2 \Delta_{21} \\ &\quad - 4\Re[U_{\alpha 1}U_{\beta 1}^*U_{\alpha 3}^*U_{\beta 3}] \sin^2 \Delta_{31} \\ &\quad - 4\Re[U_{\alpha 3}U_{\beta 3}^*U_{\alpha 2}^*U_{\beta 2}] \sin^2 \Delta_{32} \\ &\quad \pm 8J_{CP} \sin \Delta_{21} \sin \Delta_{31} \sin \Delta_{32} \\ &= P_{\alpha\beta}^{CPC} + P_{\alpha\beta}^{CPV} \end{aligned}$$

$$\Delta_{ij} \equiv \Delta m_{ij}^2 L/4E$$

Sign depends on α, β

Conventional Wisdom

1. Appearance is sensitive to CPV [True]
2. Disappearance has no CPV sensitivity [False]
3. Any δ dependence in disappearance doesn't exist in ν_e [Confusing/False]

$$\begin{pmatrix} c_{13}c_{12} & c_{13}s_{12} & s_{13}e^{-i\delta} \\ -c_{23}s_{12} - s_{23}s_{13}c_{12}e^{i\delta} & c_{23}c_{12} - s_{23}s_{13}s_{12}e^{i\delta} & s_{23}c_{13} \\ s_{23}s_{12} - c_{23}s_{13}c_{12}e^{i\delta} & -s_{23}c_{12} - c_{23}s_{13}s_{12}e^{i\delta} & c_{23}c_{13} \end{pmatrix}$$

Correct Statements

- ▶ Appearance is the best way to measure δ and CPV
 - ... given known oscillation parameters, systematics, and realistic experiments
 - ▶ Probes mostly $\sin \delta$ not $\cos \delta$
 - ▶ Don't need both ν and $\bar{\nu}$ (but systematics)
- ▶ **Disappearance can measure δ**
 - ▶ CPV can be discovered with only disappearance measurements
 - ▶ Probes mostly $\cos \delta$ not $\sin \delta$
 - ▶ Requires measurements of two flavors
 - ▶ “Works through unitarity” (as do nearly all oscillation measurements)

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

2. Disappearance experiments of one flavor can measure up to 3 amplitudes

- ▶ ν_e : Daya Bay/RENO measured 1, KamLAND measured a different 1, JUNO will measure all 3
- ▶ ν_μ : MINOS/T2K/NO ν A measured 1

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

2. Disappearance experiments of one flavor can measure up to 3 amplitudes
 - ▶ ν_e : Daya Bay/RENO measured 1, KamLAND measured a different 1, JUNO will measure all 3
 - ▶ ν_μ : MINOS/T2K/NO ν A measured 1
3. Only 2 for one flavor are independent

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

2. Disappearance experiments of one flavor can measure up to 3 amplitudes
 - ▶ ν_e : Daya Bay/RENO measured 1, KamLAND measured a different 1, JUNO will measure all 3
 - ▶ ν_μ : MINOS/T2K/NO ν A measured 1
3. Only 2 for one flavor are independent
4. Given good measurements of the ν_e and ν_μ disappearance, 4 independent parameters will be measured
 - ▶ Since one row can always be “simple” ($c_{12}c_{13}$, $s_{12}c_{13}$, s_{13}) no one row is ever enough
 - ▶ That is, CPV is physical and cannot depend on parameterization

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

2. Disappearance experiments of one flavor can measure up to 3 amplitudes
 - ▶ ν_e : Daya Bay/RENO measured 1, KamLAND measured a different 1, JUNO will measure all 3
 - ▶ ν_μ : MINOS/T2K/NO ν A measured 1
3. Only 2 for one flavor are independent
4. Given good measurements of the ν_e and ν_μ disappearance, 4 independent parameters will be measured
 - ▶ Since one row can always be “simple” ($c_{12}c_{13}$, $s_{12}c_{13}$, s_{13}) no one row is ever enough
 - ▶ That is, CPV is physical and cannot depend on parameterization
5. This is sufficient to constrain $\cos \delta$ and three mixing angles

Degrees of Freedom

1. Four DOFs in the PMNS matrix

Majorana phases are irrelevant

2. Disappearance experiments of one flavor can measure up to 3 amplitudes

- ▶ ν_e : Daya Bay/RENO measured 1, KamLAND measured a different 1, JUNO will measure all 3
- ▶ ν_μ : MINOS/T2K/NO ν A measured 1

3. Only 2 for one flavor are independent

4. Given good measurements of the ν_e and ν_μ disappearance, 4 independent parameters will be measured

- ▶ Since one row can always be “simple” ($c_{12}c_{13}$, $s_{12}c_{13}$, s_{13}) no one row is ever enough
- ▶ That is, CPV is physical and cannot depend on parameterization

5. This is sufficient to constrain $\cos \delta$ and three mixing angles

6. If we determine $\cos \delta \neq +1, -1 \Rightarrow$ CP is violated!

Direct Analytic Calculation

Disappearance experiments measure various $|U_{\alpha i}|^2$ terms

Suppose 4 are measured: $|U_{e2}|^2$, $|U_{e3}|^2$, $|U_{\mu 2}|^2$, $|U_{\mu 3}|^2$

Actually this gives all 9 magnitudes by unitarity

Direct Analytic Calculation

Disappearance experiments measure various $|U_{\alpha i}|^2$ terms

Suppose 4 are measured: $|U_{e2}|^2$, $|U_{e3}|^2$, $|U_{\mu 2}|^2$, $|U_{\mu 3}|^2$

Actually this gives all 9 magnitudes by unitarity

$$J_{CP}^2 = |U_{e2}|^2 |U_{\mu 2}|^2 |U_{e3}|^2 |U_{\mu 3}|^2 - \frac{1}{4} (1 - |U_{e2}|^2 - |U_{\mu 2}|^2 - |U_{e3}|^2 - |U_{\mu 3}|^2 + |U_{e2}|^2 |U_{\mu 3}|^2 + |U_{e3}|^2 |U_{\mu 2}|^2)^2$$

Disappearance can tell us if CP is violated, but not if nature prefers ν 's or $\bar{\nu}$'s


Numerical Studies

Inputs are *only*:



- ▶ Daya Bay for θ_{13} 1809.02261
- ▶ JUNO 6 yrs precision on θ_{12} , Δm_{21}^2 , Δm_{31}^2 2204.13249
- ▶ DUNE 6.5+6.5 yrs disappearance channels only 2103.04797

Also looked at varying JUNO's and DUNE's runtime, and at HK

Where is $|U_{\mu 2}|^2$?





Where is $|U_{\mu 2}|^2$?



	$\cos \delta$	ROI 1	ROI 2
6.5 yrs ν_μ rates	1	5506	5038
	0	5418	5115
	-1	5334	5193

Final Sensitivities




Discussion

- ▶ **Disappearance can discover CPV**
- ▶ Requires two good measurements: JUNO and DUNE/HK
- ▶ Can rule out some values of δ at $> 3\sigma$
- ▶ Analyses already exist but...
- ▶ **LBL Experiments should break down δ analyses into app vs. dis**
- ▶ Since systematics are different, provides a good cross check
- ▶ Subject to BSM degeneracies, as are most other oscillation measurements
- ▶ Works in vacuum or matter; matter slightly minimizes HK's effect

Backups

References



SK [hep-ex/9807003](#)

M. Gonzalez-Garcia, et al. [hep-ph/0009350](#)

M. Maltoni, et al. [hep-ph/0207227](#)

SK [hep-ex/0501064](#)

SK [hep-ex/0604011](#)

T. Schwetz, M. Tortola, J. Valle [0808.2016](#)

M. Gonzalez-Garcia, M. Maltoni, J. Salvado [1001.4524](#)

T2K [1106.2822](#)



D. Forero, M. Tortola, J. Valle [1205.4018](#)

D. Forero, M. Tortola, J. Valle [1405.7540](#)


P. de Salas, et al. [1708.01186](#)

F. Capozzi et al. [2003.08511](#)

CPV Sensitivity at HK




Varying Runtime/Power



Complex phase in different parameterizations

- ▶ Can relate the complex phase in one parameterization to that in another
- ▶ U_{132} and U_{213} similar to U_{123}
- ▶ δ constrained to $\sim [150^\circ, 210^\circ]$ in $U_{231}, U_{312}, U_{321}$
- ▶ Bands indicate 3σ uncertainty on $\theta_{12}, \theta_{13}, \theta_{23}$
- ▶ “50% of possible values of δ ”
 \Rightarrow parameterization dependent

DUNE TDR II [2002.03005](#)



Quark mixing

From the PDG, V_{CKM} in the V_{123} parameterization is

$$\theta_{12} = 13.09^\circ \quad \theta_{13} = 0.2068^\circ \quad \theta_{23} = 2.323^\circ \quad \delta_{\text{PDG}} = 68.53^\circ$$



Looks like “large” CPV:

$$\sin \delta_{\text{PDG}} = 0.93 \sim 1$$

yet $J_{\text{CKM}}/J_{\text{max}} = 3 \times 10^{-4}$.

Switch to V_{212} parameterization, $\Rightarrow \delta' = 1^\circ$ and $\sin \delta' = 0.02$.

Standard oscillation parameters



Can see that the combination doesn't like the NO while it does like the IO
IO preferred over NO at $\Delta\chi^2 = 2.3$

CP violation in oscillations

In vacuum at first maximum:

$$P_{\mu e} - \bar{P}_{\mu e} \approx 8\pi J \frac{\Delta m_{21}^2}{\Delta m_{32}^2}$$

$$J \equiv s_{12}c_{12}s_{13}c_{13}^2s_{23}c_{23} \sin \delta$$

C. Jarlskog [PRL 55, 1039 \(1985\)](#)

- ▶ Extracting δ from data requires every other oscillation parameter
- ▶ J requires only Δm_{21}^2 (up to matter effects)


Matter effects are easily accounted for

$$\hat{J} \simeq \frac{J}{\sqrt{(c_{212} - c_{13}^2 a / \Delta m_{21}^2)^2 + s_{212}^2} \sqrt{(c_{213} - a / \Delta m_{ee}^2)^2 + s_{213}^2}}$$

[PBD](#), S. Parke [1902.07185](#)

[PBD](#), H. Minakata, S. Parke [1604.08167](#)






Repeated rotations



	U_{121}	U_{131}	U_{212}	U_{232}	U_{313}	U_{323}
$ U_{e2} $	✓	✓	✓	✓	✗	✗
$ U_{e3} $	✓	✓	✗	✗	✓	✓
$ U_{\mu3} $	✗	✗	✓	✓	✓	✓

Note that $e^{i\delta}$ must be on first or third rotation


Allowed δ' range



The importance of $\cos \delta$

- ▶ If only $\sin \delta$ is measured \Rightarrow sign degeneracy: $\cos \delta = \pm\sqrt{1 - \sin^2 \delta}$
- ▶ Most flavor models predict $\cos \delta$

J. Gehrlein, et al. [2203.06219](#)



L. Everett, et al. [1912.10139](#)