Report from STT Working Group

S. Di Falco

INFN Pisa, Italy

R. Petti

University of South Carolina, Columbia SC, USA IIT Guwahati, India

G. Sirri

INFN Bologna, Italy

SAND meeting 19 March 2024



Focus on progress since January CM:

- + Demonstration of integrated STT readout boards with C-fiber prototype at CERN;
- Tests of the new crimping pins with mockup prototype;
- Tests of wire spacers with 4m straws;
- Thermal analysis of 4m STT module with new readout boards;
- Study of gas flow in full scale 4m STT modules;
- Connections of STT modules;
- Preparation for STT production at GTU.

Material presented during WG meetings (Wednesdays, 8:00am Central Time / US) available on Indico: https://indico.fnal.gov/category/1402/

INTEGRATED STT READOUT BOARDS

V. Bautin (JINR)

3



- ◆ Small boards reading up to 64 straws each with ASIC + micro-controller (MCU);
- + Connection with straw pins via flexible kapton PCBs;
- ◆ Off-the-shelf analog ASIC (G. De Geronimo) can be replaced with custom one;
- ◆ Low-power boards (~0.65 W each for 64 channels) minimizing signal path.

 \implies First version (v1) successfully tested, revised version (v2) in preparation with PCIe connector



4



and the second second



Demonstration of integrated STT readout

6

board with STT prototype at CERN:

*Ar/CO*₂ 70/30

⁵⁵Fe measured charge spectrum

⁵⁵Fe charge spectrum as a function of the straw number in the STT prototype (3 dead ASIC channels)



- ✦ Resolution of TAC amplitude < 1mV resulting in TDC measurement FWHM <0.125%;</p>
- ← Timing resolution within simulated 8 µs spill using the 12 bit ADC in MCU;
- + Preliminary results comparable with the ones obtained with VMM3 and Tiger at testbeam.

7

NEW CRIMPING PINS



- ♦ New large crimping pins to fix the wire + extra spacer for wire centering:
 - Reduced costs (~\$1.1M savings) and easier supply of pins;
 - Simplified assembly procedure: self-centering of wires with glued spacers insensitive to endplug misalignments.
- ◆ Samples of the final revised pins (v2) delivered to CERN (3,000 pieces total)

TESTS OF NEW CRIMPING PINS



T. Enik (INP)

After smoothing the edge of the central hole the sample pins (v1) tested on the mockup STT prototype using temporary 3D printed endplugs









The new pins (v1) can be crimped using the ATLAS tool and hold the LUMA W/Re wire with the correct nominal tension

TESTS OF WIRE SPACERS WITH 4m STRAWS



- + Samples of wire spacers produced with UV 3D printing (100 μm hole);
- + Special Cu/Au straws produced with thin metallization to allow visual inspection of spacers inside;
- + Drop of dual-component cyanoacrylate glue used to fix the spacer position along the wire.



- ✦ First test of wiring 4m straws with 3 spacers along the wire;
- ◆ Successful wiring if spacer within tolerances and with smooth external surface;
- + Additional studies to be done: wiring in vertical position, rate of broken wires or wire slippage.

12

THERMAL ANALYSIS AND GAS FLOW STUDIES

O. Kemularia (GTU)

13



- ✦ Thermal analysis of full scale STT module with 22+24 integrated readout boards;
- + Self-cooling design with expected total power dissipation about 0.65 W per board (mostly ASIC);
- + Study of gas flow within the STT module to verify uniformity and inlet/endplug design.







Preliminary results indicate that we can achieve steady state with uniform gas flow across the 4m manifold

ELECTRICAL CONNECTIONS



Details of the electrical input/output connections of STT modules (independent for XX and YY layers)



Schematic diagram of the DAQ/DTS and LV connections for one STT Super-Module

DAQ/DTS+LV DISTRIBUTION BOARDS

- Two DAQ/DTS distribution boards per supermodule separate for XX and YY straws:
 - DAQ/DTS endpoints with FPGA common to other systems;
 - 10 RJ45 shielded cables (one/STT module) from all XX (or YY) straws in a supermodule;
 - Total of 16 DAQ/DTS distribution boards / endpoints for entire STT.

 \implies Plan to use common DAQ/DTS boards with GRAIN (N. Tosi)

- ♦ One LV distribution board for each DAQ/DTS board:
 - 10 (one/STT module) + 1 (DAQ/DTS) LV channels feeding all XX (or YY) straws in supermodule;
 - Maximal number of output LV cables: 4×10 depending on input lines in STT module;
 - Same modularity for DAQ/DTS and LV distribution grouped within same distribution box.
- Each DAQ/DTS+LV distribution box outside of magnet close to supermodule:
 - Minimize length of cables as distribution boards close to corner blocks with electrical connections;
 - All RJ45 & LV cables connected to a DAQ/DTS distribution boards will have identical length.

DIGITAL I/O CONNECTIONS

- ♦ RJ45 digital I/O connector for XX (or YY) readout boards:
 - 4 pairs of LVDS signals: data TX, data RX, begin of spill, machine clock;
 - All XX (or YY) FE boards share common TX and RX lines like in RS422 protocol (V. Bautin);
 - All FE boards can receive data at all times, but only one transmits at a time;
 - MODBUS (or similar) request-response protocol.

♦ JTAG connector for firmware update in all XX (or YY) readout boards:

- After detector commissioning & initial runs we do not expect frequent updates;
- No need of permanent cable to DAQ/DTS distribution boards.



JTAG connector



PREPARATION FOR STT PRODUCTION AT GTU



- ♦ Preparation of new larger laboratory for STT production in Tbilisi;
- + Double straw production line $(2 \times 5m)$ with ultrasonic welding moved to new laboratory;
- + Straw production lines being upgraded with new parts to improve accuracy.

Backup slides

PROTOTYPING & TESTS

Demonstrate all aspects of the STT design in increasing order of complexity:

- \square Produce straws of required quality & maximal length with ultrasonic welding (UW) \implies Validation of model production lines at JINR (5m) and GTU (2m)
- ☑ Verify UW straws fulfill requirements from STT conceptual design & assembly procedure
 - ⇒ Measurement of maximal internal pressure, radial and longitudinal deformations vs. pressure, relaxation vs. time and humidity, gas tightness, etc.
- ☑ Verify XXYY straw layer assembly
 - \implies Gluing and pressure tests of $1m \times 1m$ XXYY test assembly
- ✓ Verify assembly procedure of XXYY straws to frame, gas tightness, etc. ⇒ Assembly and tests of mockup prototype with plexiglass frame
- \checkmark Verify module design with C-composite frame and related performance \implies Complete 1.2m \times 0.8m prototype with XXYY straws and actual STT frame design
- □ Verify full scale module ("module 0") with maximal straw length and complete assembly \implies Complete 4m × 3m prototype with XXYY straws and C-composite frame

Demonstrate readout performance:

- \checkmark Verify charge measurement with 55 Fe source & cosmics
 - \implies Readout small STT prototype with Mu2e FE boards with VMM3 ASICs
- ☑ Verify time measurement with signal generator
- ☑ Verify time and charge measurement at testbeam
 - \implies Readout small STT prototype with FE boards with VMM3 and Tiger ASICs

	VMM3	TIGER
Number of channels	64	64
Clock frequency	1080 MHz	160200 MHz
Input capacitance	<300 pF	<100 pF
Dynamic range	Linearity within ±2% up to 2 pC	50 fC
Gain	0.5, 1, 3, 6, 9, 12, 16 mV/fC	12 mV/fC
ENC (energy branch)	<3000 e ⁻	<1500 e ⁻
TDC binning	~1 ns	50 ps
Maximum event rate	4 MHz/ch	60 kHz/ch
Consumption	15 mW/ch	12 mW/ch