

DAQ Management Report

DUNE DAQ Consortium Board - 07.10.24

Alessandro Thea




Overview

- ProtoDUNE Operations
- DUNE-DAQ Developments
- FD - Preparation for installation
- ND - Ongoing activities



ProtoDUNE Operations



- NP04 completed 10 weeks of beam
 - ▶ 2 extra weeks extension wrt initial allocation
 - ▶ Last day of beam : Sep 16th
 - ▶ 4 weeks of detector stress tests in cold
 - ▶ Warm up and monitoring throughout the end of 2024/beginning of 2025
- NP02 Closure ongoing
 - ▶ Cooldown and fill expected in November
 - ▶ Beam time will be requested for first half of 2025




NP04 Overall DAQ Performance

T.Alves, W.Dallaway, I.Hristova,
M.Man, A.Oranday, M.Rigan,
P.Plesniak, M.Roda, A.Stucz,
D.Vargas

- DAQ stay collected data at ~15 Hz average trigger rate (2.1 GB/s), up to ~40 Hz instantaneous rate (5.7 GB/s)
 - ▶ Using 8 datawriter applications writing to SSD storage volumes
 - ▶ Limitation overall data rate is bandwidth from readout servers to data storage servers
- DAQ trigger records are ~142 MB in total size
 - ◆ 3 ms readout window for TPC (0.25 ms before trigger, 2.75 ms after)
 - ◆ 5.5 ms total readout window for all other components (2.75 ms before, 2.75 ms after)
 - ▶ TPC readout (streaming, unbiased): 107 MB
 - ▶ “Streaming” (unbiased) PDS readout in APA1: 25 MB
 - ▶ “Self-triggered” PDS readout in APAs 2-4: 9 MB
 - ▶ Trigger Primitives (from TPC, inside trigger record): 1 MB
 - ▶ Additional data from CRT, CTB, timing, high-level trigger objects is negligible
- Integration of *all external systems* (CRT, laser calibration) completed



NP04 Overall DAQ Performance





- ▶ Additional data from CRI, CTB, timing, high-level trigger objects is negligible
- Integration of **all external systems** (CRT, laser calibration) completed

NP04 Trigger Primitives

A. Oranday, M.Rigan, A.Sctuz, I. Hristova


- In addition, stably collected trigger primitives from collection planes and stored in TP stream files
 - ▶ Very high (~3 MHz) total TP rate, ~160 MB/s, due to surface operation
 - ▶ TP performance very good – clearly showing sub-MeV signals
 - ▶ TP generation on induction planes also demonstrated, but readout on all planes not stable with high (> 1 Hz) trigger rates (well beyond conditions for FD)
 - ▶ TPs have proven to be a remarkably good indicator of detector conditions



NP04 Post-beam run plans

Powered by DUNE-DAQ

- Test software-driven trigger stability and demonstrated running multiple algorithms
 - ▶ ‘ADCSimpleWindow’ algorithm previously tested and working stably
- DAQ performance testing (this week)
 - ▶ Focus on testing new readout server (np04-srv-031) with real data
 - Demonstrated running 2 APAs w/ TPG in both v4 and v5
 - Push to running 4 APAs w/ TPG
 - SN readout to local storage (10-100s sample)
 - ▶ Can also try to make time for other stress testing that benefits from detector data (e.g. storage server testing)



DUNE DAQ @ NP02

- **Integration effort with VD detector systems started long ago, with mixed success**
 - ▶ Currently bottom CRPs are the only system controlled, synchronised and readout via DUNE-DAQ.
 - ▶ Top CRPs and PDS partially/not integrated yet
- **Discussed with VD Technical Coordination about NP02 monitoring during purge, cooldown and fill**
 - ▶ Tentative goal: monitor the entire NP02 via DAQ
 - ▶ Likely: monitor BDE + PDS (legacy hardware) and complete integration in parallel
- **Other systems**
 - ▶ Cosmic Ray Taggers: positive first discussion with Grenoble and Bern groups (June)
 - ▶ Beam Instrumentation: NP04 BI to be moved to NP02
 - ◆ The Penn Central Trigger Board will provide beam triggers once more



DAQ-Detector integration status

- **Bottom Drift Electronics integrated with DAQ since '23**
 - ▶ One of the first system transitioning to Ethernet Readout in June '23
 - ▶ CRP 4 + 5 regularly monitored by BDE experts via DAQ
 - ▶ Continuous monitoring started in preparation to TCO closure
- **Top Drift Electronics**
 - ▶ Preliminary integration tests with timing ('23) and readout ('24) completed.
 - ▶ No integration for controls yet
 - ▶ Testing at scale (2 CRPs) and full integration with DUNE-DAQ still pending
- **PDS**
 - ▶ Integration with target hardware (DAPHNE v3) not started due to production delays
 - ▶ 2 DAPHNE v3 expected at CERN by end of September
 - ▶ Initial detector PDS monitoring via DAPHNE v2
 - ◆ to be swapped for v3 when ready



Overall EHN1 schedule



- Requested DAQ support for VD and HD coldboxes in autumn
 - Planning ongoing, DAQ hardware likely sufficient after rationalisation of the EHN1 setup



DUNE DAQ Developments

- **DAQ development plan heavily affected by operations at ProtoDUNE**
 - ▶ Significant amount of effort diverted to NP04 readiness and support in the Q2 and Q3
 - ◆ But operations offered many highly valuable opportunities to validate the system at scale, identify and fix existing issues
- **Main developments in 2024 (ongoing)**
 - ▶ New Configuration System
 - ▶ New Run Control
 - ▶ New Operational Monitoring infrastructure
 - ▶ Appfwk review implementation



New Configuration System - conffwk

G. Crone, E. Flumerfelt, G. Lehmann Miotto

- **Timeline**

- ▶ Prototype started in autumn '23
- ▶ Proof of concept in v5.0 engineering release (May '24)
- ▶ First detector support in v5.1 (July '24)
- ▶ Support for NP02 monitoring in v5.2 (October '24)

- **Key features**

- ▶ Based on the ATLAS configuration system (OKS+config packages)
- ▶ System configuration described as a collection of elements and their relationships via an abstract schema
 - ◆ XML schema and data files
- ▶ Includes a programmatic interface to read/write configurations in C++/Python
 - ◆ Data Access Layer - DAL
- ▶ Provides tools for editing schema and configurations



TDAQ System Description - confmodel & app model

G. Crone, E. Flumerfelt, G. Lehmann Miotto

- Main challenge so far: design of the TDAQ system representation as OKS schema


- ▶ Applications, Controllers, Hosts, FSM, Segments,... descriptions
- ▶ DAQ applications and modules description
 - ◆ including handling of large numbers of modules via automatic generation (SmartApplication pattern)
- ▶ Description of detector-readout connectivity
- ▶ DAQ modules settings optimisation
- ▶ Component enabling/disabling ...

- TDAQ model exercised at NP02


- ▶ CRP4 and 5 routinely readout using this model

- Next steps

- ▶ Testing TDAQ model flexibility and maintainability in operations context
 - ◆ and in development context (i.e. regression tests)
- ▶ Prepare specialised tools to for modifying/editing TDAQ configurations



DUNE DAQ Development Lines



New Run Control : Drunc

P.Lasorak, P.Plesinak

- Short term goals (DUNE-DAQ v5.2): readiness for NP02 operations
- Development didn't stop over the Summer
 - ▶ Made it more DAQ developer-friendly (FSM sequences, connectivity service)
 - ▶ Run archiving facilities integrated (ELisA, run registry)
 - ▶ Many bugfixes
 - ▶ Documentation rewrite
- More features in v5.2
 - ▶ **User/shifter**-friendly (hide more logging, hide/remove expert interactions)
 - ▶ Support Integration tests (a.k.a. batch mode)
 - ▶ ERS/Opmon integration
 - ▶ Timing system integration (maybe)
- Longer term
 - ▶ GUI, K8s PM, Session Handler




DUNE DAQ v5.2

Release Coordinator : E.Flumerfelt

Release status/progress

- Consolidation around new configuration and run control systems for NP02 operations
- Recovery of testing infrastructure in v5
- Forward-porting of v4 features and fixes
- Consolidation of many packages
- Good progress over the summer but large number of changes challenging to handle
- Target release date : Oct 21st




WBS NUMBER	TASK TITLE	WHO	PCT OF TASK COMPLETE	Q3							Q4					
				JUL			AUG			SEP			OCT		NOV	

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z
-s	Working Group	Package	notes	fddaq-v5.1.0	fddaq-v5.2.0-rc1	g file from OKS																			
EXT	@	FPGA Readout/SW Coord/Timing	uhal	v2.8.1		JF																			
SERVICES	CCM/SW Coord	trace		v3.17.09		JF																			
CORE	CCM/SW Coord	protobuf		v3.22.2		JF																			
	Brett/SW Coord	moo	py	v0.6.3		JF																			
	CCM/Integration	microservices		v2.0.0	Tag Pending	X	T. Alves																		
	CCM	elisa_client_api	py	v0.1.0			A. Tapper																		
	CCM	grafana-dashboards		2.3.0	Tag Pending	X	M Roda																		
	SW Coord	daq-buildtools		v8.6.1		JF																			
	SW Coord	daq-cmake		v2.9.0	Tag Pending	X	JF																		
	CCM	ers		1.5.2	1.5.2	M Roda																			
	CCM	logging		1.0.8		M Roda																			
	CCM	cmdlib		1.1.7		ELF																			
	CCM	restcmd		1.2.1		A. Tapper																			
	CCM	opmonlib		1.3.6	Tag Pending	X	M Roda																		
	CCM	rcif		1.2.3	Tag Pending	X	?																		
	CoreSW	appfwk		3.1.0	Tag Pending	X	ELF																		
	CoreSW	listrev		4.1.1	Tag Pending	X	ELF																		
	CoreSW	utilities		3.0.0		ELF																			
	CCM	erskafka		2.0.0	Tag Pending	X	M Roda																		
	CCM	kafkaopmon		2.0.0	Tag Pending	X	M Roda																		
	CoreSW	ipm		2.7.0	Tag Pending	X	ELF																		
	CoreSW	serialization		1.3.1		ELF																			
	Core SW	iomanager		1.6.0	Tag Pending	X	ELF																		
	CoreSW	dftmessages		2.7.0		ELF																			
	CoreSW	detdataformats		4.0.1		A. Thea																			
	Trigger	trgdataformats		1.1.0		A. Sztuc																			
	CoreSW	detchannelmaps		1.6.2		A. Thea																			
	CoreSW	daqdataformats		3.7.0		ELF/KB																			
	CoreSW	datahandlinglibs		3.0.1	Tag Pending	X	GLM																		
	CoreSW	dftmodules		3.1.3	Tag Pending	X	ELF/GJC																		
	Timing	hsilibs		v4.3.0		DA																			
	Timing	timing		7.6.0	Tag Pending	X	DA																		
	Timing	timinglibs		v4.2.0	Tag Pending	X	DA																		
	CoreSW, CCM (needs disc)	daqconf		8.0.1		G. Crone																			
	Trigger	trigger		2.0.3	Tag Pending	X	GLM																		
	Trigger	triggeralgs		1.2.1		A. Sztuc/JCF																			
	Trigger	trgttools		1.0.2		A. Sztuc																			
	CoreSW	hdf5libs		3.0.0		ELF																			
	CCM	oks		1.3.0		G. Crone																			
	CCM	okssystem		1.0.0		G. Crone																			
	CCM	oksutils		1.0.0		G. Crone																			
	CCM	oksconflibs		1.1.0		A. Thea																			
	CCM	conffwk		1.2.0		A. Thea																			
	CCM	oksdalgen		1.2.0		A. Thea																			
	CCM	confmodel		2.0.0		GLM																			
	CCM	appmodel		1.2.1		A. Thea/GJC																			
	CCM	dbe		1.3.0		A. Thea																			
	CoreSW	integrationtest	py	2.3.3		ELF																			
	CCM	drunc	py	v0.10.2		P.Plesniak																			
	CCM	druncschema	py	0.8.1		P.Plesniak																			
	CoreSW	ctbmodules		Not included in release !!!!																					
	CoreSW	daqsystemtest	py	3.2.1		ELF																			
	CoreSW	dpdklibs		2.1.0		A. Thea																			
	CoreSW	fddetdataformats		2.0.0		A. Thea																			



Far Detector : Installation Schedule

- DAQ Development and Procurement schedule driven by FD installation schedule
- Swap of the installation order of FD1-HD and FD2-VD completed in June
 - ▶ Later start, but shorter installation and fill time of the first module
 - ▶ Includes extra caverns delivery and CUC AUP delays



M. Nessi - Sep. DUNE CM

- Installation dates largely stable since then
 - ▶ Some clashes between DAQ and detector installation activities need following up
 - ◆ as well as a review of dependencies
 - ▶ Attempt to increase the contingency between DAQ and detector installation ongoing



Far Detector : DAQ Procurement after Detector Swap

- **Reminder: FD installation drives the DAQ procurement schedule**
 - ▶ “DAQ procures as late as possible”
- **Procurement and Production Readiness dates**
 - ▶ Installation of the first module (VD) delayed by ~7 months
 - ▶ DAQ PRR schedule updated
 - ◆ Timing, Readout network and DAQ Servers PRR delayed to early 2025 to make use of the extra time for testing and value engineering studies
- **Procurement Strategy**
 - ▶ Procurement plan under taking into account VD shorter installation and cooling schedule, and national funding constraints.



Near Detector : Updates

- New effort: Henry Wallace @ RHUL, also spending time on CCM
- ND DAQ: Being updated to be compatible with v5, work in progress
- Main driver for autumn 2024: ND review process
- Many PDR and FDR processes for ND subsystems
- Goal: DAQ Interface Control Documents (ICDs) completed by ~1 December



Near Detector : ICD updates

- ND-LAr
 - ▶ Mature technology for charge readout (=FDR this year)
 - ▶ Developing technology for light readout (=PDR this year)
 - ▶ Clear path to ICD
- TMS
 - ▶ Technology selection recently made (=PDR this year)
 - ▶ Sharing information to work out any friction points
 - ▶ Path to ICD
- SAND
 - ▶ In progress of setting up a meeting



NP02 DAQ Run Coordinator

- The ProtoDUNE DAQ run coordinator role was created in Q1 2024 times support the NP04 operations
- The ProtoDUNE DAQ coordinator
 - ▶ Is the point of contact with NP04 Run Coordination and other NP04 subsystems
 - ▶ Is responsible for the organisation of DAQ expert shifts
 - ▶ Is responsible for DAQ experts training
 - ▶ It represents the DAQ at weekly NP04 meetings and daily meetings
- W. Ketchum, who has served as DAQ run coordinator for NP04, and previously as DAQ EHN1 integration coordinator, is due to go back to FNAL in April 2025
 - ▶ I would like to take the opportunity to thank Wes for his tireless effort and for the success of the NP04 run.
- The DAQ is looking for a new DAQ Run Coordinator to lead the preparation and the NP02 DAQ operations
 - ▶ Please contact me if you have a suggestion for a candidate
- Ideally the new DAQ Run Coordinator should overlap with Wes as much as possible.



Summary

- **The NP04 run is now completed**
 - ▶ The DAQ is supporting and participating in a stress test campaign waiting for the LAr to be transferred
- **A different set of challenges is expected at NP02**
 - ▶ First demonstrator at scale of the VD technology
- **Focus shifting back to developments for DUNE**
 - ▶ New configuration system, run control, operational monitoring now available and in use
 - ▶ Discussion of 2025 development plans expected to start soon
- **Far Detector installation schedule update**
 - ▶ Procurement plan being reviewed in light of the new timeline and constraints
 - ▶ Interactions with other systems during installation being checked for conflicts
- **Near Detector DAQ interfaces being updated for the early 2025 detector reviews**
- **The consortium is looking for a DAQ Run Coordinator for NP02**

