

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

Modular Cavity Status


Daniel Bowring

Lawrence Berkeley National Laboratory

March 15, 2013



Maximum gradient decreases as applied B -field increases.



D. Huang *et al.*, *RF Studies at Fermilab MuCool Test Area*. Proc. PAC 2009, TU5PFP032, p. 888. Vancouver, Canada, 2009.

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design


Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

Reduction in gradient manifests as increased RF breakdown, cavity damage.



Damage from RF breakdown on the walls of an 805 MHz pillbox cavity. Surface is TiN-coated Cu. Damage spots are mm-scale.

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

RF breakdown in magnetic fields: Open Questions

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

- Does pulsed heating / cyclic fatigue play a role?
- Can we mitigate this problem via clever material choices?
- What role does the coupler play?
- Does measurement order (0 T vs. 3 T) play a role?

The modular cavity addresses these questions. This talk presents the design and fabrication status of the modular cavity.

Q: Who is building this cavity?

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

A: Lots of people.

- 1 LBNL is responsible for the overall R&D effort.
- 2 FNAL (the MuCool folks) have contributed much to the design effort / integration with MTA systems.
- 3 SLAC is responsible for mechanical design, fabrication. They have also brought their ACE3P expertise to the design process.

~ 20 people at 4 institutions have contributed.

Design Goals

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

- Evaluate theories of RF breakdown in strong magnetic fields. (c.f. D. Stratakis *et al.*, *Effects of external magnetic fields on the operation of high-gradient accelerating structures*. Nucl. Inst. Meth. A, **620** (23) 2010.)
- Performance limited by *cavity*, not *coupler*. (Coupler design)
- Replace damage quickly, cheaply when damage occurs. (Modularity)
- Evaluate multiple materials, surface treatments. (Modularity)
- Use facilities at MTA. (Fit the whole package in the Lab G solenoid.)

Simulation Effort

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

Mechanical
Design


Experimental
Design

Fabrication
Status


Future Plans




Omega3P



TEM3P



Track3P



G4beamline

ACE3P and G4beamline indispensable during design phase.

Multipacting simulation effort

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design



Mechanical
Design

Experimental
Design




Fabrication
Status

Future Plans

B=3T



B=0T



Track3P multipacting simulations at 0, 3 T
verify no resonant trajectories at problematic
energies.

- Extensive design effort.
- Tight fab. tolerances to achieve Q , coupling specs.

RF parameters

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

Mat.	Freq. (MHz)	Q_0	Q_{ext}	β	Neck width (mm)	Field Ratio*
Cu	805.012	25605	15854	1.62	65.25	5.36
Be	805.012	20499	15854	1.30	65.25	5.36

*Denotes the ratio of two fields: (1) the maximum surface electric field on the “beam axis”; (2) the maximum surface electric field elsewhere, i.e. on the coupling iris.

Cavity design is over-coupled in anticipation of clamping losses.

Mechanical Design: Overview

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

**Mechanical
Design**

Experimental
Design

Fabrication
Status

Future Plans



Mechanical Design (slide from David Martin)

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

**Mechanical
Design**

Experimental
Design

Fabrication
Status

Future Plans



Cavity and Waveguide

Mechanical Design (slide from David Martin)

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans



Cavity and Waveguide

Mechanical Design: Overview

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

**Mechanical
Design**

Experimental
Design

Fabrication
Status

Future Plans



Preliminary experimental program overview

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

- 1 Control runs on “regular” TiN-coated Cu end plates.
 - Does run order (0 vs. 3 T) matter?
 - Cu surface roughness comparable to that of Be end plates.
 - Quantify breakdown, damage behavior in this new cavity.
- 2 Assessment, workshop.
- 3 Study effects of chemical polishing on Cu performance.
- 4 Study effects of baking on Cu performance.
- 5 Run Be end plates.
- 6 Assessment.

A complete version of this document is available at
[http://mice.iit.edu/mta/rf/modular/
experimental_plan/experimental_plan.pdf](http://mice.iit.edu/mta/rf/modular/experimental_plan/experimental_plan.pdf)

login = modular

passwd = M0du1aR

Comments, questions welcome.

What does a run look like?

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

- Commission at 0 T.
- Open, inspect cavity.
- Run at 0 T.
- Open, inspect cavity.
- Repeat process at 3 T.

0 T, 3 T runs may be reversed, depending on the outcome of the control runs.

Automated damage inspection software will improve, speed up analysis.

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans



- Input: digital photos at regular intervals during the experiment.
- Output: Locations, sizes, creation times of all breakdown damage spots.
- Developed using free, open source software → This will be straightforward for you to install and run on your machine.
- Relevant beyond the modular cavity.
- Development supported by Muons, Inc.

Fabrication is underway.

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans



- We began cutting metal in February!
- Most work done in-house at SLAC.
- Regular, bi-monthly status meetings.

Fabrication Status as of February 28.

Modular
Cavity Status

Daniel
Bowring

By Month Due	DESCRIPT	DATE_MS	Sum of QTY_ORDER	Sum of QTY_REC	
2013					
Feb					
Motivation	SK-SB-70126287-0	RECTANGULAR FLANGE BLANK	2/25/13	2	0
	SK-SB-70126227-0	WR 975 OIP FLANGE BLANK	2/25/13	2	0
Mar					
Conceptual, RF Design	PF-701-262-93-0	VIEWPORT INSERT	02/06/13	6	0
	PF-701-262-83-0	OUTPUT BLOCK II	02/06/13	1	0
Mechanical Design	PF-701-262-84-0	COOLING CHANNEL LID	02/06/13	2	2
	PF-701-262-79-0	COPPER PLATE	02/06/13	2	2
	PF-701-262-90-0	END PLATE	02/06/13	1	1
Experimental Design	PF-701-262-56-0	PIVOT MOUNT	S.B.V.	4	4
	PF-701-262-69-0	WR 975 OUTPUT FLANGE	2/25/13	1	0
	PF-701-262-97-0	SLOTTED PLATE	02/25/13	2	0
Fabrication Status	PF-701-262-63-0	TUBE	02/28/13	2	2
	PF-701-262-64-0	6.00"OD ROT CF FLANGE MOD	02/22/13	2	2
	PF-701-262-70-	STIFFENER	02/25/13	3	3
Future Plans	PF-701-262-16-0	PORT SPOOL	02/25/13	6	8
	PF-701-262-62-0	TUBE, SUPPORT ARM	02/27/13	2	0
	PF-701-262-58-0	MIDDLE PLATE	02/25/13	4	0
	PF-701-262-59-0	END PLATE B	02/25/13	2	2
	PF-701-262-61-0	END PLATE A	02/25/13	2	2
	PF-701-262-95-0	MOUNT BLOCK	02/28/13	2	2
	PF-701-262-96-0	GUSSET BAR	02/28/13	2	0
	PF-701-262-98-0	8-32 BRAZE INSERT	02/28/13	12	0

Fabrication Photos

Modular
Cavity Status

Daniel
Bowring

Motivation


Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans



Looking forward

Modular
Cavity Status

Daniel
Bowring

Motivation

Conceptual,
RF Design

Mechanical
Design

Experimental
Design

Fabrication
Status

Future Plans

- Duplicate cavities.
- Build another cavity with gap length 15 cm.
- Dark current measurements using Be end plates.
- Button/anti-button tests.
- Exotic materials: Cu alloys, etc.