

DUNE DAQ US Servers Specifications Planning / Status

Wes Ketchum

DUNE DAQ General Meeting

4 September 2024

Scope

- US DOE responsible for:
 - Data storage and (non-readout) dataflow servers
 - Data filter servers
 - General infrastructure servers
- Focus is on specifications preparations needed to support initial detector installation
 - Would procure general infrastructure and data storage servers needed for that, starting in late 2025
 - Deprioritizing specifications/procurements for data filter servers to be closer to need-by date
- Plan to use common performance test framework where possible, focusing on key functionalities and unique drivers for specifications
 - Will include development of a more specific model for server usage

Dataflow servers

- Outlining key functionalities and developing plans for testing
 - (red – requires some more significant development for testing)
- Dataflow orchestration (EF)
 - Sanity-check tests with updates to remove single-point-failure completed
- **Trigger record building and writing**
 - NP04 system tests (KB, WK), **developing plans for testing compression in HDF5 (AM)**
- **Trigger primitive stream collection and writing**
 - **Developing scale-up tests, also considering compression tests (KB, AM)**
- **SNB data stream collection and writing**
 - **Reviving SNB transfer work, then need to develop record-building/translation code (KB, RS)**
- Data filter interfaces (orchestration, dispatch, result collection + writing)
 - Currently planning to extrapolate from other (similar) performance tests
 - Some time to revisit needs as data filter develops
- Transfer of data to offline, including metadata creation and transient data storage management
 - NP04 system tests (KB, WK)

Infrastructure Servers

Server	Comment	location	platform to proviso	Provided by	Needed for PRF shared by FD2& generator?
Kubernetes Services cluster	provision for FD2 detector installation first	multiple	metal	DUN...	<input checked="" type="checkbox"/>
facilities servers	gateway, Puppet, interactive logins, IPMI	multiple	metal	DUN...	<input checked="" type="checkbox"/>
Service	Comment			Provided by	Needed for PRRs
home areas/central storage	Ceph from CSAID? or regular NFS servers. similar	Ross ...	metal	DUN...	<input checked="" type="checkbox"/>
code distribution	CVMFS, discussion needed on architecture & testi	Ross ...	metal	DUN...	<input checked="" type="checkbox"/>
authentication (Kerberos)		Ross ...	VMWare	FNAL...	<input checked="" type="checkbox"/>
Active Directory		Ross ...	VMWare	FNAL...	<input checked="" type="checkbox"/>
DNS		Ross ...	VMWare	FNAL...	<input checked="" type="checkbox"/>
Backups		Fermi...	VMWare	FNAL...	<input type="checkbox"/>
Border and firewall		Ross ...	TBD	FNAL...	<input checked="" type="checkbox"/>
Logbook		TBD	TBD	FNAL...	<input checked="" type="checkbox"/>

- Similarly outlining key services / functionalities
 - Communication with Fermilab on host-lab-provided resources and accounting for that in our plan (BK)
 - E.g. authentication, DNS, backup services, database services, etc.
 - Developing plans for code distribution and local builds (JF, AM, BK)
 - Focus first on possible implications for specifications, but then more fully develop implementation plans
 - Translating service needs back to staged deployment plan and server specification (BK)
 - Including plans for shared resources between VD and HD, hot-spares and reliability
 - Confirm needs for additional testing plans, if any (what/where/how)

(Proposed) General timeline

- Dataflow servers:
 - Complete design/developments needed to fully test/spec systems with initial performance tests by end of September
 - Aiming for practicality, not perfection
 - Still, that may be optimistic if effort is drawn to other tasks
 - Review tests with consortium and develop more detailed server allocation plan with supporting tests (end of October?)
 - E.g., how many / which servers / what-kind-of-storage-backend for standard trigger records, trigger primitive streams, SN streams
 - Then prepare specifications documents for consortium review (end of November?)
- Infrastructure servers:
 - Develop server allocation plan / resources needs and identify any outstanding tests (end of Sep)
 - Review with consortium, including interfaces with other subsystems (end of October?) and support needs for installation
 - Relies on other subsystems / consortia to have needs prepared
 - Prepare specifications documents for consortium review (by end of November)