

# Cabling Test At CSU





01-08/09-2025

Warner,David  
Rautio,Zach  
Jablonski,Jay


Lin, Cheng-Ju Lin  
Zhao, Manhong

Stewart, James  
Joniak, Nicholas

# Cable bundle assembly station



# Machined parts of the cable bundling fixture



Cable Inlet Funnel Block



Sleeve Guide Rollers



Sleeve Application Tube




# Preload the sleeve onto the sleeve application tube

126 ft (38.4 m) long sleeve is loaded on the 8 ft long tube.




# Cable Spool Rack Design


Spool rack design #1



Spool rack design #2




Spool rack design #3





# Prototypes of Cable Spool Rack





# Cable bundle assembly station at CSU





# Winding individual cables onto separate spools





# Assembling the cable bundle


Sleeve applied on the cable bundle

Cable bundle and sleeve are pulled together

Cables on the rack


Sleeve on the tube

Cable bundle pulled through the tube






# Ladder cable tray assembly





# Cable bundles attached to the cable tray



# Summary

- Two cable bundles are assembled using the cable bundle assembly station.
- One ladder cable tray is assembled.

## **Issues Found:**

- Winding cables onto the spools is time-consuming.
- Cables on the spool unwind due to their own weight.
- Cables fit very tightly into the tube, and the connectors must be staggered.

## **Improvements CSU Plans to Make:**

- Design a fixture for winding cables onto the spools.
- Implement a brake mechanism on the cable spools.
- Split the 8 ft tube along its axis to allow for direct placement of cables inside.