Scintillator module design concept

Andy Furmanski Preliminary Design Review 7th February 2025

Calibrations/LED – monitor system, repair replace, etc



Introduction

- I will outline the conceptual design of the active detector modules
- Julianna will describe the mechanical details of the design
- I will summarise our prototyping plans
- Mayly will describe our construction plans



Scintillator detectors

- Interleaved with steel
 - See earlier talks for the details
 - Gaps are 50mm not much space!
- Core requirements:
 - Measure muon trajectories to sufficient precision to
 - Determine charge from bend in B-field
 - Measure range for energy estimate
 - Measure position/direction to match to ND-LAr
 - Cost-effective
- Plan is to use extruded scintillator bars from Fermilab's extrusion facility




Scintillator bar dimensions

- Bend in B-field leads to ~8cm total sagitta
 - Need to distinguish +8cm from -8cm
- Matching to LAr limited to ~5cm by multiple scattering
- Fast timing (few-ns) will separate RF buckets, and we'll see <1 muon per RF bucket
 - Therefore few-cm resolution is sufficient
- Light yield needs to provide "digital" response at minimum, 90% single-plane efficiency
 - This needs to still be true after 10 years
- Additional requirement is to fill the minimum active area (~7m x 3m)



Scintillator bar dimensions

- 3.6cm wide bars provide sufficient spatial resolution
- Dimensions fill space neatly, when split into 32-bar modules
 - 96 horizontal bars (3x32) would be 3.45m tall
 - 192 vertical bars (6x32) would be 6.9m wide
- This bar width leads to ~19,000 channels over the detector
- Bars are 1.6cm thick
 - Largely driven by mechanical design of modules





WLS fiber and readout

- 1.4mm fiber inserted into extruded hole
 - No glue used
 - Similar to T2K FGD construction
- All fibers read out on one end
- No "active" reflection added at other end
 - If prototypes suggest this is needed, it can be added

Evaluated alternatives. Using Kurary Y11 etc... Well-known timing characteristics




Light yield

- Muons (MIPs) will deposit approx. 2.5 MeV per bar
 - Assuming perpendicular path length can be longer
- Mu2e CRV tested TMS-like counters recently
- Same scintillator, similar dimensions
 - 10mm x 40mm (vs 16mm x 36mm)
 - Same 1.4mm fiber
- Test stand observed 38.8 PE per MIP
- Implication for TMS, with thicker scintillator \rightarrow 45+ PE per MIP
 - Assuming up to 5% decline per year from aging, still over 20PE per MIP after 10 years



"Modules"

- 32 bars make a module (~1.2m wide)
 - Each module has a mass of ~60kg
- Module design allows trivial adjustments to length
 - Planning 3.15m and 3.65m see later





Module orientation


- Modules tilted pm 3 degrees from vertical (U and V)
- Each *module* is tilted, not each bar
 - i.e. modules are rectangles, and we get small empty triangles
- Periodic counters placed horizontally to improve vertical resolution
 - Referred to as Y counters (they measure Y)
 - Expect ~10% of counters to be horizontal



Modules arranged in planes


U/V plane – readout on top —

Clarify centering, Y coverage includes all U/V coverage






Modules arranged in planes






- Stereo tilt provides ~30cm vertical position resolution
- But ~2cm horizontal resolution
 - This is to maximise bending plane resolution
- Knock-on effect on range measurement due to uncertain direction
- Add horizontal counters periodically!






- Stereo tilt provides ~30cm vertical position resolution
- But ~2cm horizontal resolution
 - This is to maximise bending plane resolution
- Knock-on effect on range measurement due to uncertain direction
- Add horizontal counters periodically!






- Stereo tilt provides ~30cm vertical position resolution
- But ~2cm horizontal resolution
 - This is to maximise bending plane resolution
- Knock-on effect on range measurement due to uncertain direction
- Add horizontal counters periodically!

Example – green and yellow paths are 3% different in length








Now only a very narrow

range of paths

- Stereo tilt provides ~30cm vertical position resolution
- But ~2cm horizontal resolution
 - This is to maximise bending plane resolution
- Knock-on effect on range measurement due to uncertain direction
- Add horizontal counters periodically!

 $\begin{bmatrix} -1 \\ -2 \\ -3 \end{bmatrix}$ $\begin{bmatrix} 1 \\ 12 \\ 13 \\ 14 \\ 15 \\ 16 \\ 17 \\ 18 \\ 2 \\ [m] \end{bmatrix}$





Some technical requirements

- One plane (view) of scintillator per inter-steel gap
- To meet efficiency and resolution requirements, single-plane muon efficiency must be >90%
- This can be a combination of:
 - Dead material
 - Dead/noisy electronics channels
 - Low efficiency (light yield)
- Goals are:
 - Light yield sufficient for ~100% efficiency
 - Dead channels < 5% (assumed requirement is 3%)
 - Dead material <5% (over the active area)

Module concept

- As far as possible, rely on:
 - Well-understood previously used design concepts
 - Off-the shelf, or mass-producible components
 - Re-use of equipment
- MINOS design for light-tight structural case
- NOvA-inspired injectable glue joints
- NOvA (and mu2e) automated flycutters for fiber ends
- Previous reviews urged us to consider ways to keep electronics accessible
 - Everything electronic is now separate from the mechanical modules



- Nesting aluminium half-boxes
- Edges crimped together





- Nesting aluminium half-boxes
- Edges crimped together





- Nesting aluminium half-boxes
- Edges crimped together





- Nesting aluminium half-boxes
- Edges crimped together





- Nesting aluminium half-boxes
- Edges crimped together








- Nesting aluminium half-boxes
- Edges crimped together



Crimping machine runs along the length, whatever that length may be



- Nesting aluminium half-boxes
- Edges crimped together
- Dead material between modules is 2x0.5mm aluminium




Sharp metal edges hidden!



Fiber manifolds


- Fibers grouped into sets of eight
 - Cables will have 10 conductors 8xSiPM, 1xLED, 1xRTD
- Four manifolds per module
- Reduce number of connectors by factor of 8
- Size dictated by minimum bend radius





End caps


Injectable glue joints allow a simple extrusion to form a light-tight seal





Whole module


• A whole module will therefore look like this





Cassette concept


- Magnet will be built and tested before installation of active detectors
- Each full plane will be constructed as a "cassette" to be inserted later
- Separates steel installation and detector construction timelines
- Allows removal of a cassette for repair/replacement in principle





Cassette outline


- Cassette is not a distinct object, which contains modules
- Modules are joined together to form a cassette
- This keeps the thickness minimised





Y cassette

• Horizontal counters assembled into a cassettee






Cassette installation

- Cassette will slide on a rail
 - Rail is supported below coils
- Low-friction surface provided by "ultra high molecular weight polyethylene" (UHMW-PE)
 - Available as adhesive-backed tape
- Cassette will be pulled, not pushed
- Angled pull allows reduced friction
 - Optimal angle TBD



Cable routing

- To keep cables short, electronics are directly above the magnet
- Coils will be installed before cassettes
- Cables need to be extracted after insertion
- Space is 5cm wide, and ~1m deep
 - A human arm isn't going to suffice
- Retractable arms built in to top of cassette allow a simple hook to lift prebundled cables



Potential performance improvements

- Conservative inter-steel gaps (50mm gaps, only 16mm of scintillator)
- More layers would increase reach (higher momentum, or better resolution)
 - Determine if cassette thickness can be reduced
 - Determine flatness of cassettes and steel
- Some easy fine-tuning possible:
 - Number and location of Y counters
 - Exact U/V stereo angle



Construction plans

- Two sites identified for module construction
 - University of Minnesota
 - Florida State University
- Expect to produce all modules (~600) in under 24 months
- Cassette construction will be done at Fermilab
 - Specifics depend on installation schedule
- See Mayly's talk later for details



Responses to charge

- Design updates from CDR design
 - Electronics/modules repairable/replaceable
 - Magnet and detector timelines decoupled
 - Module light-sealing and mechanical structure fully designed
 - Y modules now considered in addition to U and V
- See later talks for mechanical details, prototyping, and electronics plans

