



QXF Coil Fabrication & Tooling

Reaction / Impregnation

Jesse Schmalzle, BNL
February 17, 2014





Outline


- Tooling design
- Coil fabrication
- Status
- Summary

Coil Tooling Design


- QXF tooling design is based on tooling used successfully for LQ and HQ.
 - Reaction & Impregnation Tooling:
 - Stainless steel fixtures used to react and impregnate coils.
 - Full length base plate, top plate, side rails.
 - Mandrel and form block pieces are short blocks, approximately 50 mm long.
 - Thin stainless steel liner inside form blocks.
 - End plates seal the ends.



LQ (90 mm)
Coil Length 3.3 m






HQ (120 mm)
HQ 1.2 m, LHQ 3.3 m



QXF (150 mm)
SQXF 1.5 m, LQXF 4.3 m

Coil Tooling Design

- QXF tooling design is based on tooling used successfully for LQ and HQ.
 - Coil Lifting Fixture:
 - Rigid support for handling cured coil or impregnated coil.
 - Reacted coil not handled until after impregnation.
 - Coil Shipping Fixture:
 - Coil support tube mounted on rubber shock mounts.
 - Coil lead solder fixture:
 - Make connection between Nb_3Sn conductor and NbTi extension leads.





Coil Fabrication

- Coil fabrication procedures are well established and documented from LQ and HQ.
 - Travelers used on the shop floor provide step by step instructions, place for technicians to sign-off as operations are completed. Engineering sign-off at key points, e.g. after electrical checks.
 - QXF travelers are based on most recent HQ travelers.
- Facilities / Infrastructure is in place at multiple labs.
 - Reaction ovens at 3 labs (accommodate 4m coils).
 - Vacuum impregnation facilities at 3 labs.



Superconducting Magnet Division **LARP - LHQ Coil Prep for Impregnation** MDC No. LARP-210 Rev: A
 Page 4 of 23
 Rev Date: 05/08/2013
 Author: J. Schmalzle
 Approved: 10/11/2013

OP	Description	Name/Life #	Date	DR		
170	Coil electrical checks. Measure and record R, L and Q:	DC24716	27 DEC 13			
R (kOhms) (apply 25 V DC / 1 Amp)		.559 kΩ .559 VDC				
F (Hz)	20	50	100	200	500	1000
L (mH)	3.68	3.58	3.42	3.24	2.97	2.60
Q	.81	1.75	2.69	3.59	3.57	2.76

175 Perform continuity checks:

Coil to LE outer layer saddle: OPEN
 Coil to LE inner layer saddle: OPEN
 Coil to NL outer layer saddle: OPEN
 Coil to NL inner layer saddle: OPEN
 Coil to Pole (check each segment): OPEN
 Coil to End Spacers (2 LE, 1 NL): OPEN

180 Cognizant Electrical Engineer to sign-off results "OK to proceed".
 Cog. Electrical Engineer: [Signature]

190 Remove the LE saddle extension pieces and sst lead shims from the coil.
 Note: Saddles are not to be removed.


195 Carefully fold back the two layers of glass cloth from between to coil layers.

200 Remove the glass sleeve from coil leads. Carefully clean the lead with a SST brush.

LHQ03

Coil Fabrication

- Typical Reaction Impregnation schedule:



Procedure Outline:

- Reaction:

- Base plate and mandrel blocks laid out on assembly table.
- Cured coil placed into reaction mandrel blocks.
- Outer layer covered with fiberglass cloth and mica paper.
- Reaction liner, form blocks and top plate installed.
- Fixture bolted closed, flipped over and opened.
- Inner layer and midplanes covered with mica paper.
- Reaction mandrel blocks and base plate installed.
- Fixture bolted closed, end plates installed.
- Fixture moved into oven for reaction.
- Reaction includes steps at 210 C, 400 C and 640 C.

- Impregnation:

- Fixture moved from oven to assembly table.
- Reaction top plate, form blocks, liner, mica, fiberglass removed.
- Lead extensions soldered to coil leads.
- Outer instrumentation trace installed, covered with fiberglass.
- Impregnation liner, form blocks and top plate installed.
- Fixture bolted closed, flipped over.
- Reaction mandrel blocks, base plate and mica paper removed.
- Inner instrumentation trace installed, covered with fiberglass.
- Impregnation mandrel blocks and base plate installed.
- Fixture bolted closed. End plates and lead seals installed.
- Fixture moved to vacuum tank for impregnation.
- Pump down, bake out.
- Impregnate with CTD101k.
- Cure includes steps at 110 C and 125 C.

Coil QA

- Coil QA

- Electrical:

- Resistance / RLQ

- Coil
 - Voltage Taps
 - Heaters


- Hipot

- Coil to Heaters
 - Coil to End Shoe
 - Heaters to End Shoes
 - End Shoe to End Shoe

- Impulse


- Mechanical:


- Coil Length
 - Coil Azimuthal Size



Coil CMM Measurements

	Coil			Coil Hipot Checks			
		Heater PHA01		Actual / Target			
Heater PHA01	1000 / 1000		Heater PHA02				
Heater PHA02	1000 / 1000			Heater PHB01			
Heater PHB01	1000 / 1000				Heater PHB02		
Heater PHB02	1000 / 1000					LE IL Endshoe	
LE IL Endshoe	500 / 500	500 / 500	500 / 500				RE IL Endshoe
LE OL Endshoe	500 / 500			500 / 500	500 / 500	500 / 500	
RE IL Endshoe	500 / 500	500 / 500	500 / 500				
RE OL Endshoe	500 / 500			500 / 500	500 / 500		500 / 500







LARP



LHQ Coil Fabrication & Testing

- Electrical tests of the LHQ practice coil were run at higher levels than normal for HQ in order to demonstrate the ability to meet CERN's more stringent requirements.
 - Hipot coil to quench heaters – Passed at 5000 volts.
 - (Normal HQ test - 1000 volts)
 - Coil Impulse test – Passed at 3000 Volts.
 - (Normal HQ test - 1000 Volts)
- Upcoming mirror test of LHQ coil will demonstrate HQ features not present in the LQ magnets.
 - Cable with core, braided insulation, stainless steel end parts.





Status

- Coil fabrication procedures:
 - SQXF traveler preparation underway (based on HQ).
 - Coil QA is in place, being reviewed for compliance with CERN requirements.
- Tooling fabrication:
 - SQXF Reaction Impregnation fixtures – fabrication underway (FNAL).
 - First reaction set due early March.
 - First impregnation set due mid March.
 - Remaining sets by end of March.
 - SQXF Coil lifting fixtures - fabrication underway (BNL).
 - Some parts received, remaining due by end of February.
 - SQXF Coil shipping fixtures - fabrication underway (BNL).
 - Some parts received, remaining due early March.
 - Coil lead solder fixture - fabrication underway (BNL)
 - Due mid March.
 - LQXF Reaction Impregnation fixtures – design complete, drawings ready.
 - LQXF Coil lifting & shipping fixtures - design complete, drawings ready.



Summary

- QXF tooling designs based on tooling used successfully for LQ and HQ.
- Procedures well established and documented.
- Facilities / Infrastructure in existence at multiple labs.
- SQXF tooling fabrication well underway.