



QXF Plans and Preparation for Project

G. Ambrosio2/17/14





Outline

- Overview
- Short models plan
- Long models plan
- Schedule and budget
- Preparation for Project



LARP-CERN Integrated Plan

LARP and CERN are <u>working closely together</u> for developing and demonstrating the MQXF design:

- Requirements from Hi-Lumi LHC WP3
 - With strong LARP participation
- Shared work for the design (single design)
 - Working groups with representatives from 4 labs
- Shared effort for the 1st short model (SQXF1)
- Work in parallel for subsequent short models (SQXF)
- LARP/CERN full-length (4m/6m) prototypes (LQXF)





Plan Overview

- Short model program: **2014-2016**
 - Fabrication of practice coils is starting this month
 - According to schedule presented at CM20 (4/13)
 - First SQXF coil test (Mirror structure) in Dec. 2014
 - First magnet test (SQXF1) in May 2015
 - -2 (LARP) + 3 (CERN) short models + reassembly ($^{\sim}4$)
- Long model program: 2015-2017
 - Coil winding starts in 2015: Jan. (LARP), Sept. (CERN)
 - First LQXF coil test (Mirror structure) in Dec. 2015
 - First model test in Oct. 2016 (LARP) and July 2017 (CERN)
 - 3 (LARP) + 2 (CERN) models in total
- Series production: 2018-2022



SQXF plan and schedule: Coil fabrication



LARP

- Number of coils
 - First set
 - 2 practice coils
 - 1 mirror coil
 - 5 RRP coils
 - Second set
 - 5 RRP coils
- Fabrication steps
 - First set
 - FNAL: winding + curing
 - BNL, FNAL, LBNL: reaction + impregnation
 - Second set
 - FNAL: winding + curing
 - LBNL: reaction + impregnation
- Fabrication time
 - ~100 days (5 months) per coil
 - 1 coil produced every month
 - Budget limited

CERN

- Number of coils
 - First set
 - 2 practice coils
 - 1 mirror coil
 - 5 RRP coils
 - Second set
 - 6 PIT coils
 - 5 RRP coils
- Fabrication steps
 - Winding + curing + reaction + impregnation
- Fabrication time
 - ~100 days (5 months) per coil
 - 1 coil produced
 - every 2 months in the 1st year
 - every 1.5 months in the 2st year
 - every 1 months in the 3st year



SQXF plan and schedule:



Tests


From assembly to test and disassembly: ~5 months; Test by LARP or CERN

- 1st generation coils
 - First LARP coil test in 12/2014 (mirror structure)
 - First CERN coil test in 04/2015 (SQXF structure with practice coils or LARP mirror structure)
 - First magnet test (SQXF1) in 05/2015
 - Assembled ad tested by LARP with 3 LARP coils and 1 CERN coil
 - Then SQXF1b (prestress optimization)
 - First magnet test by CERN (SQXF2), then SQXF2b (test of LHe containment)
- 2nd generation coils
 - LARP RRP: SQXF3 (04/2016) and SQXF3b (11/2016)
 - CERN PIT: **SQXF4** (2016-2017)
 - CERN RRP: **SQXF5** (2017)
- Test of 2-magnets in 1-cold-mass: SQXF5+SQXF3b (2017)





SQXF Schedule





Long model program Plan and schedule



LARP

Number of coils

- 2 practice (1 FNAL & 1 BNL)
- 1 coil for mirror test
- 15 RRP coils
- Coil winding starts 01/2015

Models/tests

- 3 models, 3 tests + mirror
- 2 structures
- Vertical tests (BNL)
- Mirror test in 12/2015
- First model test in 10/2016
- Last test 04/2018

CERN

Number of coils

- 3 practice
- 1 coil for mirror test
- 11 coils (5 RRP + 6 PIT)
- Coil winding starts 09/2015


Models/tests

- 2 models, 3 tests
- Horiz. "simplified" tests
- Mirror test in 11/2016
- First model test in 07/2017
- Last test 10/2018



"In preparing for battle, I have always found that plans are useless but planning is indispensable."

DWIGHT D. EISENHOWER







Minimal program.

Having LARP & CERN

in parallel provides

risk mitigation

Planning

- Nb₃Sn magnets have never b particle accelerator yet!
- Short models (SQXF):
 - -2new + 2re (LARP)
 - Minimum for quench performance and prestress range
 - -2new + 2re (LARP, RRP) + 2new + 1re (CERN, RRP)
 - OK for understanding He-shell impact and 2-in-1 He-vessel
 - Minimum for field quality
 - 1mirror (LARP)
 - Very minimum (HQ had 3)
 - Provides test bed in case of issues



Planning

- Long models (LQXF):
 - 3new (LARP)
 - Almost minimum for demonstration of reproducibility
 - Ore (LARP)
 - This is a risk, LQS01b was very useful for LQ development
 - 1mirror (LARP)
 - Minimum: if we have limited performance in LQXF1 the mirror test will help understanding cause btw coil/structure
 - Provides test bed in case of issues

CERN will start after LARP and will develop 6.8m long magnets.

→ We count only on LARP for this.





QXF Schedule

- From strand procurement to test analysis
- Durations based on input from task leaders and L3s
- Schedule is budget limited (scenario #1)
- Resource loading is in progress
 - Started with this FY in order to compare RLS estimate with LARP-style estimate
 - Already providing useful feedback







LARP MS Budget Request

Unit: M\$	FY14	FY15	FY16	FY17	FY18
Labor	6.1	5.8	5.7	6.9	0.2
M&S	1.4	2.8	2.8	1.3	0.1
TOTAL	7.5*	8.6	8.5	8.2	0.3

^{*}Assuming \$0.3M from APUL contingency

• M&S drivers:

- Conductor (S/LQXF coils): \$2.5 M
 - Assuming \$1.2 M CDP contribution
- QXF coil tooling: ~\$1.5 M
- LQXF structures (2): \$0.8 M
- BNL vert. test facility upgr.: \$0.7 M

Need some trimming to fit into Scenarios #1,2

In order to fit into Scenario #3 we have to remove the LQXF mirror (\$1.5M):

Strand, Cable, Coil fabrication,
Structure procurement,
Assembly, Test.

high risk in case
 of limited
 performance of
 LQXF1





Preparation for Project


- Each lab is focusing and starting/strengthening its contributions to the Construction Project
 - Starting wind&cure line for LQXF coils at BNL
 - Strengthening QC and QA in all areas
 - Setting up a test facility for L/MQXF magnets
 - Building documentation and process
 - Conductor specs
 - Functional test requirements
 - SQXF1 design report





Monitoring Expenses

- For all major tasks we plan to monitor expenses vs. estimates on a monthly base
 - Both Labor and M&S
 - Work performed vs. work scheduled is already monitored separately
 - Previously done for some LQ tasks
 - First step toward EVMS







Conclusions

- In HiLumi, for the 1st time ever, Nb₃Sn magnets are a critical component of a particle accelerator
 - There is an intrinsic risk ... unknown unknowns
- LARP in collaboration with CERN has developed a plan adequate to this challenge
- We can make it successful with the <u>best</u> <u>resources</u> at all labs and sufficient <u>support</u> <u>from the funding agency</u>.