

# MICE Coupling Coil Tests and Results at Fermilab

Mike Tartaglia (TD/MSD → TD/T&I)

With major contributions from Ruben Carcagno

TD Test & Instrumentation Department

Fermilab Accelerator Division Cryo Group


LBNL Magnet Division

And much support from many many contributors

*MAP Collaboration Meeting*

*May 30, 2014*

- This has been a very intense, consuming, high priority ~3-year collaborative effort between numerous laboratories, divisions, and experiments
- It has resulted in a successful test of the 1<sup>st</sup> MICE CC magnet, although the outcome did not completely achieve the desired goal ( $I_{\max}$  x time)



Fermilab recognized the need for a large solenoid magnet test capability: MICE and Mu2e


- Obtained a large SMES cryostat from the NHMFL/FSU (October 2011)
- Test Stand designed/built to test MICE Coupling Coil Magnet windings (total of 4)
- Evaluated several Fermilab locations for this facility (IB1, CDF, CHL). Recommended CHL
- Plan approved by Directorate in January 2012
  - An enormous amount of work took place to quickly build this facility, get it ready and reviewed for safe operation
- Obtained ORC April 17, 2013
  - Test of first MICE CC cold mass started in May 2013

**Operational Readiness Clearance (ORC) granted April 17, 2013**






- Included cooling tubes welding, installation of leads stabilization, passive QP (cold diodes), instrumentation, etc.
- Preparations took ~ 1 year ! (in parallel with test stand construction)



SC Leads Stabilization




Cooling Tubes Connections



Leads Stabilization

Cold QP Diodes







- First Coupling Coil arrived at Fermilab on January 31, 2013
- Coil passed hipot, leak check, and instrumentation check
- (hipot Voltage limited to 250 V at 300 K)



Parameter	Value
Coil Length (mm)	285
Coil Inner Radius (mm)	750
Coil Thickness (mm)	102.5
Number of Layers	96
No. Turns per Layer	166
Assembly O.D. (without cooling tubes, mm)	1860.00
Assembly O.D. Envelope (with cooling tubes protrusion, mm)	2025.64
Assembly Height (mm)	325
Assembly Weight (tons)	2.2
Operating Current (A)	210
Maximum Test Current (A)	220
Self-Inductance (H)	596
Stored Energy at 210 A (MJ)	13
Stored Energy at 220 A (MJ)	14.4
Coil Temperature Margin (K)	0.77



- Magnetic Field at 210 A
  - Peak field in the coil: 7.5T
  - At center of coil: 2.6T
  - 600 G line radius: 9.8 ft
  - 100 G line radius: 16.4 ft
  - 5 G line radius: 50 ft







Fig. 1. Solenoid cross-section. All dimensions are in mm.

12 layers per coil, stycast “wet layup”  
 Cu/Nb-Ti Single Strand (L=600 H)  
 Slip planes to reduce shear stress (?)  
**There is no MICE Note or Publication on the actual coil fabrication**  
 (There are for prototype test coils)


Coil 1    Coil 8

Voltage Taps, protection diodes across each coil (diodes in both polarities)





Mice Coupling Coil - cool-down




- Started Monday 5/6/13 at noon
- Automatic cooldown with  $< 50$  K Delta T proceeded very well
- Coil  $< 10$  K by Wednesday 5/8/13 afternoon
- Helium to vacuum leak resulted in T limit to 9 K

4-5 day cool down from 300 K to stable “4K” conditions has been typical for 5 Thermal cycles; warm up is also 3-4 days.

- 1<sup>st</sup> TC in May 2013
  - reached 9K; He→vac leak
- Summer 2013:
  - re-design/make up (flexible) He connections
  - qualify stand cryogenics (zero magnet) - no leaks!
  - shorted bus & power supply endurance test to 220 A
  - lead thermal intercept improvements
  - Better vacuum gauges, He valve control
  - Increased cold surface area for cryo-pumping
- 2<sup>nd</sup> TC September 2013
  - Cool down 9/09 to 9/13; Rate-of-T-rise Heat Load  
Calc: ~10 W      Measurement: ~70 W
  - Power testing and quench training started, thru 9/27

- Coil kept quenching at ~62A
  - Thermal Limit?
- Decision was to warm up and identify source of heat load




- Problem: MLI Installation
  - Inadequate venting provisions
  - Thermal shorts
  - Too tight
  - Missing MLI on support rods










- Cold Mass surface temperatures reached equilibrium at temperatures higher than expected (5.2K-7.5K)



LBNL Thermal Model (Heng Pang)




- Required Heat Load for  $T_{coil} < 5.4K$ :  $< 15W$
- Estimated Heat Load  $\sim 10W$
- Measured Heat Load  $\sim 70-75W$



- Added Thermal Shield around cold mass, support brackets, and magnet reservoir
- Added thermal intercepts for mechanical supports
- Installed RGA, moved 400 l/s turbopump closer to cryostat
- Added thermometry
- Obtained technical support and blankets from Meyer Tool for MLI wrapping
- Calculated Heat Load with improvements: 2.8 W
  - <http://tiweb.fnal.gov/w/eb-site/controller/2637>





- 40 layers of MLI in 5-layer blankets with aluminum tape
- Loosely wrapped
- 2" long slits every 6" for venting provisions
- Vent pipe






- Third cooldown started February 18, 2014
- Cold Mass Temperatures reached equilibrium at ~ 4.4K-5.7K
- Measured shield T lower than predicted
  - Cold mass shield T < 10K
  - Support brackets shield T < 20K
  - MLI surface T 240-250K
- Insulating vacuum level is  $4 \times 10^{-6}$  Torr.
- T measurements comparison with model suggest a heat load of ~ 5 W
  - Measured (rate of rise) at 2 W !
- First coil quench at 127.7 A on 2/25/14
- T at neg lead still 1K higher than hottest coil surface temperature



- Third cool down started 2/18/14
- TC3 Quench Training (21 Feb - 02 Apr 2014)
- Thermal Cycle (03 – 13 Apr)
- TC4 Quench Re-training (14 – 18 Apr)
  - test quench memory after a TC
- Thermal cycle (20 Apr – 06 May)
  - CHL compressor failure and repairs
- TC5 Quench Re-training (07 – 16 May)
  - test re-training after a 2<sup>nd</sup> TC
  - test in reverse polarity (diodes) and “soak test”



Voltage Spike disturbance profiles are seen in most events at low current; similar, only the amplitude changes.

Visible on QD monitor even after training

Diodes turn on in the range of 5 to 15 V

First “triggered” event is at about twice the current previously reached in Sept. 2013 (64A). The very first event seen in Sept. at 62A was a similar voltage spike.


Quench Detection:  
 “Half coil difference” >3.0 V  
 Open PS contactors, forces current discharge through 2 Ohm dump resistor across coil  
 Large reverse voltage, forces all protection diodes to conduct (across each coil segment)

**Initial  $dI/dt=0.6A/min$   
 (>3 hour ramp to 120A)  
 (PS voltage limit, large L)**




- To prevent nuisance trips due to conductor-motion voltage spikes (not necessarily quench)
  - Raise Half-coil QD threshold to 4.5 V
  - Introduce 15 ms validation delay above threshold
- Add a second power supply
  - Peak ramp rate 30 mA/second
  - (initial eddy current T-rise of ~100 mK)
- Recover and ramp again (2/day)
  - Slow training, long ramp time
  - Only at low Current: Recovery time grows with  $I^2$
- Many attempts made to improve cryo stability
  - Several low current quenches caused by temperature excursions

# “Typical” Ramp to Quench



Ramp 48, Iq=194.5A




Slow but steady training (~1.5 A/quench), mostly “remembered” after each TC !





## Quench Current vs Maximum Surface Temperature (at negative lead; proxy for actual coil temperature)

Ability to maintain steady temperature conditions (2 phase helium) limited ability to reach high currents and hold for long periods  
Peak  $I_q=194.5A$

“soak test” performed for 2.5 hours at 175 A







Quench Developments are all  
**VERY SIMILAR**



Variable delay between time of disturbance and start of quench propagation depends upon:

- 1) Energy deposited > MQE
- 2) Distance from high field region


Need  $T >$  critical surface (r,z)

**TC3 Q26  $I_q = 168.9A$**


Magnitude vs. Time  
MICE\_CC\_03-17-14\_180310.qda







- Diode turn-on voltages



Lab tests (Barzi, Turrioni at FNAL) showed T, field-dependence ( $B_{\perp}$ ,  $B_{\parallel}$ ), 4-25 volts growing with  $B_{\perp}$








- Turn-on Voltages ~5-15V, appear to decrease slightly with field (Coil1 ~ 5V)

We never saw diodes conduct due to coil resistive voltage ??




- Marathon Test of 1<sup>st</sup> MICE Coupling Coil is complete
  - The entire team is exhausted and relieved!
- Coil Reached 194.5 A (goal was 214A) with slow but steady training
  - mostly coil 1 (highest field and forces) & 8
  - limited by temperature in negative lead region
  - Looking at the thermal intercepts, etc.
- Quench memory is very good after Thermal Cycles to room temperature
  - $I_q > 174A$  after each of 2 TCs
- 2.5 Hour “soak test” performed at 175 A
- Still much analysis to do – modeling of quench and peak coil temperature (MIITS)
  - Being done at LBNL


- BACKUP SLIDES



- “Ratcheting” stress redistribution during early ramps (1-5 shown)



- Expect linear behavior with  $I^2$ 
  - Some “unloading” possibly seen on the inner bobbin gauges



Wed Mar 12 18:45:56 2014

- Cooling Tube Vacuum Leak found during checkout
- Solution: a bypass pipe branch






Figure 1 CAD model image of magnet showing approximate location of vacuum leak.












- The Test Cryostat was brought to Fermilab from the NHMFL in Florida and installed in the CHL building, South Annex
- Unnecessary internals were removed, and both the vacuum vessel and the top plate were leak checked and passed





- New Dished Head
- Mechanical Supports
- Cryo Piping
- Current Leads
- Valves, Instrumentation
- Pressure Test
- Leak Check
- Hipot






- Conduction-cooled, optimized for 220A
- Two thermal intercepts: 60K (thermal strap to 4.5K GHe return pipe) and 4.5K (Wang NMR intercept to 4.5K boiling He reservoir)
- Low Temperature Superconductor (LTS) section between 4.5K intercept and coil leads
- G-10 mechanical support for magnetic forces



- Valves and Instruments, Instrumentation Tree, U-Tubes Connections, Power Connections, etc.

New Dished Head



- Liquid Helium and Helium gas recovery provided by the Central Helium Liquefier (unused after the Tevatron shutdown in September 2011)
- Up to 10 g/s of liquid helium at 4.5K supply to the Coupling Coil cooling tube from a nearby CHL 10,000 Gallon liquid helium Dewar
- Helium inlet temperature during cooldown/warmup controlled inside test cryostat to maintain a maximum cold mass gradient of 50K
- The return helium warmed up to room temperature before sending back to the CHL facility for recovery
- No venting to atmosphere expected during a quench (small LHe inventory in the cooling tube)

- Liquid Helium (LHe) Transfer Line from 10,000 Gallon LHe dewar to Bayonet Can




Bayonet Can

LHe Transfer Line

Connection to LHe Dewar







U-Tube to Bayonet Can





Return Gas to Warmup Heater






- Test Stand Instrumentation Racks and Examples of User Interfaces



- Local control station cannot be used under high magnetic field because personnel have to evacuate the area for safety reasons
- Two remote control stations installed: one in the CHL building, and another at the IB1 Magnet Test Facility
- E-log and measurement data available on a web interface

Remote Test Stand control station at IB1 Magnet Test Facility Control Room




CHL Test Stand Control Room (Climate Controlled, Acoustically Insulated)






- The Test Facility Power System Rack delivered by LBNL
- Fermilab added personnel Emergency Trip System Box and current readout hardware to the rack




MICE COUPLING COIL POWER SUPPLY SYSTEM



AC power and system grounding details not included

- Insulating vacuum quickly degraded when two-phase helium started flowing to the coil cooling tube
- Cold Mass surface temperatures could not get below 8 – 11K.





- After pressurizing the piping to 80 psig, a leak was found at one of the outlet VCR connections. All other joints did not show signs of a leak.
- Installed flexible hose to mitigate risk of VCR leaks
- A Test Cryostat acceptance test was conducted on July 24, 2013. The cold mass was bypassed and current leads shorted.
  - No Leaks
  - Current ramped successfully to 210A

