

# MICE Construction

Alan Bross

*Fermilab*

*May 28, 2014*


# Outline



- High-level overview
- US-Construction
  - Detector systems
  - LiH absorbers
  - Spectrometer Solenoids
    - 2 needed for Step IV
  - RFCC (RF-Coupling Coil)
  - Magnetic mitigation
    - Partial Return Yoke

# MICE Overview

- Purpose of MICE is to demonstrate  $\mu$ IC feasibility and validate its simulations
  - Engineering “proof-of-principal” in a number of areas
- Understand performance well enough to reliably extrapolate to cooling systems for MC or NF
  - Measure an  $\approx 10\%$  emittance reduction to 1% relative precision, i.e.,  $10^{-3}$  emittance resolution
  - Requires single-particle measurements in low-intensity beam



# US Organization



- MICE Construction L1: AB

*L2 structure:*



- Detectors
  - AB
- RF
  - Derun Li, LBNL
- Magnets
  - Soren Prestemon, LBNL
- Magnetic shielding
  - Holger Witte, BNL
- Component integration
  - Sandor Feher, Fermilab

# Detectors & LiH





- All detector systems are complete, installed and commissioned
- LiH disks are complete and ready to ship to RAL
- LiH wedges:
  - Partially completed. On hold at Y12 pending funding availability

# LiH



ISOMETRIC VIEW



- Will ship the LiH to RAL through Y12.
  - Since  ${}^6\text{Li}$  enriched, considered nuclear material

# Magnets

# Spectrometer Solenoids


- Both have been completed and are at RAL
- Reached full operating current (+2%) in flip and solenoid modes
  - Soak test a full current performed
  - Tested with iron shield in place
    - Minimal re-training
  - Fully mapped with CERN mapper
    - With & with out shield
    - x-check calib. With NMR probe




SS1 leaving Wang NMR




# SS1 and SS2 Training




# Training history



# Coupling Coil Magnets (CCM)



# Coupling Coils



# Solenoid Test Facility (STF)




- Designed/built to test MICE Coupling Coil Magnet windings
  - Will also be used to test coils for  $\mu 2e$
- Obtained a large SMES cryostat from the NHMFL/FSU
- Evaluated several Fermilab locations for this facility (IB1, CDF, CHL). Recommended CHL
- Plan approved by Directorate in January 2012
- Obtained ORC April 17, 2013
  - Test of first MICE CCM cold mass started in May 2013




# SMES Cryostat

*Then and now*







# Final MLI installation






# CC cryo performance

**MuCool-01 Temperatures**  
Heng Pan Model vs Measured Data 3/4/14





MICE CC Quench History ( 16-May-2014 )



- Training in CHL complete
- Cold mass warm and removed from STF
- Will be moved to ICB




# CCM Cryostat #1

- Being fabricated at LBNL
  - Ready to ship to Fermilab this week
- Thermal shields and cooling circuit
  - Shield drawings nearing completion
  - Cooling circuit drawings still in process
    - Design review in June
  - Both will be fabricated at LBNL



# Cold Mass / Thermal Shield Mock-up

A wood mock-up of the cold mass/thermal to assist in defining the coupling coil magnet assembly procedure



Vessel and shield mock-up being readied for shipment to FNAL

# Magnetic Shielding/Mitigation


# Magnetic shielding

- About 18 months ago, it was realized that the stray field from the MICE magnets would affect the operation of numerous electrical components in the MICE hall
- After extensive simulation studies and an external review, it was decided to utilize a partial return yoke (PRY) to reduce the stray fields to a level where all components in the MICE hall could operate
  - PRY also protects ISIS control room unequivocally



# Step IV Partial Return Yoke

- Design complete
- Steel order placed
  - Using JFE-EFE steel.
- Fab order out for bid
  - Close: 6/5





# RF

# RF

- The primary responsibility for MICE RF lies with LBNL
  - Cavity bodies complete except for final EP
  - Tuners for one RF module complete
    - NSF MRI (Mississippi)
  - Actuator design complete
    - First set delivered
  - New RF power coupler design complete
    - First 2 should be delivered to Fermilab this month
- At Fermilab we are setting up a Single-Cavity Test-System to conduct a full test in the MTA of the first production MICE 201 MHz cavity
  - First full system test



# MICE 201 MHz Production Cavity Test



Installed in the MTA and being readied for test  
Tests starting 2<sup>nd</sup> week of June  
See Yagmur's talk on Friday for details

# US MICE Construction project

## Critical Dates



- SS #1 arrives at RAL 5/1/14
- Step IV PRY at RAL (complete) 12/15/14
- CCM Assembly Complete 3/21/16
- CCM Testing Complete 8/31/16
- RFCC integration complete 12/28/16
- RFCC delivered to RAL 5/15/17
- Step V PRY complete 5/15/17
- Notes:
  - Expedited installation and commissioning schedule presently under review by UK team
  - Delivery schedule of Step V hardware could be expedited by having a suitable budget profile

# Conclusions



- Detector systems complete and all have been commissioned.
- Spectrometer solenoids are complete and at RAL
- First coupling coil winding looks good
  - Chinese company (Qi Huan) has started winding the next CC coil
- CMM cryostat nearing completion
- CCM assembly area identified
  - Setup starting
- Component fabrication for first RFCC is well along