



ND & FD Civil Construction

Steve Dixon
Fermilab Short-Baseline Neutrino Working Meeting
30 April 2014

Agenda

- Recent Building Examples
- Near Detector Building
- Far Detector Building
- Schedule




Recent Building Examples

- SciBooNE Enclosure
- NOvA Surface Building
- LArTF
- MC-1
- Mu2e



SciBooNE Enclosure

- Constructed in 2006
- -\$695,489
- 368 square feet
- \$2,266/square foot










NOvA Surface Building

- Constructed in 2010
- -\$1,500,012
- -2,160 square feet
- \$762/square foot











LAr Test Facility

- Constructed in 2013
- \$4,611,182
- -3,500 square feet
- \$1,349/square foot










MC-1 Building

- Constructed in 2014
- \$7,100,000 (budget amount)
- 13,500 square feet
- \$526/square foot











Mu2e Building

- Start Construction in 2014 (est)
- \$12,172,000 (estimate)
- 22,240 square feet
- \$547/square foot










Summary of Recent Construction

				2014		
	SF	Year Built	Constructed Cost	Construction Cost	\$/SF	
SciBooNE	368	2006	\$695,489	\$834,000	\$2,266	
NOvA Surface Building	2,160	2010	\$1,500,012	\$1,645,000	\$762	
LArTF	3,500	2013	\$4,611,182	\$4,720,000	\$1,349	
MC-1 (Budget)	13,500	2014	\$7,100,000	\$7,100,000	\$526	
Mu2e (Estimate)	22,240	2015	\$12,172,000	\$12,172,000	\$547	




Site Plan






Site Plan






Near Detector – 1st Pass





30APR14

Near Detector – 1st Pass




Near Detector – Two Estimates

SciBooNE Enclosure x 2

		FERMILAB FES	s cosi	ESTIMATE		
				Suggested Pr	oject Budget	\$4,060,00
Indirect Costs (assumes current GPP rates)						\$398,00
Management Reserve/Contingency 50%						\$1,156,00
Engineering, Design, Inspection and Administration			25%			\$508,00
			Estin	nated Subcontract	Award Amount	\$1,998,00
Esca	lation	ı	0.0%	1		\$
Subc	ontra	actor's Overhead and Profit	15.0%	This OH&P is only on	Site Work	\$46,00
Difficult Conditions		5.0%			\$93,00	
				Subcontract E	Base Estimate	\$1,859,00
Neı	utrin	o Campus Plan		Project No.	Status:	Date:
Fixed Price - LAr-1 Enclsoure			6-7-91	Pre-CD	25-Apr-14	
ITEM NO. DESCRIPTION OF WORK:						LOW
01		Site Work			\$215,00	
	01	Mobilize				ÅE 00
	0.1					\$5,00
	02	Roadwork				+-,
	02					\$5,00 \$15,00 \$150,00
	02	Roadwork				\$15,00 \$150,00
	02	Roadwork Extend Electrical (1.5 MW)				\$15,00 \$150,00 \$20,00
02	02 03 04	Roadwork Extend Electrical (1.5 MW) Extend ICW				\$15,00
02	02 03 04	Roadwork Extend Electrical (1.5 MW) Extend ICW Extend Data/Comm				\$15,00 \$150,00 \$20,00 \$25,00
02	02 03 04 05	Roadwork Extend Electrical (1.5 MW) Extend ICW Extend Data/Comm Building			\$685,000	\$15,00 \$150,00 \$20,00 \$25,00 \$1,644,00
02	02 03 04 05	Roadwork Extend Electrical (1.5 MW) Extend ICW Extend Data/Comm Building LAr-1 Enclosure - 736 sf SciBooNE - \$685k in 2006, 368 SF	% per year)		\$685,000 \$137,000	\$15,00 \$150,00 \$20,00 \$25,00 \$1,644,00
02	02 03 04 05	Roadwork Extend Electrical (1.5 MW) Extend ICW Extend Data/Comm Building LAr-1 Enclosure - 736 sf				\$15,00 \$150,00 \$20,00 \$25,00 \$1,644,00

50% Management Reserve/Contingency based on level of design requirements

Surface Building (NOvA Like)





Near Detector

Working Backwards from \$3m GPP Target

Construction		\$1,608,000
EDIA		\$402,000
Contingency/Management	\$548,000	
	Subtotal	\$2,558,000
Indirect Costs		\$472,000
	TOTAL	\$3,030,000




Design refinement and better requirement definition is required to go from 50% MR/C to 27%



Far Detector – October 2013 Study







Far Detector – October 2013 Study

						Low	High
				Suggested Pro	ject Budget	\$12,825,000	\$19,935,000
Indire	direct Costs (assumes current GPP rates)					\$1,277,000	\$1,878,000
Management Reserve/Contingency 50%			50%			\$3,738,000	
Engineering, Design, Inspection and Administration		30%			\$1,824,000	\$2,841,000	
			Estimat	ed Subcontract Av	vard Amount	\$5,986,000	\$9,377,000
Escalation 0.0%			0.0%			\$0	\$0
		15.0%			\$781,000	\$1,223,000	
Diffic	cult Co	onditions	2.0%			\$102,000	\$160,000
				Subcontract Ba	se Estimate	\$5,103,000	\$7,994,000
CAI	RUS	/NESSIE at Fermilab		Project No.	Status:	Date:	Rev Date
Fixed	Price			6-7-89	Pre-CD	11-Oct-13	
ITEM	1 NO.	DESCRIPTION OF WORK:				LOW	HIGH
01		Site Work	\$1,175,000	\$2,260,000			
	01	Wetland Mitigation (3 acres at 2:1 ratio)				\$450,000	\$660,000
	02	2 Roadwork					\$400,000
	03 Electrical (3 MW for Experiment, 1.5 MW for Cyro, 1 MW house power)					\$400,000	\$600,000
	04	4 Extend ICW					\$300,000
	05	Extend DWS			\$50,000	\$100,000	
	06	Extend Sanitary				\$50,000	\$100,000
	07	Extend Data/Comm				\$25,000	\$100,000
\dashv							
02		Building				\$3,928,000	\$5,734,000
	01	High Bay (170'x38') - Low based on MC-1 (\$3	500/sf) costs	\$2,261,000	\$3,230,000		
\neg	02	Below Grade Pit Construction Premium (ass	,_,	\$565,250	\$807,500		
\neg	03	Architectural Treatment Premium based on		\$452,000	\$646,000		
	04	Overhead Crane (1-30 ton)	\$150,000	\$250,000			
\neg	05	, ,				\$500,000	\$800,000
\Box							
\dashv							



Far Detector – January 2014 Update

Changes from October 2013 Study

- The requirements for the facility have been changed from a combined ICARUS/NESSIE experiment, to one that supports the construction and operation of only the ICARUS experiment only;
- The length of the building has been reduced from 51.5m (170') to 38m (125');
- The width of the below grade detector pit has increased from 8.5m (28') to 12m (39.5');
- The overall width of the building has increased from 11.6m (38') to 15.5m (51');
- The overhead bridge crane capacity has increased from 30 tons to 40 tons and the span of the bridge crane has been widened from 11.6m (38') to 15.5m (51') to correspond to the increased building width;
- The updated suggested project budget calculations listed below include increased Fermilab Indirect Rates issued in 24OCT13



Far Detector – January 2014 Update

						Low	High	
				Suggested Pr	oject Budget	\$13,180,000	\$20,529,000	
Indirect Costs (assumes current GPP rates)					\$1,435,000	\$2,104,000	4	
Management Reserve/Contingency 50%				\$3,772,000	\$5,918,000			
Engineering, Design, Inspection and Administration 30%				\$1,862,000	\$2,908,000			
Estimated Subcontro			ated Subcontract	Award Amount	\$6,111,000	\$9,599,000		
Escalation 0.0%					\$0	\$0		
Subcontractor's Overhead and Profit 15.0%				\$797,000	\$1,252,000			
Diffi	cult C	onditions	2.0%			\$104,000	\$164,000	
		•		Subcontract E	ase Estimate	\$5,210,000	\$8,183,000	
ICA	RUS	at Fermilab		Project No.	Status:	Date:	Rev Date	
Fixea	l Price			6-7-89	Pre-CD	11-Oct-13	21-Jan-14	
ITEN	ITEM NO. DESCRIPTION OF WORK:					LOW	HIGH	
01		Site Work			\$1,175,000	\$2,260,000	4	
	01 Wetland Mitigation (3 acres at 2:1 ratio)					\$450,000	\$660,000	
	02 Roadwork				\$200,000	\$400,000		
	03	03 Electrical (3 MW for Experiment, 1.5 MW for Cyro, 1 MW house power)				\$400,000	\$600,000	
	04					\$20	\$300,000	
	05	Extend DWS				\$50,000	\$100,000	İ
	06	6 Extend Sanitary				\$50,000	\$100,000	
	07	Extend Data/Comm		\$25,000	\$100,000			
02		Building		\$4,035,000	\$5,923,000			
	01	High Bay (125'x 51') - Low based on MC-1 (\$	350/sf), High b	ased on Mu2e (S	5500/sf) costs	\$2,231,250	\$3,187,500	ĺ
	02	Below Grade Pit Construction Premium (assu	.,,	\$558,000	\$797,000	ĺ		
	03	Architectural Treatment Premium based on	\$446,000	\$638,000				
	04	Overhead Crane (1-40 ton)		\$300,000	\$500,000			
	05	· · ·				\$500,000	\$800,000	



Far Detector


Working Backwards from <\$10m GPP Target

Construction	\$5,424,00	0
EDIA	\$1,357,00	0
Contingency/Management Reserve	e \$1,927,00	0 28% (Typical GPP: 25%-30%)
Subto	stal \$8,708,00	0
Indirect Costs	\$1,092,00	<u>0</u>
ТОТ	AL \$9,800,00	0

Design refinement and better requirement definition is required to go from 50% MR/C to 28%



Far Detector - Wetland





Looking Northwest

Wetland Impact

- \$450k-\$600k (construction cost)
- ~1+ year



Far Detector – Site Work





Aerial Photos of MINOS Construction in 2003





Far Detector - Depth



Aerial Photo from 2013 showing LArTF under construction






LArTF Stockpile

> bing

Schedule





Questions



Backup



Site Plan





Site Plan – Far Detector





Excavation Begins at SciBooNE



29





























