




U.S. DEPARTMENT OF  
**ENERGY** Office of  
Science



---

# Mu2e Tracker

Aseet Mukherjee  
Tracker L2 Manager  
7/8/2014



# Requirements




- Blind to DIO

- **$r < 380\text{mm}$** : “No” mass (vacuum)
- **$380 < r < 700\text{mm}$** : Low mass detector
- **$r > 700\text{mm}$** : Support structure

# Requirements

Reconstructed  $e^-$  Momentum




- Resolution

Tails matter, but using simple Gaussian

**$\sigma < 180$  keV/c at 105 MeV/c**

# Requirements



## • Timing

- Take data 500ns after proton pulse at full intensity.  
*Highest rate straws: 5 MHz (average over livetime)*
- 300ns after proton pulse at reduced intensity for calibration


# Requirements

---

- Particle ID
  - $dE/dx$  (pulse height) for p/e separation per hit
- Reliability
  - Operate in ambient vacuum
  - Leak rate  $<7$  ccm



***More complete requirements found in document 732***

# Design: Straw





- 5 mm OD metalized Mylar<sup>®</sup> straws, 15 $\mu$ m wall
  - Mylar for higher yield and modulus (compared to Kapton)
  - Aluminum on inner and outer surface
  - Gold on inner surface
- 25  $\mu$ m gold plated tungsten sense wire

# Design: Panel



- 96 straws of varying length form a *panel*
  - Staggered pattern to improve efficiency and left/right ambiguity resolution
  - Gap between straws to allow for expansion
- Panel frame encloses front end electronics

# Design: Panel





- Panel structure encloses front end electronics
- O-ring and screwed-down cover for gas seal
- Read out straws from both ends for time division  
*Measure position along wire by propagation time*





# Design: Plane, Station

---




- 6 panels form a self supporting ring called a plane
  - 30° rotation between sides for stereo and for mechanical strength
- Two planes, with a small gap, form a station

# Design: Full Tracker



- 20 stations with horizontal support beams form the tracker
- Support beams also carry utilities

# Design: Readout



# Material and Work Flow

1. Material from Sheldahl to PPG.  
*Winding done by PPG*
2. Straws from PPG to York  
*Test, cut, terminate*
3. Straws from PPG & Gas manifold parts from Fermilab to Rice.  
*Rice & U. Houston Assemble panels*
4. Completed panels to Duke  
*Wire position scan*
5. Panels sent to Fermilab  
*Assemble Tracker*



# Changes since CD-1

---

- Expanded radially from 800 to 810mm
  - Span of gas manifold goes from 100 to 110mm
    - Thicker support elements
    - Can use lower cost aluminum and plastic
  - Increased space for electronics
- Panel construction
  - Combine aluminum, stainless steel, and 3D printed plastic to reduce cost
- Plane Construction
  - Found 30° rotation gives improved stereo performance

# Changes since CD-1

---

- Number of stations
  - Found 20 stations gives excellent performance
- 3 beam support (was 4)
  - All cabling, gas... on lower beams
  - Allows easier removal of planes for repair
- Revised stiffener ring geometry to leave more room for calorimeter
- Front End Electronics
  - Commercial, off the shelf components

# Value Engineering since CD-1

---

- Most changes since CD-1 are part of value engineering
  - Panel Frame Construction
  - Number of Stations
  - Front end electronics

# Downselects


---

- Front end 100% COTS (no ASIC)
  - Reduces schedule uncertainty
  - Lower contingency
  - Greater benefits from Moore's Law




# Performance

- Resolution
  - Meets the simple Gaussian approximation requirement on  $\sigma$
  - Meets the SES requirement



# Performance

- Robustness
  - Functions with good efficiency and resolution with ~1000 dead straws



# Remaining work before CD-3

---

- Complete and test 1<sup>st</sup> panel
  - All metal frame
  - Testing includes operating in vacuum
  - Define parameters to enter into QC database
  - Test bed for electronics
- Complete and test 2<sup>nd</sup> panel
  - Composite frame
  - Refine parameters to enter into QC database
- Complete and test 1<sup>st</sup> plane
  - 6 panels
  - Refine assembly procedure
  - Test for ground loop or other coherent noise issues


# Remaining work before CD-3

---

- Design assembly fixtures
  - Panels to plane
  - Planes into full tracker
- Refine survey and installation
- Test outgassing from cabling, including optical fibers
- Test for electrical breakdown around Townsend regime

# Organizational Breakdown

Deputy L2 Manager R. Wagner  
Mechanical Engineer J. Howell  
G. Gallo  
Electrical Engineer: TBD



# Quality Assurance

---

- **Single Straws.** Each straw remains in a bar-coded storage tube from the first test till it is installed in a panel
  - Leak test each straw
    - May switch to spot-checking if failure rate remains very low
  - End-to-end resistance check
  - Record straw and wire tension over time
- **Panel.** Each panel is bar-coded.
  - Locate all wires relative to survey monuments using X-ray
  - Leak test all panels
    - May test in batches – multiple panels in vacuum vessel – if failure rate is low
- **Completed Tracker**
  - Optical survey of panel positions

# Quality Assurance

---

- **Preamps**
  - Bench test with pulser and high voltage
  - Test HV disconnect circuit on subset  
*Destructive to disconnect... needs repair after test*
- **Digitizers & ROC**
  - Bench test with pulser and built-in pattern generators
- **Monitoring**
  - Pressure and multiple temperature monitors in each panel
  - Precision electronic level and Hall probes to monitor detector orientation

# Risks

---

- TRACK-097 Catastrophic Failure
  - Probability: Very low
  - Impact: High, on cost and schedule
  - Mitigation
    - Natural disaster (flood, fire, tornado, ...): None
    - Over-pressure: Multiple relief valves (or bubblers), segmentation of gas system (each station fed separately)
    - Over-heating: Multiple sensors and interlocks




# Risks

- TRACK-139 Mylar Creep

- Probability: Low
- Impact: Medium, on cost, schedule, and performance
- Mitigation: Add one or more intermediate supports

*Conceptual design exists, will pursue if ongoing tests indicate a problem*




- There are no unusual ES&H issues
  - Gas (Ar:CO<sub>2</sub>) is non-flammable and non-toxic
  - Total detector gas volume is <1000L, less than a single compressed gas cylinder. Not a serious ODH issue.
  - High voltage is moderate by Fermilab standards  
1500V, <1mA and ~10mJ stored energy on any one line
  - Power is from 48V supplies which have passive (bound on capacity) and active current limitation
  - No toxic or hazardous materials used
    - Epoxy is used but there is extensive experience with this at all participating institutions

# Cost Table


	Base Cost (AY k\$)			Estimate Uncertainty (on remaining costs)	% Contingency on ETC	Total Cost
	M&S	Labor	Total			
475.06 Tracker						
475.06.01 Project Management	21	1,785	1,806	253	19%	2,059
475.06.02 Straws	1,354	65	1,419	488	38%	1,908
475.06.03 Straw Assemblies	2,991	824	3,815	1,495	42%	5,310
475.06.04 Front End Electronics	1,414	703	2,118	641	33%	2,759
475.06.05 Infrastructure	372	557	929	347	38%	1,276
475.06.06 Detector Assembly & Installation		68	68	36	53%	104
475.06.07 Tracker Conceptual Design/R&D	928	654	1,582		0%	1,582
475.06.99 Risk Based Contingency				651		651
Grand Total	7,080	4,656	11,736	3,912	43%	15,648

# Cost Breakdown




- L Labor
- M Material
- N Non-Fermi Labor

AY K\$




- 475.06 Tracker 475.06.01 Project Management
- 475.06 Tracker 475.06.02 Straws
- 475.06 Tracker 475.06.03 Straw Assemblies
- 475.06 Tracker 475.06.04 Front End Electronics
- 475.06 Tracker 475.06.05 Infrastructure
- 475.06 Tracker 475.06.06 Detector Assembly & Installation
- 475.06 Tracker 475.06.07 Tracker Conceptual Design/R&D

# Quality of Estimate




AY K\$

# Labor & Material by FY



# Labor Resources by FY



# Major Milestones

---

- Single Panel prototype evaluation complete enough for TDR Chapter
- Single Plane Prototype Evaluation Complete
- Final Design Tasks Complete
- Implementation Tasks Complete (Ready for Verification that KPP are met)
- Ready for Operations




# Schedule

CD-3a

CD-2/3

CD-4



# Summary

---

- Manufacture and QC of straws well defined
- Straw assembly procedures being tested now
  - Panel late FY14
  - Plane test late FY15
- Design and analysis of full tracker support and assembly under way
- Front end electronics technology chosen
  - Preliminary version of preamps, digitizers, ROC exist
  - Mother board design in progress
- Key elements of infrastructure defined
  - Cooling
  - Readout cables
  - LV distribution via DC-DC convertors
- Final assembly and installation being worked out with Muon Beamline
- Ready for construction starting FY16