




Mu2e CD-2 Review (Trigger and DAQ)

Mark Bowden
DAQ L2 Manager
7/8/2014




Requirements

- The requirements for the DAQ are described in Mu2e-docdb 1150.
- Collect and assemble data from the Tracker (estimated 13 GBytes/sec) and Calorimeter (estimated 8 GBytes/sec) for online analysis
- Provide online filtering to reduce data Tracker + Calorimeter data volume by ≥ 99%
- Combine with data from CRV, Extinction and Target Monitors (estimated 100 MBytes/sec) for transfer to offline storage

Requirements

- Provide global timing synchronization
- Provide fast and slow control networks
- Provide connections to offline storage and site networking
- Provide control room/operator interfaces



- architecture supports both
 streaming (Tracker, Calorimeter) and
 triggered (CRV) readout
- DAQ Servers handle data readout, event building and processing
- bidirectional front-end interface for fast control and readout
- large front-end buffers for uniform data transfer
- commercial DAQ hardware
- scalable...approximately 1 GByte/sec per DAQ server









Commercial (off-the-shelf) hardware


- DAQ server
 - 3U rack-mount computer
 - integrated DAQ and online processing
- Data Transfer Controller (DTC)
 - PCIe card with mid-range FPGA, memory, and an 8-port SFP+ optical interface
 - 1 GByte/sec readout bandwidth
- Event Building network
 - 48 port 10G Ethernet switch






Software based on art and artdaq

(a common DAQ & Online Processing framework developed for Mu2e and other current/future experiments)













Changes since CD-1

- changes in data rate estimates due to improved background simulations
- CRV data rate increases by a factor of 10-100 depending on thresholds
- switch to a triggered CRV readout (CRV data not needed for online analysis)
- rejection rate reduced from 99.8% to 99.0% to accommodate independent Calorimeter triggers

Value Engineering since CD-1

- switch to triggered CRV readout to compensate for higher background rates
- reduction in number of DAQ servers (48 → 36) to optimize front-end configuration, use higher performance servers


Performance

- Tests have been performed on the primary DAQ interfaces digitizer to readout controller (LVDS), readout controller to data
 transfer controller (optical link), and data transfer controller to DAQ
 server (PCIe) to verify bandwidth requirements
- Optimized version of the online Tracker filter meets processing requirement

Remaining work before CD-3

- Completion and test of a small (15%) DAQ Pilot system (~ 1 year)
- Test preliminary Calorimeter filter
- Test interfaces between DAQ and detector Readout Controllers (ROC)
- Evaluation of next generation Intel Phi processor

Organizational Breakdown







Quality Assurance

- DAQ system can be tested to 95% CL using simulated data, prior to Cosmic Ray test
- Full DAQ system is a scaled version of the Pilot system
- In-situ testing diagnostic features include monitoring of data link bit-error rate and optical power levels, memory and processor tests using large simulated data sets

Risks

- Insufficient manpower for DAQ software (TRIG-128)
 - Cause: uncosted labor resources are not available for scheduled tasks (note: Fermilab, CalTech, UFlorida, & Yale will contribute, collaboration is actively recruiting additional resources)
 - Mitigation strategy: use additional costed labor (~\$500k)
- Insufficient DAQ online processing (TRIG-130)
 - Cause: limited improvement in processor performance and filter optimization
 - Mitigation strategy: add 12 DAQ servers (~\$75k)
- Higher than expected data rates to DAQ (TRIG-131)
 - Cause: low thresholds in CRV
 - Mitigation strategy: add 6 DAQ servers, DTCs and optical links (~\$70k)





ES&H

- ES&H issues are minimal
 - High voltage (208 VAC, no exposed connections)
 - Class 1 lasers (eye safe)

Cost Table

WBS 9 Trigger & DAQ


Costs are fully burdened in AY \$k

	M&S			Estimate Uncertainty	% Contingency on ETC	Total
475.09.01 Project Management	3					
j		679				
475.09.02 System Design and Test						
475.09.03 Data Acquisition	313	1,528	1,841	463	32%	2,304
475.09.04 Data Processing	301	555	856	208	29%	1,064
475.09.05 Controls and Networking	123	461	. 585	155	31%	740
Risk Based Contingency				273		273
Total	741	4,076	4,816	1,243	38%	6,059






Cost Breakdown




- 475.09 Trigger & DAQ 475.09.01 Project Management
- 475.09 Trigger & DAQ 475.09.02 System Design and Test
- 475.09 Trigger & DAQ 475.09.03 Data Acquisition
- 475.09 Trigger & DAQ 475.09.04 Data Processing
- 475.09 Trigger & DAQ 475.09.05 Controls and Networking



Cost Breakdown




Quality of Estimate







Resources by FY






Major Milestones

- Completion of Pilot System development for Data Acquisition, Data Processing, and Controls and Networking tasks (6/11/2015)
- Completion of Production System development for Data Acquisition, Data Processing, and Controls and Networking tasks (7/27/2018)
- Cosmic Ray Test (final integration with detectors and full readout test) (10/12/2020)

Schedule



Summary

- Based on initial testing of DAQ components, we are confident that the system throughput and processing will meet requirements.
- Currently at beginning of DAQ Pilot phase development, expected to take approximately 1 year.
- Pilot phase goal is a small (6 server) functioning DAQ system, with the basic features necessary to communicate with detector readout controllers, buffer and exchange event data between servers, and measure online filter performance.
- 80% of effort is in firmware/software development...this provides great flexibility, but is also difficult to estimate. Estimates are based on a top-down approach using recent experiments of similar complexity.
- Costs are reduced through the use of commercial hardware and a common software framework.

