




U.S. DEPARTMENT OF
ENERGY Office of
Science

Mu2e Cosmic Ray Veto

8.7 Module Fabrication


Craig Group
Level 3 Manager
July 8, 2014




Outline

- Organizational Breakdown
- Overview of Module Production Factory
- Quality Assurance
- ES&H
- Schedule and Remaining Work Before CD3
- Cost Table
- Cost Breakdown
- Quality of Estimate
- Labor Resources by Fiscal Year
- Schedule

Organizational Breakdown



Organizational Breakdown






WBS Dictionary for 8.7

- **475.08.07.01 Design and Fabricate Assembly Station:** This set of activities cover the design and fabrication of the equipment needed to fabricate the counters and modules.
- **475.08.07.02 Assembly Station Quality Assurance Design and Fabrication:** This set of activities cover the design and fabrication of the quality assurance jigs needed to test the counters and modules during and after assembly.
- **475.08.07.03 Fabrication of Module Parts:** This task covers the fabrication of the all the parts needed for the assembly of the counters and the modules, save the extrusions, fibers, photodetectors, and electronics.
- **475.08.07.04 Module Production, Testing, and Shipping:** This task covers all aspects of the counter and module assembly, testing, and shipping. It includes non-working mechanical prototype modules, pre-production modules, and production modules.
- **475.08.07.05 Breakdown of Module Factory:** This task covers the decommissioning of the module fabrication factory.

CRV Fabrication Overview

- Fabrication: assemble scintillator extrusions, wavelength-shifting fibers, and photodetectors into working modules.
- QA at each assembly step – large component of labor effort.
- 82 modules of 7 different sizes, as well as 9 spare modules.
- Scintillator lengths range from 0.9 m for the cyro modules to 6.6 m for the extra-long modules.
- Module widths for 16 (8) counters for normal (narrow) width modules is ~80 cm (40 cm).
- The “extra long” modules weigh about 2000 lbs

Reminder: Basic CRV Module




Overview (continued)

- Factory space will be rented near UVA.
- Materials shipped to UVA factory.
- Di-counters assembled with fiber, manifolds and SiPMs. Di-counter QA performed.
- Modules assembled from di-counters, epoxy, and aluminum sheets. Module QA performed.
- Modules crated and shipped to Fermilab.
- During peak production factory will be capable of producing 6 modules per month.

Note: we have a pre-production phase for the first 10% of the modules in which we allow that module production will proceed at 50% of the peak rate.


Module Factory

5000 ft²




Module Factory

5000 ft²




Module Factory

5000 ft²




Module Factory

5000 ft²




Module Factory

5000 ft²



Module Factory

5000 ft²



Required Space Estimate


| Required space | |
|-------------------------------|----------------------------|
| Storage/receiving | 1500 ft ² |
| Counter assembly/QA | 900 ft ² |
| Module assembly | 400 ft ² |
| Module QA test stand | 400 ft ² |
| Crating/shipping | 1000 ft ² |
| Total production space | 4200 ft² |
| Target space | 5000 ft² |

Ideally, we would have 5000 square feet of space in the module factory. (Less space would be possible, but would stretch the fabrication timeline)

Factory Notes


- Plan is to rent industrial space. ~\$1/ft²/month
- Discussion ongoing at UVA to find space on campus.
 - May provide an opportunity to reduce cost.
- All major components will be on locking casters to maximize flexibility of available space.
- Counter Assembly Tables and Module Assembly Tables will be moved to vent hoods for epoxy application steps.

Epoxy




- Modules held together only by epoxy
 - Plastic-aluminum bond is critical!
- Devcon HP250 – 400 ml cartridges (will use about 2000 cartridges)
- Plan to spread the epoxy “manually”
 - Dispenser and squeegee

Counter Assembly Table



- Shelf heights adjustable to working level.
- One shelf to assemble di-counters for each module layer
 - Epoxy di-counter pairs (overnight cure required)
 - Di-counter pairs cut to length with chop saw
 - Install fiber
 - Epoxy fiber guide bar (3 day cure required for FGB)
 - Fly cut FGB with fibers (one 0.015" trim cut and one 0.004" polish cut)
 - Fiber QA to test cut/polish (details in QA section)
 - Digital photo with 80x microscope
 - Fiber light transmission tester
- Bar-counter interface will be painted using black latex-enamel paint.

Di-counter Assembly



Chow Saw and Fly Cutter



To be modified with cross-slide stage for 36" travel so that full module layer can be cut at once.

Module Assembly Table




Simple table for module assembly

- Base: two heavy-duty machine tables with locking casters
- 80/20 frame attaching the two tables
- 2"x6" lumber frame and $\frac{3}{4}$ " plywood top
- The table has guides (module glue jig) to locate the counter pairs onto the aluminum absorber plates and to offset counter layers 10 mm from each other
- Vacuum lifter (with crane or gantry hoist) required for handling aluminum sheets and completed modules

Module Assembly Steps

- Aluminum cover (0.032"-thick) placed on table and epoxy spread to a uniform ~0.010" thickness (or 0.005" on each interface).
- Di counters are placed and spaced carefully so that edge counters are aligned with aluminum edges (8 di counters for normal-width module) -- see next slide for spacing estimate.
- Epoxy spread to a uniform ~0.005" thickness on di-counter layer
- AL absorber (0.250"-thick) placed onto the wet di-counter layer and positioned using the module glue jig.
- Repeat previous steps to build up 4 layers.
- Aluminum cover (0.032"-thick) is placed onto the wet di-counter layer and positioned with using the module glue jig.
- A plywood weight is placed on top to provide light contact pressure while curing (3 day cure required).

Test Beam Prototype Assembly




QA at the Fabrication Factory

- Counters:
 - Digital photon with 80x microscope
 - Fiber light transmission tester
- Modules:
 - PE yield measurement with CSC cosmic ray test stand
- QA checklist in QAP (DocDB 4165 – attachment 3)


Counter QA

- Counters can't be “unglued”, so QA is critical at the counter assembly step.
- Optical QA via digital image with 80x microscope.
- Image will be stored for each fiber cut.






Counter QA

- Counters can't be “unglued”, so QA is critical at the counter assembly step.
- Fiber tester: to be designed/fabricated by Dean Shooltz who built similar devices for NOvA.




Module QA: CSC Test Stand

- A CSC prototype is being assembled that will be converted into a cosmic ray test stand for module QA.
- Winding complete
- HV/noise tests ongoing



Test Stand Plan

- 1x1 m² active area
- Test stand will employ:
 - two multi-layer CSCs
 - gas system (Ar-CO₂)
 - Trigger: large scintillation counter (for minimum energy confirmation)
 - Readout electronics
- PE yeild will be measured from each module end
- 10-hour runs will yield several hundred thousand cosmic ray muons
- Test procedure will be optimized using module prototypes
- Chamber commissioning is going well...



Cathode strips register signal from cosmic-ray trigger.

QA Checklist



Mu2e CRV Module Factory Quality Assurance Program
Rev-2- 04/04/2014

Mu2e DocDB: 4150



UNIVERSITY
OF VIRGINIA


ATTACHMENT 3: CRV Module Factory QA Checklist:

Summary of additional QA checks:

- Scintillator extrusions - dimensional tolerances, defect free.
- Devcon HP 250 Epoxy - Glue test protocol, peel, shear, durability, hardness.
- Fiber guide bars (FGB) - dimensional tolerances, defect free.
- Counter motherboards (CMB) - dimensional tolerances, electronics tests.
- SiPM mounting blocks (SMB) - dimensional tolerances, defect free.
- Front end boards (FEB) - dimensional tolerances, electronics tests.
- Aluminum absorbers - dimensional tolerances, defect free.
- Light-tight paint and bumpers - defect free.
- ...

Safety at the Module Factory

- Safety plans are also covered by the QAP (DocDB 4150)
- There are several hazards in the module factory: high voltage, compressed gas, epoxy fumes, power and other sharp tools...
- All employees must study and sign the UVA standard operating procedures (SOP) document to begin work.
- Each employee will be trained in all current OSHA, Fermilab and UVA ES&H safety guidelines for identifying, mitigating and managing all relevant hazards at the job site.
- Operation of the chop-saw or fly-cutter or access to the machine shop will require UVA machine shop training.
- All epoxies contain some toxic chemicals, engineering controls will be employed to mitigate occupational exposure levels ...



Epoxy Fumes

- A similar design will be adapted for the Counter Assembly Tables.
- Devcon HP250 **does not contain MDA** which is a known carcinogen often found in epoxy. We chose a “safer” epoxy.
- However, it **does contain a suspected carcinogen, MBCHA, and other known toxins.**
- A prototype ventilation system will be tested via air sampling while building prototype modules to ensure air contaminants are mitigated to acceptable levels.

Personnel at the Module Factory

- **Technician Leader:** Factory design, prototyping, factory management (QA/safety), documentation, fabrication, ...
- **Mechanical Technician:** Assist in moving into factory, building assembly stations, and fabrication efforts.
- **Undergraduates:** tedious tasks in the module factory: cleaning/de-burring components, spreading epoxy, QA checklists, ...
- **Uncosted graduate students, postdocs, and faculty:** commission the QA tools, establish metrics, and analyze data from QA measurements.


Personnel at the Module Factory

- About 7300 total hours of effort to fabricate, pack, and ship 91 modules to Fermilab.
- ~80 hours of fabrication effort per module.
- ~54 hours of tech effort per module for fabrication.
- With full-time effort, about 6 modules per month can be produced in the module factory.
- Example work flow in backup slides and DocDB 4197.

Prototype Plan



- Past experience with “test beam” prototype
- Prototyping is critical for understanding ideal tooling and required tech hours



Prototype Plan

- Mechanical prototype (late FY14 / early FY15):
 - 4.7 m long; No electronics
 - Time and motion studies; handling modules
 - Test/practice epoxy application
- Two short (cryo-length) electronics prototypes (FY15):
 - Outfitted with electronics
 - Study mounting techniques
 - Test bed for electronics
- Two “pre-production” prototypes (FY16):
 - Outfitted with electronics
 - Production scintillation and fiber
 - Shipped to Fermilab to test installation and mounting procedures

Shipping

- Plan for ~9 shipments (~10 modules per shipment)
- Plan for 2 modules per crate
- Crates will weigh about 4000 lbs
- Crates will be assembled at a local job shop
- Will consider shipping crates back to UVA.
- Crates designed to be stackable.




Shipping

- Crates will be loaded via fork lift
- Need access from side of truck
- Flatbed truck with tarps possible, but “Conestoga 2” seems ideal -- sliding tarp system:



Schedule and Remaining work before CD3




- Complete fabrication of prototype assembly stations
- Complete fabrication of cosmic ray test stand
- Produce “mechanical” prototype module
- Produce “short electronics” prototype module
- Produce “pre-production” prototype
- Test “pre-production” prototype
- Design and fabricate “pre-production” prototype shipping crate
- Ship “pre-production” prototype to Fermilab

Schedule

Cost Table (Base Cost – AY k\$)

| | M&S | Labor | BAC | Estimate Uncertainty | % contingency on ETC | Total |
|--|-------------|------------|--------------|-------------------------|----------------------------|--------------|
| 475.08.07 Actuals | 93 | 1 | 96 | | | 96 |
| 475.08.07.01 Design and fabricate assembly station | 161 | -- | 161 | 61 | 38% | 222 |
| 475.08.07.02 Assembly Station Quality assurance design and fabrication | 53 | 15 | 68 | 27 | 40% | 96 |
| 475.08.07.03 Fabrication of Module Parts | 447 | -- | 447 | 92 | 21% | 539 |
| 475.08.07.04 Module Production, Testing, Shipping | 680 | -- | 680 | 272 | 40% | 952 |
| 475.08.07.05 Breakdown of Module Factory | 23 | -- | 23 | 10 | 43% | 33 |
| Grand Total | 1460 | 528 | 1,476 | 462 | 34% | 1,938 |


Cost Breakdown (Base Cost – AY k\$)



Labor

Materials

Non-FNAL Labor



Actuals

08.07.01


08.07.02

08.07.03


08.07.04

08.07.05

Quality of Estimate (Base Cost – AY k\$)



Labor Resources by FY



Major Milestones

- Approve mechanical prototype
- Approve pre-production prototype
- Production modules complete
- Module Factory Breakdown complete

Summary

- Factory plan is complete and prototyping is ongoing...
- All factory components on castors -- flexibility is important-- location won't be finalized until rental space acquired.
- Prototype assembly is critical for time and motion studies.
- The cost and schedule are well understood, with contingency estimated to reflect estimate uncertainty.
- The CRV fabrication activity is ready for approval of its performance baseline.

Supplementary Material

Cost Table v2 (UVA effort counted in labor)

| | M&S | Labor | BAC | Estimate Uncertainty | % contingency on ETC | Total |
|--|------------|------------|--------------|-------------------------|----------------------------|--------------|
| 475.08.07 Actuals | 93 | 3 | 96 | | | 96 |
| 475.08.07.01 Design and fabricate assembly station | 104 | 57 | 161 | 61 | 38% | 222 |
| 475.08.07.02 Assembly Station Quality assurance design and fabrication | 35 | 34 | 68 | 27 | 40% | 96 |
| 475.08.07.03 Fabrication of Module Parts | 413 | 34 | 447 | 92 | 21% | 539 |
| 475.08.07.04 Module Production, Testing, Shipping | 297 | 383 | 680 | 272 | 40% | 952 |
| 475.08.07.05 Breakdown of Module Factory | 6 | 17 | 23 | 10 | 43% | 33 |
| Grand Total | 948 | 528 | 1,476 | 462 | 34% | 1,938 |

Work flow at module factory


| Sunday | Monday | Tuesday | Wednesday | Thursday | Friday | Saturday |
|-----------------|---|---|---|---|--|-----------------|
| | | | 1 di-counter | 2 fiber di-counter | 3 cure fiber di-counter | 4 cure cure |
| 5 cure cure | 6 flycut cure fiber | 7 fiber QA flycut cure | 8 manifold fiber QA cure | 9 transition manifold cure transition | 10 di-counter transition flycut module transition | 11 cure |
| 12 cure | 13 fiber di-counter fiber QA cure module | 14 cure fiber manifold transition cure transition | 15 cure cure transition transition cure CR test stand | 16 cure cure di-counter module cure Crate (1) | 17 flycut cure fiber cure transition transition | 18 cure |
| 19 cure | 20 fiber QA flycut cure CR test stand | 21 manifold fiber QA flycut transition Crate(2) | 22 transition manifold flycut transition CR test stand | 23 di-counter transition fiber QA module transition Crate(3) | 24 fiber di-counter manifold cure module | 25 cure cure |
| 26 cure cure | 27 cure fiber transition cure transition | 28 flycut cure transition transition CR test stand | 29 fiber QA cure di-counter module transition transition Crate(4) | 30 manifold cure fiber cure CR test stand | 31 transition flycut cure cure transition Crate (5) | 1 cure |

Month 1
(DocDB 4197)

| Day of the Week | | |
|-----------------|-----|-----|
| # | | |
| CT1 | CT2 | CT3 |
| MT2 | | MT2 |
| CR test stand | | |
| Crate/Ship | | |

| |
|-----------|
| Module 1 |
| Module 2 |
| Module 3 |
| Module 4 |
| Module 5 |
| Module 6 |
| Module 7 |
| Module 8 |
| Module 9 |
| Module 10 |
| Module 11 |
| Module 12 |
| Module 13 |
| Module 14 |

Work flow at module factory



Module 12 crated in less than 2 months!

Month 2

Mu2e

| Day of the Week | | | |
|-----------------|---------------|-----|-----|
| # | CT1 | CT2 | CT3 |
| | MT2 | | MT2 |
| | CR test stand | | |
| | Crate/Ship | | |

- Module 1
- Module 2
- Module 3
- Module 4
- Module 5
- Module 6
- Module 7
- Module 8
- Module 9
- Module 10
- Module 11

Prototype Counter Assembly Table



Up



M


Down



Mu2e

Module End Caps

Simple “Z bar” design.



To protect the sensitive module readout ends during transportation and handling.

Fly Cutter With 36" Slide...

