




Mu2e Director's Review – Breakout Conventional Facility Mechanical

Emil Huedem 7/8/2014



Requirements

- Documented in Docdb# 1088 "CF Requirements"
- Basic building utilities (DWS, SAN, NAT GAS, ICW)
- High Bay
 - HVAC heat load to air (~35KW)
 - No ODH; no tight temp stability reqmnt; 68Fmin; 78F max
- Power Supp Room,
 - HVAC heat load to air (~50KW)
 - ODH ventilation 6,300 cfm; no tight stability reqmnt; 68Fmin; 85F max
- DAQ room
 - Heat load to air (~49 kw); No ODH
 - >20%RH min to 60%RH max






Requirements...continuation

- Lower DS
 - minor heat load to air (~16 kw)
 - ODH ventilation 7,000 cfm; no tight stability reqmnt; 68Fmin; 80F max
- Absorber, PS,
 - Dry outside air ventilation
 - Decay airflow limit ~900cfm; ODH ventilation 7,000cfm
- Remote Handling /Extinction Monitor
 - Ventilation air (part of supply to absorber)
 - Currently no ODH ventilation reqmnt
- Misc equipment (tracker cooling skid, dehumidifier, vac pump)
 - Chilled Water taps
- Misc spaces (mech room, planning room, entry)=
 - HVAC except for mech rm






Design Building grade level















Design Lower level PS







Design CHW Piping



Summary

- Design is complete. Commissioning is included with the project.
- Upper and lower spaces will be left open to each other for a while, (duration of years after the CF project is done and before the experiment begins). The current design includes control sequence for pressurization & can be simulated during commissioning but the pressurization will be highly dependent on proper sealing of the multiple penetrations, chases and spaces.
- ODH sensors and actuation of the ODH system will be by WBS 2 (accelerator)

