

# Introduction to NBI + J-PARC hadron hall experiences

Kazuhiro Tanaka

Institute of Particle and Nuclear Studies, and  
Particle and Nuclear Physics Division, J-PARC,  
High Energy Accelerator Research Organization,  
KEK

FIRST INTERNATIONAL WORKSHOP ON  
NEUTRINO BEAM INSTRUMENTATION  
DEDICATED FOR LONG BASELINE EXPERIMENT

High Energy Accelerator Research Organization(KEK), Tsukuba,

26-29 July, 1999

本年7月26日から29日まで、ニュートリノビーム技術に関する国際ワークショップを開催します。7/26(月) 午後に、ワークショップの開会式を兼ねて、FNAL及びCERNの長基線ニュートリノ振動実験の現状報告と、KEKでの実験の「物作り」と「物理」の両面からの報告会を開催します。会場は3号館1階の会議室です。みなさまどうかご出席ください。



STATUS OF THE LONG BASELINE NEUTRINO OSCILLATION EXPERIMENTS  
AT FNAL, CERN AND KEK

July 26 (Mon) Afternoon: 13:30 - 16:30 pm  
Opening Open Session at the KEK Large Meeting Room  
(at the first floor of the Building No.3.)

Program

Welcome address by the KEK Director General [H. Sugawara(KEK)]  
A status report of the NuMI/MINOS project at Fermilab [Jorge G. Morfin (FNAL)]  
The CERN Neutrino beam towards Gran Sasso (NGS)[K. Elsener]  
Status at KEK: Instrumentation [K. H. Tanaka (KEK)]  
Status at KEK: Physics [M. Sakuda (KEK)]


# NBI1999

## The first one of the series.

In order to celebrate  
the first beam for  
K2K experiment!



K2K: March 1999,  
First beam.

# Neutrino Beam Facility for K2K






# Horns, Target & Decay Volume



- Two Horns (Collector & Reflector).
- Built-in Target in Collector
- 250kA Operation
- 10M Excitation with 30mm $\phi$  Target
- Transformer near-by
- 200m Decay Volume filled with He.



# NBI1999



- from CERN-CNGS

- Konrad Elsener

- Valeri Falaleev

- from FNAL-NuMI

- Gorge Morfin

- James Hylen

# At That Time.....

- FNAL
- NuMI Project
- 120GeV Main Injector
- Several Hundred kW Beam Power
- Long Experience of Neutrino Beams

- CERN
- CNGS project
- 400GeV SPS
- Several Hundred kW Beam Power
- Long Experience of Neutrino Beams

- KEK
- K2K Project
- 12GeV 0.5 micro A – 5kW Beam Power
- No Experience of Neutrino Beams
- **SuperKAMIOKANE**



# FNAL, CERN and KEK





# NBI Over View

## (NBI2014)

- This workshop is a unique opportunity for physicists and engineers, working on conventional neutrino beams, to meet together, and discuss intensively their equipment in operating and planned experiments.
- Traditionally, this workshop focuses closely on the actual physical devices that compose neutrino beam facilities, with an emphasis on operating experiments and those at advanced phases of construction or planning.
- This will be the 9th instance of the workshop since the first in KEK in 1999; it has since rotated between the regions of Asia, Europe, and the United States.

# The emphasis of the workshop


- The emphasis of the workshop is detailed descriptions of equipment, tests and results, and in particular, on challenges in the design.  
The maniac discussion is always welcome.
- Not for one brilliant success, let's discuss hundred failures before the success.
- Let's report serious mistakes in order to avoid further mistakes of the same kinds.
- Let's make straight/frank discussions for future great success!

# For these purposes



- No write ups and/or no proceedings will be published.
- Only a set of copies of presentations will be kept in the WEB site of NBI.
- Let's reserve one session for real discussion for the construction of real things!





## Horn Flexible Feeder Trouble ( $8.5 \times 10^5$ excitations)





## Horn Cooling Water Pipe Trouble ( $5 \times 10^5$ excitations)





# 1st Horn Target Rod (20mm $\Phi$ ) Break ( $1.9 \times 10^6$ excitations)






Cross Section  
of Collector





Power Supply  
for Horns






## Horn Strip Line Break ( $4.3 \times 10^6$ excitations)



## Transformer Flag (primary side) $25.8 \times 10^6$ Excitation




# On Horns, what we learned are...

## (at NBI2000)

- Horn can work as designed in both mechanically and electrically.
- We should pay attention more and more to peripherals, which can break as designed.
- Test excitation in the actual position should be as many as possible.
- Never compromise with Physicists.
- Sufficient time, money, manpower for R/D and for operation, maintenance.
- Believe yourself.


# For the Safety Construction & Maintenance (NBI2002)



- Often our high-class people says that we should learn Egyptian Technology to save MONEY.
- This may be wrong. We need wider space & Crane to handle highly radioactive beam line elements!




# J-PARC hadron hall experiences






# Hadron Experimental Facility (Current Layout)




# Hall



$\Xi$  hypernuclei  
 $\Lambda\Lambda$  hypernuclei  
 $\Xi$ -atomic X-rays  
 $\Lambda$  hypernuclear  $\gamma$  rays  
Neutron-rich  $\Lambda$  hypern.  
Pentaquark  $\Theta^+$  search  
 $K^-pp$  bound state

Hyp. weak decay ( $A=4$ )  
Hyp. weak decay ( $A=12$ )  
 $\pi$  Double charge exch.  
 $\omega$  mesonic nuclei  
 $\Sigma p$  scattering





K1.8

$K^0_L$  rare decays

Hadron mass in nuclei  
Nucleon quark structure

K1.8BR

$K^-pp$  bound states  
 $K^-$  atomic X rays  
 $\eta$  mesonic nuclei



K1.1

K1.1BR

T violation in  $K^+$  decay  
Universality in  $K^+$  decay  
 $\Theta^+$  study by  $K^+n$  scattering

$\Phi$  mesonic nuclei  
 $\Lambda$  hypernuclear  $\gamma$  rays  
 $\Sigma$ -nuclear systems  
YN scattering  
 $\Theta^+$  hypernuclei

High momentum line

30~50 GeV  
primary beam


Approved (stage-2) / (stage-1) / proposed, LOI

$\mu$ -e conversion search



# New Primary Proton Beam Line

- New primary Proton Beam Line




## ■ High-momentum Beam Line

- Primary protons ( $\sim 10^{10} - 10^{12}$ pps)
- E16 (phi meson) is considered to be the first experiment.
- Unseparated secondary particles (pi, ...)
- High-resolution secondary beam by adding several quadrupole and sextupole magnets.

## ■ COMET

- Search for  $\mu$  to e conversion
- 8 GeV, 50 kW protons
- Branch from the high-momentum BL
- Annex building is being built at the south side.

# High-p Line and E16 Spectrometer





E16 will have 100 times more statistics than the KEK-PS E325 experiment with the new beam line and the spectrometer



# Outline of the Accident


11:55 on May 23

- An abnormal proton beam was injected to the gold target.
- The target heated up to an extraordinarily high temperature.
- Radioactive material was released from the target.
- The radioactive material was leaked into the HD hall.
  - Workers were exposed to radiation.
- The radioactive material was released to the outside of the radiation controlled area and to the environment outside of the HD hall.




# Abnormal Beam

- At around 11:55 on May 23, the power supply system of a special magnet in the 50 GeV Synchrotron malfunctioned.
  - $2 \times 10^{13}$  protons were extracted in a very short period of 5 milliseconds, while in normal operation  $3 \times 10^{13}$  protons should have been slowly extracted over 2 seconds.







# Target Temperature (Simulation Results)



temperature






## Observed Au Target




Au target observed from the downstream: a 1mm in diameter hole was seen at the downstream end.



Traces of sprayed-out melting gold at the Be window at the downstream




These observations well match with our simulation results.




# Concept of the improvements of the Hadron facility

## Before the improvements



## After the improvements





# Hadron Hall – facility renovations

## HH ventilation system with a monitor and a stack

(authorized on 2014.March.19,  
inspected on April.22 )

exhaust duct



stack




filters



ventilator  
(10,000 m<sup>3</sup>/h)

Truck yard  
( tent )




South exhaust fans: removed and sealed  
(2014.January.10)

# Construction at the South Area






# Hadron Hall – renovations in the Experimental Hall






# Hadron Hall – renovations in the Experimental Hall



**improving air-tightness  
of Primary Beam Line**



**side view**

Gas barrier sheet  
Protective sheet  
Rubber






# South Area of the Hadron Hall




# Scheme of the target system





# Structure of New Target chamber



Circulation System

- Water: existing

- Gas: new

Since the beam windows are always exposed to a primary beam directly, we designed the windows to keep their soundness even in the case of 5- $\mu$ s pulse beams.



\* 5- $\mu$ s = revolution of Main Ring







# Structure of New Target




Cross-sectional view

\*Gold, copper, and stainless-steel are bonded by **HIP (Hot Isostatic Pressing)**

## Improvements


- Gold is partially sunk in copper block to avoid instantaneous separation of gold from copper.
- Cooling pipes are located closer to gold for efficient cooling.
- Width of gold is increased (6 => 15) for wider beam.
- 2-headed structure for quick and remote replacement of target.





# Result of Thermal Analysis of Target (50kW)

In normal operation (2-sec extraction)



Bonded interface 61 MPa

beam

STEP=4  
SUB =1  
TIME=2  
SEQV (AVG)  
DMX =.781E-04  
SMN =22319  
SMX =.669E+08

22319  
.420E+07  
.838E+07  
.126E+08  
.167E+08  
.209E+08  
.251E+08  
.293E+08  
.335E+08  
.377E+08  
.418E+08  
.460E+08  
.502E+08  
.544E+08  
.586E+08  
.627E+08  
.669E+08


sold-target0108-115p (62.4T,Au0-8,fD2.5,1.0)-double @ 30GeV-6.24e13ppp @ slit6

Design margin: 2.1

In accident (5-msec extraction)

max. 2832 °C

\*Latent heat and radiation cooling are not included.



Bonding strength:  
171MPa(@25°C)  
137MPa(@200°C)  
76MPa(@400°C)  
linear interpolation:  
129MPa(@225°C)



## Milestone



Repair tasks have been underway to recover and improve the hadron experimental facility.

- ~ End of 2014
  - Target replacement → Now
  - Sealing of the primary beam line
  - After measures are completed, we will ask the authorities and local governments to allow us to resume the operation.



# Major Events up to now

## 2013

- May 23 The accident at the hadron facility
- July 19  $\nu_e$  appearance physics finding
- September 26 Report to MEXT on the accident
- December 8 The gold target observation
- December 26 Local government's approval

## 2014

- January 17 Linac 400 MeV energy upgrade
- February 17 MLF restarted operation at 300 kW
- April 28 MR started test
- May 26 Neutrino restarted experiment

Repair tasks have been underway to recover and improve the hadron experimental facility.