

# MICE Step IV


*Milorad Popovic*  
*Fermilab*

*NuFact 2015*


# Muon Ionization Cooling

- Muon Ionization Cooling is the key technology required to be able to create useful Beam of Muons for NF, MC, etc.

## Principle



## Practice



Small  $\beta_{\perp} \Rightarrow$  strong focusing

$$\frac{d\varepsilon}{dz} \approx - \frac{\varepsilon}{E_{\mu} \beta^2} \frac{dE_{\mu}}{dz} + \frac{\beta_{\perp}}{2m\beta^3} \frac{(13.6 \text{ MeV})^2}{E_{\mu} X_0}$$


Ionization:  
cooling term

Multiple scattering:  
heating term


# Collaboration

## MICE is International Collaborative Effort

- Of more than 80 Physicists & Technical Professionals
- From 27 Institutions:
- 9 Countries (Bulgaria, China, Italy, Japan, Nederland, Serbia, Switzerland, UK, USA)
- 3 Continents (North America, Europe and Asia)




# MICE, demonstration of ionization cooling




MICE home is RAL and it is approved to:

- **Design, build, commission and operate a realistic section of cooling channel**
- **Measure its performance in a variety of modes of operation and beam conditions**
  - Results will allow Neutrino Factory [and Muon Collider] complex to be optimized
- **Normalized transverse emittance: 0.1%**
  - Requires selection of 99.9% pure muon sample




# MICE Muon Beam





# Step IV; Study of factors that affect cooling (materials, momentum & emittance)

7th February 2015



## Emittance:


Varied through MICE Muon Beam optics and diffuser settings

## Material:






Absorber change (LH2; LiH);

$\rho$ ,  $E$  and  $\beta$ :

Vary beam momentum, optics




# Final Installation Sequence, Step IV





# Step IV installation






# Status as of August 5th



# Step IV: Time Table, Operations & Status

| ISIS Cycle | Date From | Date To   | 1 Jun 15 | 1 Jul 15 | 1 Aug 15 | 1 Sep 15 | 1 Oct 15 | 1 Nov 15 | 1 Dec 15 | 1 Jan 16 | 1 Feb 16 | 1 Mar 16 | 1 Apr 16 |
|------------|-----------|-----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| 2015/01a   | 2 Jun 15  | 5 Jul 15  |          |          |          |          |          |          |          |          |          |          |          |
| 2015/01b   | 14 Jul 15 | 24 Jul 15 |          |          |          |          |          |          |          |          |          |          |          |
| 2015/02    | 8 Aug 15  | 16 Oct 15 |          |          |          |          |          |          |          |          |          |          |          |
| 2015/03    | 3 Nov 15  | 18 Dec 15 |          |          |          |          |          |          |          |          |          |          |          |
| 2015/04    | 14 Feb 16 | 1 Apr 16  |          |          |          |          |          |          |          |          |          |          |          |

- **Cycles 2015/01a,b (March/July 2015):**
  - Data taking interleaved with commissioning
  - Calibration
  - Field-off data for mechanical alignment
  - Data with field on (100A) in downstream solenoid to check magnetic axis



# Magnet Status




- . Upstream solenoid:
  - . Issues identified in initial commissioning addressed
  - . Commissioning coo-down and commissioning restart 10 August 2015
- . Downstream solenoid:
  - . Trained to 203A (operating current 283A);
  - . Training will resume late August 2015
- . Focus coil:
  - . Thermal issue identified during initial training of downstream solenoid
  - . Warm-up to allow diagnosis and repair underway



# Absorber for Step IV

- Safety review of LH2 system Jan15:
  - Part of safety “sign-off to operate Step IV” process
  - Required:
    - Additional safety-window burst tests; and
    - Enlarged emergency H<sub>2</sub>-gas evacuation line
- Status of implementation:
  - Burst-tests complete; satisfactory
  - Enlarged relief line agreed and installed
- Next steps:
  - Demonstrate satisfactory operation with He gas
  - Obtain permission to operate with LH<sub>2</sub>
  - H<sub>2</sub> safety review scheduled for 6Sep15




All detectors are now  
commissioned and are  
being used in the  
alignment/magnetic axis  
studies

# Conclusions

- Muon ionization cooling is the key technology required to make Neutrino Factories and Muon Colliders viable
- Significant investment, effort (and patience) from all the funding agencies have been paramount in achieving the construction of the Muon Ionization Cooling Experiment at RAL
- MICE is ready (almost) to commence its Step IV data taking in order to observe reduction of transverse normalised emittance and characterise the parameters that affect cooling performance





# Conclusions



The End