




---

## Mu2e CD-2 Review

Mark Bowden

TDAQ L2 Manager

10/21/2014



# TDAQ Team

---

- Mark Bowden – L2 Manager, L3 Manager (System Design & Test)
  - 31 years
- Kurt Biery – L3 Manager (Data Acquisition), Department Head - Scientific Computing Division, Real-time Systems Engineering
  - 16 years
- Ryan Rivera – L3 Manager (Data Processing, Controls & Networking), Group Leader - Real-time Systems Engineering, Detector Electronics
  - 11 years

Greg Deuerling, Rick Kwarciany, Ron Rechenmacher, Mike Wang

# Requirements

---


- Requirements for the DAQ are described in mu2e-docdb 1150.
- Collect and assemble data from the Tracker (~13 GBytes/sec) and Calorimeter (~8 GBytes/sec) for online analysis.
- Provide online filtering to reduce data Tracker & Calorimeter data volume by  $\geq 99\%$ .
- Combine with data from CRV, Extinction and Target Monitors for transfer to offline storage.

# Requirements

---

- Provide global timing synchronization
- Provide fast and slow control networks
- Provide connections to offline storage and site networking
- Provide control room/operator interfaces

# Design



- architecture supports both streaming (Tracker, Calorimeter) and triggered (CRV) readout
- DAQ Servers handle data readout, event building and processing
- bidirectional front-end interface for fast control and readout
- large front-end buffers for uniform data transfer
- all commercial DAQ hardware
- scalable... 1 GByte/sec per DAQ server

# Design



Commercial (off-the-shelf) hardware

- DAQ server
  - 3U rack-mount computer
  - integrated DAQ and online processing



- Data Transfer Controller (DTC)
  - PCIe card with FPGA, memory, and 8-port SFP+ optical interface
  - 1 GByte/sec readout bandwidth




- Event Building network
  - 48 port 10G Ethernet switch


# Design

## Software based on *art* and *artdaq*

(a common DAQ & Online Processing framework developed for Mu2e and other current/future experiments)




# Design



- interface firmware & protocols
- prototype development

## Detector Readout Controllers





# Design


Several algorithmic and compiler optimizations were applied to the reference Tracking filter to achieve a speedup of almost 30X.

Optimization stage for MakeStereoHits	Compiler	Execution Time (ms)	
		Xeon (speedup)	Xeon Phi (speedup)
Reference	gcc 4.4.7	132	-
Modified algorithm	gcc 4.4.7	6.67 (19.8x)	-
Modified algorithm	icc 14.0.1	2.04 (3.33x)	-
Additional optimizations	icc 14.0.1	1.88 (1.08x)	30.4

Optimization stage for FlagBkgHits	Compiler	Execution Time (ms)	
		Xeon (speedup)	Xeon Phi (speedup)
Reference	gcc 4.4.7	14.2	-
Reference	icc 14.0.1	8.03 (1.77x)	123
Optimizations (mem align/layout)	icc 14.0.1	5.01 (1.60x)	37.7 (3.26x)
Optimizations (single precision)	icc 14.0.1	3.37 (1.49x)	24 (1.57x)

*Note : Speedup factors in parentheses are relative to previous stage*

# Design



# Design

---



Mu2e Remote Control Room - Wilson Hall, 1<sup>st</sup> floor West  
(shared use - LBNF, MicroBooNE, MINERvA, MiniBooNE, MINOS, Muon g-2, Mu2e, NOvA)

# Integration and Interfaces

---

- DAQ has external interfaces to the Detectors (control/timing, data), Accelerator (timing), other subsystems (slow controls), and site networking.
- Internal interfaces between servers, timing system and general-purpose networking.
- Internal and external interfaces identified and described in DAQ Interface document (docdb #1520).
- Participation in Electronics and Detector integration meetings.
- Formal sign-off between owners of all external interfaces as part of final design requirements.
- Interfaces understood and under control.

# Improvements since CD-1

---

- better data rate estimates due to improved background simulations
- switch to a triggered CRV readout to accommodate higher background rates and lower thresholds (CRV data not needed for online analysis)
- rejection rate reduced from 99.8% to 99.0% to allow independent Calorimeter filters

# Value Engineering since CD-1

---


- reduction in number of DAQ servers (48 → 36) to optimize front-end configuration, use higher performance servers

# Performance

---

- Tests have been performed on the primary DAQ interfaces - digitizer to readout controller (LVDS), readout controller to data transfer controller (optical link), and data transfer controller to DAQ server (PCIe) to verify bandwidth requirements
- Optimized version of the online Tracker filter meets processing requirement

# Organizational Breakdown





# Quality Assurance

---

- DAQ system can be tested to a high level of confidence using simulated data, prior to Cosmic Ray test
- Full DAQ system is a scaled version of the Pilot system
- In-situ testing - diagnostic features include monitoring of data link bit-error rate and optical power levels, memory and processor tests using large simulated data sets

# Risks

---

- 7 DAQ risks in risk registry
  - All risks mitigated to the extent possible
  - 3 threats
    - 0 high
    - 3 low / medium
  - 4 opportunities
- Detailed mitigation plans for all risks, documented in risk forms on docdb and linked from Risk Register (docdb #4320)
- All risks understood and under control.
- Details in breakout session.

# ES&H

---

- ES&H issues are minimal
  - High voltage (208 VAC, no exposed connections)
  - Class 1 lasers (eye safe)
  - no issues with radiation or magnetic field


# Cost Table

WBS 9 Trigger & DAQ


Costs are fully burdened in AY \$k

	Base Cost (AY K\$)			Estimate Uncertainty (on remaining budget)	% Contingency on (on remaining budget)	Total Cost
	M&S	Labor	Total			
475.09.01 TDAQ Project Management	3	1,162	1,165	118	23%	1,284
475.09.02 TDAQ System Design and Test		361	361	23	35%	385
475.09.03 Data Acquisition	317	1,513	1,831	459	37%	2,290
475.09.04 Data Processing	310	551	860	208	30%	1,068
475.09.05 Controls and Networking	125	458	583	154	34%	737
475.09.99 Risk Based Contingency				244	-	244
Grand Total	755	4,045	4,800	1,207	41%	6,007


# Cost Breakdown




# Cost Breakdown



# Quality of Estimate




# Resources by FY





# Resources by FY




# Major Milestones

---

- Completion of Pilot System development for Data Acquisition, Data Processing, and Controls and Networking tasks (July 2015)
- Completion of Production System development for Data Acquisition, Data Processing, and Controls and Networking tasks (January 2020)
  - last two years are optimization & debug at reduced level of effort
- Cosmic Ray Test (final integration with detectors and full readout test) (June 2020)

# Schedule



# Summary

---

- We have a design that fully satisfies the requirements
- Cost estimates for the DAQ are complete
  - 100% of the cost understood at the Preliminary Design level or higher
  - Risks are understood, mitigated to the extent possible and are under control.
- All interfaces are identified and defined
- Resource needs understood
- ES&H embedded into all aspects of the Project
- Responded to all recommendations from previous reviews
- DAQ is ready for CD-2