



# MICE Update

J. Pasternak



# Outline


- Introduction
- Preparations for Step IV
- MICE Demonstration of Ionization Cooling (MDIC)
- Summary




# Basics of ionization cooling



- Muons pass through absorber (liquid hydrogen) and accelerating cavity (RF).
- As a net effect transverse momentum is reduced.
- Strong focusing (using solenoids), low Z material as absorber and high RF gradient are necessary.
- It has never been demonstrated yet, but...
- It will be done in world's first muon cooling device - MICE (Muon Ionization Cooling Experiment)



MICE at STEP IV configuration




# Basics of ionization cooling (2)




LiH disk



LH2 system



Single Cavity Test Stand  
(SCTS) at MTA, FNAL



# Ionization cooling equation


Depends on the input beam

Depends on magnetic lattice

$$\frac{d\varepsilon}{ds} = \frac{-\varepsilon_n}{\beta^2 E} \left\langle \frac{dE}{dX} \right\rangle + \frac{\beta_t (13.6 \text{ MeV})^2}{2\beta^3 E m_\mu X_0}$$

$$\frac{p}{E} = \beta, E = \sqrt{p^2 + m_\mu^2}$$

Depends on material



# MICE goals


	Step IV	MDIC
<b>Study of properties that determine cooling performance</b>		
Cooling properties of LH <sub>2</sub> and LiH	<b>Yes</b>	<b>No</b>
Observation of $\epsilon_{\perp}^n$ reduction	<b>Yes</b>	Yes
<b>Demonstration of sustainable ionization cooling</b>		
Observation of $\epsilon_{\perp}^n$ reduction with re-acceleration		<b>Yes</b>
Observation of $\epsilon_{\perp}^n$ reduction with $\epsilon_{\parallel}$ “management”		<b>Yes</b>
Observation of $\epsilon_{\perp}^n$ reduction with $\epsilon_{\parallel} \oplus \mathcal{L}$ “management”		<b>Yes<sup>†</sup></b>

<sup>†</sup> Requires systematic study of “flip” optics.



# MICE – path towards a future


MICE, once successfully completed will enable for exciting future applications of cold muons



MICE at STEP IV configuration



## Neutrino Factory (NuMAX)




n Factory Goal:  
 $10^{21}$   $m^+$  &  $m^-$  per year  
within the accelerator  
acceptance


m-Collider Goals:  
126 GeV  $\Rightarrow$   
~14,000 Higgs/yr  
Multi-TeV  $\Rightarrow$   
Lumi  $> 10^{34} \text{cm}^{-2}\text{s}^{-1}$

High brightness beams  
for future precision experiments  
(rare muon decays, cLFV),  
applied science (muon  
spectroscopy),  
security applications, etc.


Share same complex

## Muon Collider






# Step IV configuration – to be operational in 2015-2016







# Step IV Schedule

Step IV	
1 Compressors ready for cooling channel tests	29th January 2015
2 Rack Room Complete	2nd February 2015
3 South side yoke material delivered	16th March 2015
4 South side return yoke installation complete	1st April 2015
5 North side yoke material delivered	28th April 2015
6 North side return yoke installation complete	14th May 2015
7 MICE Step IV installation complete	2nd June 2015
8 Combined magnet operational tests complete	11th August 2015
9 End of Step IV Data taking	1st June 2016


User Period	Start Date	End date
1	17/3/2015	24/4/2015
2	2/6/2015	24/7/2015
3	8/9/2015	16/10/2015
4	3/11/2015	18/12/2015
1	?	?

Construction ongoing,  
possible beamline pre-commissioning  
Magnet and beam commissioning

Physics

Physics

Physics



# Progress towards Step IV

- Spectrometer solenoids:

- ☐ Upstream:

- Tracker fitted; installed in MICE Hall; leak checked

- ☐ Downstream:

- Tracker fitted; installed in MICE Hall; leak checked

- Focus coil:

- ☐ FC1:

- Presently in MICE Hall; will be moved to R9 03Dec14

- ☐ FC2:

- Electrically/magnetically superior to FC1;

- Met acceptance criteria; field mapped; installed in Hall (03Dec14)

- Partial return yoke:

- ☐ Material ... Procurement complete;

- ☐ Installation of “below-floor” structures underway;

- ☐ Above-floor framework complete (at Keller Tools Inc., NY);


- ☐ Plates delayed by 3 months:

- Primarily due to procurement issues

- Software and analysis are progressing

- Commissioning and run plan have been created

- Excitement is growing!






# Prioritisation of Step IV data taking:

## Pressures:


- Completion and commissioning of Step IV;
- Start of reconfiguration for cooling demo;
- Staffing for safe operations 24/7 versus 16/5

1	Detailed scan (with $\sim 20k$ good muons per point) of the effect of empty, liquid-hydrogen and lithium-hydride absorbers as a function of betatron function (9 points) at the nominal momentum of 200 MeV/c.
2	1 & detailed scan (with $\sim 20k$ good muons per point) of the effect of empty, liquid-hydrogen and lithium-hydride absorbers as a function of momentum (9 points) at the (single) nominal betatron function ( $\beta$ ) of 420 mm.
3	1, 2 & 100k good muons per point muons at the nominal $\beta = 420$ mm, $p = 200$ MeV/c, scanning over emittance (3 points) with empty, liquid-hydrogen and lithium-hydride absorbers.
4	1, 2, 3 & detailed scan (with $\sim 20k$ good muons per point) of the effect of liquid-hydrogen and lithium-hydride absorbers as a function of betatron function (9 points) and emittance (3 points) at the (single) nominal momentum of 200 MeV/c.
5	1, 2, 3 & sampling of $3 \times 3$ emittance, momentum matrix at three betatron functions with reduced sample size ( $\sim 25k$ good muons per point).
6	1, 2, 3 & sampling of $3 \times 3$ emittance, momentum matrix at three betatron functions with reduced sample size ( $\sim 50k$ good muons per point).
7	1, 2, 3 & sampling of $3 \times 3$ emittance, momentum matrix at three betatron functions with reduced sample size ( $\sim 100k$ good muons per point).




# Step IV Run Plan

User Period	Run Type	Absorber	Focus coil Mode	Run-time (days)	Total (days)
2	Commissioning			54	
3	Physics	Empty	Solenoid	18	
	LH2 Fill			2	
	Physics	LH2	Solenoid	18	38
4	Calib/Setup			7	
	Physics	Empty	Flip	18	
	LH2 Fill			2	
	Physics	LH2	Flip	18	45
1	Calib/setup			7	
	Physics	LiH	Flip	18	
	Physics	LiH	Solenoid	18	43
					126



# Commissioning of Detectors


- TOFs, KL: no need for special commissioning.
- CKOVs: Equalise gains of PMTs, Cherenkov threshold scans
- EMR: hardware upgrade in progress, software integration into MAUS almost complete, documentation to be provided.
- Trackers: see next slides.



# Tracker commissioning runs


- Readout commissioning – no beam, random and LED triggering to iron out VME based trigger logic – 2 days
- Calibration – no beam runs with LED varying bias, discriminator and TDCs (latter not Step 4 essential) – 4 days (bias) + 4 days (discriminators) + 4 days (timing) = 12 days
- Timing commissioning – starting with LED and moving to beam to ensure integration and veto period align with arrival of particles – 5 days
- Fiber efficiency – 1 hour LED, 2 hours beam
- Alignment checks – no field straight tracks ( $\sim 25\%$  transmission) to reconstruct actual alignment of tracker in reference frame – 1-5 days depending on previous commissioning





# Tracker commissioning runs

- **Three weeks**, without beam
- **Two weeks**, with beam
- Total commissioning time alone is not enough – need time between commissioning and real running to analyze data, make adjustments, etc.
- Run 1: 15/4/15 – 24/4/15?
- Run 2: 2/6/15 – 23/6/15?
- Tracker should get unrestrained (by other detectors) time at the beginning of the commissioning period



# MICE magnets commissioning at STEP IV


- Magnets will be installed, connected and a ramping test completed in advance.
- Sufficient supply of LHe needs to be secured
  - ☐ Discussions with BOC indicate Liquid Helium availability will not be an issue!
  - ☐ Each magnet will be equipped with its own dewar and the transmission line.
- It will be followed by individual magnet training
  - ☐ SS will be trained in parallel, but, only 1 magnet will be ramped at a time (1 quench per magnet per day and 2 quenches per day in 24/7 training operations).
  - ☐ We will start most likely in solenoid mode.
- Once all magnets reached their independent nominal settings, set nominal current in both SSs and start raising current in the FC.
  - ☐ Detecting which coil quenches first knowing the FC current will allow to assess how far we are from the nominal setting:
  - ☐ Depending on experimental findings the procedure may be followed by:
    - ☐ Training the FC with SS currents fixed at nominal (repeating the procedure).
    - ☐ Training the FC with SS currents fixed at derated value (to be defined).
    - ☐ Switching to combined training (Scenario 1 with ramping all magnets simultaneously at approximately 2.5 quench per week incl. 40% contingency)



# Shift request


## for beam commissioning

- Beam line pre-commissioning with beam (does not require Tracker) – **8 shifts**
- Beam line commissioning including Diffuser and matching into Channel (requires Tracker - essential) – **15 shifts**
- Beam Commissioning of MICE Channel - **21 shifts**
  - At this stage we do not know, how much time is required, so this is only a guess.





# Tracker Position Residuals

T1 X Residual




T2 X Residual






# Tracker Momentum Residuals

T1 p<sub>t</sub> Residual




T2 p<sub>t</sub> Residual







T1  $p_z$  Residual




T1  $p_z$  Residual



T2  $p_z$  Residual



T2  $p_z$  Residual




Tracker  
Longitudinal  
Momentum  
Residuals






## Emitittance Reconstruction at Reference Plane

Approx 80,000 Muons - With Covariance Matrix Corrections




C. Hunt

A  $6\pi$  mm at 200 MeV/c Positive Muon Beam using a Step IV Cooling Channel Geometry




# Single Particle Amplitudes

Upstream Reference



Downstream Reference





- Truth MC
- Reconstructed MC

Currently see a 1-2% emittance bias in the reconstruction, consistent for both trackers




Amplitude Change






# Field Mapping: Magnetic Axis Analysis


- In a perfect world...
  - The **magnetic axis** (defined by coil bobbins) is aligned to **geometric axis** (defined by survey)
  - The field **mapper axis** is aligned with the **magnetic** and **geometric** axes





# Field Mapping: Magnetic Axis Analysis


- In a realistic world...
  - The **magnetic axis** is not aligned to **geometric axis**
  - The field **mapper axis** is not aligned with the **magnetic** or **geometric** axes
  - We know the relationship between the **mapper** and **geometric** axes
  - We do not know the relationship between the **mapper** and **magnetic** axes







# Field Mapping: The Naïve Analysis\*

Calculated field from a Focus Coil operating at 150A in “flip mode”





# Field Mapping: Why So Naïve?




Mapper does not measure  
“pure”  $B_x$  and  $B_y$ , but includes  
a small amount of  $B_z$

$$B_{xm} \approx B_x + \alpha B_z$$


$$B_{zm} \approx B_z + \alpha B_x \approx B_z$$






# Field Mapping: Testing the theory

1. Define the **mapper axis** and the measured co-ordinates in **mapper space**.
2. Define a test magnet (FC-like, 150A, flip mode), whose **magnetic axis** is not aligned to the **mapper axis**.
3. Obtain the measured co-ordinates in **magnetic axis space**.
4. Calculate the **true field** measured at these co-ordinates, then translate them back into **mapper space**.
5. We now have a “field map” of a tilted magnet, and the challenge is to find the (known but unknown) tilts.




# Field Mapping: Test # 1 (large tilt)





**“Naïve fits”:** Assume a perfect world and ignore the fact that  $B_{xm} \neq B_x$  etc

**“After fits”:** Assumes a realistic world, finds  $\alpha$  and axis

**“Real axis”:** The line between the **known** upstream and downstream ends of the test magnet.



# Field Mapping: Test # 2 (small tilt)



**“Naïve fits”:** Assume a perfect world and ignore the fact that  $B_{xm} \neq B_x$  etc

**“After fits”:** Assumes a realistic world, finds  $\alpha$  and axis

**“Real axis”:** The line between the **known** upstream and downstream ends of the test magnet.








# Progress on various other fronts

- MLCR Upgrade 75% complete (P. Smith)
- Huge progress in control and monitoring
- Global Tracking: focus to merge Trackers with TOFs
- Improvements in documentation
- MAUS is in good shape (MAUS team)
- CDB Geometry validated (Geometry team)
- Physics Block Challenge: test data generated, analysis in progress (R. Bayes)
- Electrical installations progressing well (S. Griffiths)
- LH2 system preparations in progress (S. Watson)
- Alignment team created and started working (S. Boyd)
- .....many more!



SS's and Trackers

# Step IV



Racks




AFC

TOF/KL



EMR



ge


nfere






MICE Hall






# Development of cooling demonstration design:


- Initially classified possible lattices using:
  - Two focus coils, note no CC;
  - Two cavities;
  - Single LiH absorber module
- Gaps between solenoids were populated with all logical combinations of cavities and absorbers




- Linear optics used to study beta-function, energy loss and expected cooling performance
- The two lattices that performed best were identified and selected for further analysis




# Reference and alternative:









## Alternative







# Beam dynamics in both lattices



- ++ -- configuration preferred
  - Field-flip in centre of cell
- Reference yields smaller beta at central absorber and smaller maximum beta
- Reference has smaller excursions in radial direction:
  - Aperture limitations less severe for reference



# Beam dynamics in both lattices(2)




- Cooling effect in reference stronger:
  - Result of more advantageous beta function







# Criteria:


- Priority-ordered criteria agreed at CM40, Rome Oct14:
  1. 4D emittance reduction; transmission/scraping:
    - Have not (yet) studied full simulation/reconstruction;
    - Therefore essential that configuration adopted produces largest 4D cooling effect;
      - Best chance for systematic study.
  2. 6D emittance reduction:
    - Largest change in 6D emittance presented at recent CM at ~1% level;
      - Confirmed for reference and alternative since; still under study;
      - Very large data sets likely to be needed to measure such a small effect;
      - 6D emittance reduction is a desirable, rather than essential.
  3. Lattice cell:
    - MICE approved to demonstrate “realistic” section of cooling channel;
    - Ideally cell constructed would be part of an extended cooling channel;
    - Implies appropriate matching criteria;
      - Applied in developing reference/alternative;
    - Lattice cell suitable for incorporation extended channel desirable.



# Performance Comparison:



- Reference lattice therefore confirmed:
  - Studies of 6D performance in hand:
    - Indication is that performance of reference and alternative is very similar



# Engineering of Mice Demonstration of Ionization Cooling


Imperial College  
London

Helium Window

Radiation Shutter

Main Absorber


Vacuum Envelope



Alternative location for secondary absorber


Reference position for  
the secondary absorber





# Question to be addressed

- Do we need to have movable Secondary Absorbers?
  - ☐ If yes, can we use the Shutter mechanism?
    - ☐ If not, we need to design an alternative mechanism.
  - ☐ If not, is it better to put them into the SSs?
- What is the optimum distance between FCs?
- The deadline is 18<sup>th</sup> December!



# Conclusions

- Step IV construction is ongoing with the aim to complete **2<sup>nd</sup> of June 2015**.

- ❑ Critical delivery is **PRY**

- Preparations on all fronts are progressing well
- Scenarios for MICE Demonstration of Ionization Cooling with RF re-acceleration without RFCC have been successfully created.

- ❑ They substantially **reduce** the **risk** of the project

- Reference scenario for MDIC has been identified and the design will be frozen soon (**18<sup>th</sup> of December**)
- Very positive feedback was obtained at the last MPB -> we have **defended** the Project!
- MICE is on a good path toward the essential **demonstration of the ionization cooling** – an essential tool required for our field!