

Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

The Long-Baseline Neutrino Facility

Jim Strait, LBNE Project Director

Open meeting for the scientific community to form LBNF

5 December 2014 (CERN)

12 December 2014 (Fermilab)

Outline

- Overview of the Fermilab Neutrino Program
- Increasing proton beam power: PIP and PIP-II
- The Facilities for a long-baseline experiment
 - The facilities team for LBNF
 - Neutrino Beamline
 - Sanford Underground Research Facility
 - Conventional Facilities at Fermilab and SURF
 - Cryogenic infrastructure
- Technically limited schedule
- Summary and Conclusions



Accelerator-Based Neutrino Program at Fermilab

Fermilab hosts an active, diverse, international accelerator-based neutrino program

- Two neutrino beams in operation and a third under design
- Four experiments currently taking data
- Three completed experiments analyzing data
- One experiment under construction
- Two experiments under design
- One proposal reviewed by the PAC and under consideration by Fermilab management
- Several experimental proposals submitted or in development
- Various R&D programs proposed or under way
- Supporting test beam program for detector development and calibration.

The Fermilab Neutrino Program Hosts Collaborators from across the globe: Brazil, Canada, Chile, Czech Republic, Greece, India, Italy, Mexico, Peru, Poland, Russia, Switzerland, UK, US, ...




Fermilab Accelerator Complex Advanced Accelerator Test Area Proton Beamline Tevatron Accelerator Technology Complex (Decommissioned) **Facility** Superconducting Linac (Part of proposed PIP II project) Linac Booster. Muon Area. Neutrino Beam To Minnesota Booster Neutrino Beam Neutrino Beam To South Dakota [Part of proposed LBNF project] Main Injector and Recycler **Protons** Neutrinos **■ Muons** ■ Targets R&D Areas

NuMI and Booster Beams


NuMI:


- tunable1 GeV to>10 GeV
- Near hall at 1 km
- -Far detectors 735 810 km



BNB:


- Low energy 0.1 – 1.5 GeV
- Focused on short-baseline oscillations and cross sections






Experiments in the NuMI Beam

Long-baseline oscillation experiments



Neutrino scattering experiments



Brazil, Chile, Mexico, Peru, Russia, Switzerland, US

5 and 12 Dec 2014

Experiments in the Booster Neutrino Beam

Testing short-baseline anamolies ... sterile neutrinos?



MicroBooNE



Fermilab Short Baseline Neutrino (SBN) Program

- Utilize successful Booster Neutrino Beamline (BNB) developed for MiniBooNE
- In 2015 next phase: MicroBooNE (approved for 6.6E20 P.O.T.)
- In 2018: Three LAr-TPC detectors:
 - Near: New detector using LBNE technology @ 110m from BNB target

Switzerland, UK. US

- Middle: MicroBooNE @ 470m Switzerland, UK, US
- Far: refurbished ICARUS detector moved from Gran Sasso, Italy @ 600m

Italy, Poland, Russia, Switzerland, US

- Motivations
 - Science: precise study of v anomalies from the MiniBooNE and LSND experiments. Search for Sterile v's
 - R&D: continued development of LAr-TPC technology for LBNF program
 - Build international partnerships for LBNF program



SBN Program Layout




SBN Program Development


- International partnership of the three collaborations developing joint proposal for submission to January 2015 PAC meeting
 - More than 40 institutions from 5 countries including 4 DOE labs and CER
 - Strong support from US DOE and NSF, INFN, and CERN. Additional support requests to CH NSF and UK STFC
- Very Fast timeline
 - 2014 Proposal preparation initial design and logistics
 - 2014 Civil construction start, near detector design, T600 refurbishing
 - 2016 Civil construction complete, near detector construction, T600 refurbishing
 - 2017 Detector installation
 - 2018 Beam operations with all three detectors
- Support expected from US DOE, US NSF, INFN and CERN.




Additional Possible Experiments in the Booster Beam



ANNIE: Measure v-induced backgrounds relevant for large water detectors using an Optical Time Projection Chamber in BNB




Short-baseline v_{μ} -disappearance measurement in BNB (NESSiE)



space is available in and out of building at points A, B and C



CAPTAIN




Calibrate LAr TPC response to low-energy neutrinos with stopped pion beam Fermilab

Increasing beam intensity

- Upgrades to the Main Injector and Recycler done as part of the NOvA construction will enable doubling the NuMI beam power to 700 kW
 - Convert Recycler to proton-stacking ring
 - Increase Main Injector ramp rate
 - ~10% increase in intensity per pulse
- Proton Improvement Plan (PIP) to increase proton flux from Booster to the Main Injector
 - Refurbish Booster RF system: 7.5 → 15 Hz beam operation
 - Upgrades to Linac and Booster for higher reliability
- Combined upgrades will deliver 700 kW to NOvA and increase the intensity of the Booster Neutrino Beam.




Proton delivery scenario (approximate)



Proton Improvement Plan II (PIP-II)

- Goal is to increase Main Injector beam power to 1.2 MW.
 - Replace the existing 400 MeV linac with a new 800 MeV superconducting linac => 50% increase in Booster intensity.
 - Shorten Main Injector cycle time 1.33 → 1.2 sec.
- Build this concurrently with LBNF
 => 1.2 MW to LBNF from t = 0.
- This plan is based on welldeveloped SRF technology.
- Developing an international partnership for its construction
- Strong support from DOE and P5


14



Jim Strait | Facilities for LBNF 5 and 12 Dec 2014

Flexible Platform for the Future

- Future upgrade would provide
 2 MW to LBNF
- Flexibility for future experiments
 - 100's kW at 800 MeV
 - 100's kW at few GeV, depending on design of next upgrade
 - Example shown is for 2 GeV
 SRF linac + new Rapid Cycling
 Synchrotron





Long-Baseline Neutrino Facility

Fermilab is prepared to host a Long-Baseline Neutrino Facility. Working with international partners it will provide the infrastructure required to carry out a world-leading long-baseline neutrino oscillation experimental program.

The facilities will include:

- A neutrino beam capable of operating at 1.2 MW and upgradeable to at least 2.4 MW
- Far site infrastructure to house a massive LAr TPC far detector 1300 km from Fermilab at the Sanford Underground Research Facility,
- Near site infrastructure to house the near detector
- Major technical infrastructure such as cryostats and cryogenic systems for LAr TPC detector(s).



The LBNF Facilities Team

The work so far has been done mainly by the LBNE Project Team, already with significant international collaboration: China, Finland, Japan, Switzerland, UK, US, ...

- Beamline: Fermilab with collaborations with UTA, RAL, RADIATE Collaboration, CERN, US-Japan Task Force, IHEP/Beijing, and others.
- Conventional Facilities: Fermilab, SURF and contractors; collaboration initiated with LAGUNA-LBNO team
- Cryostat and cryogenic systems: Fermilab; collaboration initiated with CERN and with LAGUNA-LBNO team.

The LBNF team will be built on this foundation, with expanded collaboration as this becomes a truly international program.

- Expanded roles for existing partners
- Augmented by additional partners



The LBNF Facilities

- The facilities team has been working with the scientific community to develop facilities to support the experimental program.
 - Has worked for many years with the LBNE Collaboration

Armenia, Brazil, Czech Rep., India, Italy, Japan, Russia, UK, US

- During the past year, have expanded to also work with the LAGUNA-LBNO Collaboration
 Bulgaria, Finland, France, Germany, Greece, Italy, Japan, Poland, Romania, Russia, Spain, Switzerland, Turkey, UK
- The LBNF facilities team will work with the new Collaboration, which will provide scientific and technical requirements for the LBNF experiment, to design and build the facilities that will enable a world-leading long-baseline program.
- The slides that follow summarize the current facility designs on which the new LBNF facility designs will build.




Beamline for a new Long-Baseline Neutrino Facility

A design for a new neutrino beam at Fermilab is under development in the context of the LBNE Project, which will support the new Long-Baseline Neutrino Facility.

- Directed towards the Sanford Underground Research Facility (SURF) in Lead, South Dakota, 1300 km from Fermilab.
- Beam spectrum to cover 1st (2.4 GeV) and 2nd (0.8 GeV) oscillation maxima => Cover 0.5 ~ 5 GeV
- All systems designed for 1.2 MW initial proton beam power.
- Facility is upgradeable to ≥2.4 MW proton beam power.




Beamline for a new Long-Baseline Neutrino Facility





20 Jim Strait | Facilities for LBNF

Target Hall and Decay Pipe Layout



Conventional Facilities Designs






Near Detector Hall and Surface Building



5 and 12 Dec 2014

Primary Beam and Lattice Functions

• The LBNF Primary Beam will transport 60 - 120 GeV protons from MI-10 to the LBNF target to create a neutrino beam. The beam lattice points to 79 conventional magnets (25 dipoles, 21 quadrupoles, 23 correctors, 6 kickers, 3 Lambertsons and 1 C magnet).




Horizontal (solid) and vertical (dashed) lattice functions of the LBNF transfer line The final focus is tuned for σ_x = σ_y = 1.50 mm at 120 GeV/c with β^* = 86.33 m and nominal MI beam parameters ϵ_{99} = 30 π µm & $\Delta p_{99}/p$ = 11x10⁻⁴




Components inside the target chase Baffle 47 graphite target segments, each 2 cm long BERYLLIUM TITANIUM Target cross section WATER GRAPHITE, 1.78 G/CC -5.2000 Horn Stripline 13.3675 35.2000 36.0000 3.0000 10.0000 Horn Outer Conductor 0.33m Outer Diameter, 16 mm Wall

Helium-filled/Air-cooled Decay Pipe



- Concentric Decay Pipe. Both pipes are ½" thick carbon steel
- Decay pipe cooling air supply flows in four, 28" diam.
 pipes and the annular gap is the return path
- The helium-filled decay pipe requires that a replaceable, thin, metallic window be added on the upstream end of the decay pipe




Absorber Complex – Longitudinal Section

The Absorber is designed for 2.4 MW

26


A specially designed pile of aluminum, steel and concrete blocks, some of them water cooled which must contain the energy of the particles that exit the Decay Pipe.



Jim Strait | Facilities for LBNF 5 and 12 Dec 2014

Absorber Design/MARS Simulations (2.4 MW)

9 sculpted Al blocks and 4 solid Al blocks in the core





ANSYS

5 and 1

PLOT NO. 1 NODAL SOLUTION

Hadron Flux (cm⁻² s⁻¹) at E > 30 MeV (2.4 MW)








R a D I A T E Collaboration





Novel Target Designs

Radiation Damage In Accelerator Target Environments


- High heat-flux coolants
 - Elimination of water
- Composite targets
- Segmentation
- Robust materials and assemblies








Improved Focusing for Second Oscillation Maximum






Significant improvements are possible and needed, which collaborators could bring into the design of the LBNF beam design.




CN2PY v-beam optimisation



- Beam target and focusing system optimization using Genetic Algorithm
 - Multi-variable analysis of horn/reflector parameters
 - Optimization:
 - use GLOBES to maximize the δ_{CP} sensitivity at the FD
 - ▶ **HE-optimization**: maximum yield of v-s in the range [1-10]GeV
 - LE-optimization: maximum yield of v-s in the range [1-2] GeV





POT normalization for SPS: 3.75E+20 POT normalization for HPPS: 3.0E+21


- New optimization for CDR, using additional engineering constraints:
 - R_{min} horn ~27mm
 - Same relative position horn/reflector for 400/50 GeV beams
 - Target length <1.3 m

Jim Strait | Facilities for LBNF

03-Nov-2014

16

Apply LBNO-design low-energy beam (HPPS LE) to LBNE



- Application of HPPS LE beam spectrum to LBNF baseline
 - -modestly improves CP violation reach
 - -improves minimum Δx^2 by $\sim x^2$ for MH



Sanford Underground Research Facility


Experimental facility operated by the State of South Dakota.

Current experiments:

- LUX (dark matter)
- Majorana (0 $\nu\beta\beta$)

Davis Campus

Several smaller experiments



Future home of:

- LZ (G2 dark matter experiment)
- CASPAR (Compact Accelerator System for Astrophysical Research)
- LBNF



Ross Campus

Sanford Underground Research Facility

Entrance to Davis Campus



- Experimental Facilities at 4300 mwe
- Two vertical access shafts for safety
- Shaft refurbishment in process and has reached the 2000 foot level
- Total investment in underground infrastructure is >\$100M
- Facility donated to the State of South Dakota for science in perpetuity

Majorana Demonstrator $(0v\beta\beta)$



LUX (dark matter)




Planned Location of LBNF Cavern(s)

Current reference* design:

- Rectangular caverns for rock-supported cryostats
- 2 caverns: 10 kt + 24 kt fiducial mass sizes
- 10 kt cavern fully outfitted and detector-ready

24 kt cavern excavated only





Geotechnical Investigation Program



A geotechnical exploration program at the 4850L has been completed to explore the rock mass south of the south access drift. Analysis of geotechnical data is on-going to determine maximum span and preferred cavern geometry.

Area near Yates shaft extensively studied for WCD option.






Rectangular vs. Cylindrical Cryostat


LBNE Design:

Rectangular, rock-supported cryostat



- Current reference design
- Rectangular geometry makes maximum use of excavated volume
- Rectangular geometry requires rock support

LBNO Design: Cylindrical, free-standing cryostat




3D Tank & Detector Model Screen Shot (courtesy ETH Zürich)


- Follows industry standard design and construction methods
- Requires larger span cavern, similar to LBNE WCD design


Joint LBNE - LBNO evaluation launched





Cryogenic System Design











Summary and Conclusions

- Fermilab hosts an active, diverse international accelerator-based neutrino program.
- Fermilab has a record of delivering high-intensity proton beams with high reliability and long running time for neutrino physics.
- On-going upgrades will increase the Main Injector beam power to 700 kW over the next ~2 years.
- PIP-II will further increase the beam power to 1.2 MW and provide a platform for future beam power >2 MW.
- Fermilab is prepared to host LBNF and work with international and U.S. partners to provide:
 - A high-intensity, broad-band neutrino beam
 - Conventional facilities for the LBNF detectors at SURF and Fermilab
 - Major technical infrastructure for the LBNF detectors

