



# Crab Cavities Summary

A. Ratti (LBNL)  
for the Crab Cavity Team

May. 13, 2015



Science & Technology  
Facilities Council





# Outline



- Progress since KEK - highlights
- Cavity design update
  - Manufacturing tolerances sensitivity analysis
  - HOM damper optimization
  - Dressed cavity studies
- Cavity fabrication
- Open issues being resolved
  - Impedance budget
  - Losses
- Planning for SPS tests
  - Installation and location
  - MD proposal






# Cavity Development in Industry



- Most but not all documents in the manufacturing readiness list were delivered and accepted
- Tested all forming steps in Copper
  - Similar behavior to Nb
- Formed nearly all Nb parts
- Built test beam pipe assembly
  - Measured and tested at CERN
    - Some non compliances (being addressed)
- Beam pipe assemblies fabrication started
  - Working on acceptance plan



# DQW – Assembly and Spec.





# DQW – Outer Conductor



- Outer conductor halves
  - 4 halves etched, fixtured, and ready for weld





# DQW - Cake pan assemblies



- Ready to weld






# DQW – Inner Conductors

- “Bowls”
  - Complete
  - Etched, and ready for NbTi tuner attachment welds






# RFD – Assembly and Spec.







LARP

# RFD Stamped Parts



Science & Technology  
Facilities Council





# Fabrication Summary



- Nearly all Nb parts are stamped
  - Waiting for 1/4" plates to finish stiffeners for one RFD
    - Due next week
- All parts are measured at the factory
  - Variances addressed on a case-by-case basis
- DQW bodies ready to weld
- RFD bodies will be ready to weld in about one month
- Beam pipe assemblies fabrication underway
  - First welding cycle this week
- CC team will visit Niowave on Thursday
  - Inspect all parts that are ready and available

From Niowave



# Cavity design




As fabrication of the core cavity is underway, progress in other areas:

- Magnetic shield and He vessel design
  - Review @ CERN on 6 May
  - Plan to complete both designs by June 2015
- Tuner Design
  - Discussed also at the 6 May review
- HOM optimization



# Dressed Cavity Overview





# Cold Magnetic Shielding

## Specification



- $<1\mu\text{T}$  on cavity surface
- To be achieved in conjunction with 3mm warm MuMetal shield

## Constraints

- Internal to Helium Tank
- Suspended in 2K Helium
- Mounted off Helium Tank – no cavity connection

## Operating Conditions

- $>200\mu\text{T}$  – Earth's magnetic field + shielded local sources







# Cold Shield Design Approach


1. Minimise number & size of penetrations
2. Ease of manufacture & assembly
  - Minimise number of panels
  - Fabricated from Bent / Folded sheet
  - *Pressed panels possible future batch shield orders*
3. Maximise penetration attenuation
4. Maximise curvature

Shield	No. Penetrations	No. Panels
DQW	11	7
RFD	7	10





# Helium Tank Overview






# Reasons for Bolted Helium Vessel




- Nature of compact crab cavity design requires a stiff helium tank for pressure testing and tuning.
- Thin walled vessel requires large number stiffening ribs.
- Manufacturers advised that thin walled design would result in large weld distortions.
- Weld distortions would be detrimental to cavity, thin walled design deemed too high risk.








# Double Quarter Wave Helium Vessel





# RF Dipole Helium Vessel








# DQW Assembly Procedure



Shield & cavity mounted to base plate of the Helium Vessel  
Top End caps are attached as well as bottom side panel and  
Dummy beam pipe attenuation sleeve.







# DQW Assembly Procedure




Final 2 top panels are brought into place and remaining cover strips and brackets are fastened






# DQW Assembly Procedure




Side and top Vessel walls are assembled with remaining Flexi-Mounts before Helium Vessel is closed






# RFD Assembly Procedure




Pre-assembled shield body is assembled Top and Bottom






# RFD Assembly Procedure




Shield body is mounted to Helium Vessel base



# RFD Assembly Procedure



Split folded-end panels are assembled around 3 ports  
End Cover is assembled to main body and fastened with cover panels and brackets









# RFD Assembly Procedure



2 Curved-End panels are assembled around Beam Pipe






# RFD Assembly Procedure



Split panels complete the Shield at the FPC & HOM Ports  
Remaining cover strips are assembled







# RFD Assembly Procedure




Flexi-mounts are connected and Helium Vessel is assembled





# RFD Assembly Procedure




Thin caps are TIG welded over the fastener slots  
Vessel is sealed



# Impedance of Crab cavities



- Crab cavities in LHC are a worry for the impedance team due to:
  - The very large transverse beta functions at their planned location (~4 km)
  - The large number of cavities (16 in the final stage)
  - The large number of HOMs and their high Q if undamped.
  - The already optimized LHC impedance to reach high brightness beams.
- In the SPS, however:
  - The beta function can not be very high.
  - There are only 2 cavities.
  - The large number of HOMs and their high Q if undamped.
  - The SPS impedance is large compared to LHC, in particular in the longitudinal plane.



LARP

# HOM Damper Design



- Two reviews since KEK meeting
  - Electromagnetic design
  - Mechanical design
- Major progress
- Reducing worse offending modes
- Review outcome
  - > ready to build NOW

**BROOKHAVEN**  
NATIONAL LABORATORY



**The Cockcroft Institute**  
of Accelerator Science and Technology

**Lancaster University**



Science & Technology  
Facilities Council

**OLD DOMINION UNIVERSITY**

**SLAC**  
NATIONAL ACCELERATOR LABORATORY







# DQW – HOM impedance



Results above 1.75GHz are not accurate as the modes started to leak out from the beam pipe.



By inserting the most recent version of HOM filters to the **100mm aperture cavity**, the HOM longitudinal and transverse impedances were calculated. There are a few modes need to be optimized. It is a good starting point.






# Improved HOM Damping




## Horizontal HOM Coupler

- Coupling hook optimized
- 30 degree hook orientation
- No change in filter elements



## Vertical HOM Coupler

- 7 mm offset incorporated into the pickup tip to enhance coupling to the dipole modes at around 2GHz
- Small RF power leakage through the coupler,  $\sim 1.5\text{W}$ , due to asymmetry









# HOM Damping and Impedance



RFD HOM Damping  $Q_{ext}$



RFD HOM Impedance



- $Q_{ext}$  calculated using Omega3P for modes up to 2 GHz
- Solid lines are the impedance budget for dipole HOMs (blue) and accelerating HOMs (red) respectively



# Impedance Summary



- CC impedance is a concern in the LHC
  - On the other hand, we may not be able to even notice their presence in the SPS
- Studies are underway both in beam physics (WP2) and RF design (WP4) to find a suitable solution


[Note: dedicated MD time in the SPS is tight]



# Status SM18 p.o.p. tuner



Design: P. Minginette



**Motor 1.3 Nm Bipolar Nema 23  
(1.8 deg/step)**

**HD HFUS-20-100-2SO**

Ratio  $i : 0.01$  ,  
repeat. peak Torque 82 Nm, average  
torque 49 Nm

Accuracy  $< 1$  arcmin, precision  $< 0.1$   
arcmin

Fa Dyn 7.7 kN,  $\eta \sim 0.80$  (grease, 20 °C)

**Roller screw Rollvis RV 12 x 1**  
 $\eta = 0.79$  , static load capacity 17 kN



$$M = p i F / 2000 \pi \eta = 0.01 \text{ Nm} \quad F = 4 \text{ kN}, p = 1$$

Detend torque 0.017 Nm, self locking




# Cryomodules

Double Quarter  
Wave, Vertical  
Deflection



RF Dipole,  
Horizontal  
Deflection




LARP


# Supporting system - Vertical Rods and Inter-cavity Link




25 Hz




33 Hz



36 Hz



94 Hz





# Summary – Cavity and CM integration




- Lots of progress and lots of work ahead of us in preparation for the SPS test
  - Need to freeze He vessel design very soon
    - Successful review of 6 May is a key step forward
  - Magnetic shield and He Vessel
  - Tuner prototype underway
- Finalizing the cryomodule design will be next, if we want to be ready at the end of 2016
  - Studies also in progress



# Conclusions



- Major progress across the board
  - Cavity production of both cavity designs is underway at our US industrial partner
  - Finalizing dressed cavity and He vessel design
- Working on other major aspects of the design
  - Impedance and machine protection
- Planning for SPS test
  - A decision is needed soon
  - Schedule remains tight
- Active contributions from all collaborators



LARP



# Acknowledgments – The Team

- Contributions to this presentation came from the whole collaboration
  - BNL – S. Belomestnykh, S. Verdu-Andres, Q. Wu, B. Xiao
  - CERN – L. Alberty, R. Calaga, O. Capatina, T. Capelli, M. Garlasche, C. Zanoni (and more)
  - FNAL – T. Nicol
  - LBNL – A. Ratti
  - Niowave – J. Hollister, T. Grimm, S. Klass, E. Maddock, J. Yancey,
  - ODU – J. Delayen, H. Park, R. Olave, S. da Silva
  - LU/STFC – G. Burt, B. Hall, T. Jones, S. Pattalwar, N. Templeton
  - SLAC – Z. Li

And I'm sure there are more...



# Questions

