

Yannis PAPAPHILIPPOU, CERN

Fermilab, May 12th, 2015

Thanks to

F.Antoniou, G.Arduini, G.Campogiani, S.Fartoukh, R.Jones, R.deMaria, A.Patapenka, T.Rijoff, H.Schmickler, A.Valishev, F.Zimmermann




Outline



- Wire compensation basic considerations
- Wire effect on the beam
 - □ Multipole expansion,
 - Orbit, coupling, tune, tune-spread
- Test of wire compensation in the LHC
 Nominal and available positions
 Present simulation status
- Experimental conditions, observables and associated instrumentation needs
- SPS wires status and plans
- Study plans

12/05/2015



separations) $x_W = x_c$, $y_W = y_c$, $I_W L_W = ecN_b$

This gives 5.5 Am/encounter for the nominal LHC 12/05/2015
Y. Papaphilippou - HL-LHC LARP 2015 meeting




Basic considerations



J.P. Koutchouk, 2001

• Locality of the compensation

- \Box Close to the BBLR encounters which occur at $\sim \pi/2$ from either IP side
- □ A lot of space available between D1 and TAN but integration may be difficult
- \Box Phase advance still close to $\pi/2$ even up to Q5






Basic considerations



- **Position** of the wire with respect to the beam
 - □ As close as average BBLR separation (9.5σ)
 - Integrated kick is scaled inversely with distance, i.e. the smaller the distance the lower the required integrated current and vice versa
 - □ Difficulty with wire-in-jaw collimator to approach the beam closer to \sim 12-13 σ
 - Some strength can be recovered by wire current but dependence is not uniform depending on resonance order



A. Bertarelli




Basic considerations



Optics considerations

- Large and equal beta functions for efficient tune-shift compensations
- The optics functions equality may be not optimal for resonance driving term compensation see work of S. Fartoukh
- The absolute criterion should be **non-linear compensation** (increase of DA, i.e. lifetime, through combined reduction of non-linear resonances and tune-spread)






Two wires per IP



- Integrated current can be reduced for the same correction reach
- Powered independently to fit better the integrated kick on either side
- Due to optics anti-symmetry and different plane crossing, effect of two wires in the two planes is also anti-symmetric



Wire multi-pole expansion

The multi-pole expansion of the wire can be written

$$B_{y} + iB_{x} = \frac{\mu_{0}IL}{2\pi r_{W}} \sum_{n=1}^{\infty} (b_{n} + ia_{n}) \left(\frac{x + iy}{r_{W}}\right)^{n-1}$$

with the radial distance of the wire to the beam

$$r_W = (x_W^2 + y_W^2)^{1/2}$$

and the multipole coefficients

 $b_n = -\cos(n\phi_W)$, $a_n = \sin(n\phi_W)$ with the angle $\phi_W = \arctan(\frac{y_W}{x_W})$ The same expansion is applicable to the BBLR field for the round beam, 1/r approximation

Wire multi-pole expansion



- For a wire positioned in the horizontal plane (or horizontal BBLR crossing), i.e. $r_W = |x_W|$
 - \Box For $\phi_W = 0$, $a_n = 0$ and $b_n = -1$
 - \Box For $\phi_W = \pi$, $a_n = 0$ and $b_{2n-1} = 1$, $b_{2n} = -1$
- For horizontal wire (or horizontal BBLR crossing), only normal multipoles are excited
- Putting the wire in the opposite side with respect to the "strong" beam will cancel only half of the multipoles (odd or even depending on the polarity of the wire)

Wire multi-pole expansion



- For a wire positioned in the vertical plane (or vertical BBLR crossing), i.e. $r_W = |y_W|$
 - □ For $\phi_W = \pi/2$, $a_{2n} = b_{2n-1} = 0$ and $a_{4n-1} = b_{4n} = -1$, $a_{4n-3} = b_{4n-2} = 1$
 - \Box For $\phi_W = -\pi/2$, $a_{2n} = b_{2n-1} = 0$ and

$$a_{4n-1} = b_{4n-2} = 1$$
, $a_{4n-3} = b_{4n} = -1$

- For vertical wire (or vertical BBLR crossing), even skew and odd normal multipoles are not excited
- Putting the wire in opposite side with respect to "strong" beam cancels only half of the excited BBLR multipoles (odd skew or even normal, depending on the wire polarity)
- Alternating crossing cancels the effect of b_2, b_6, b_{10}, \ldots



Orbit effect due to wire



The wire induces an orbit shift due to a "dipole" kick expressed as

$$\delta x'_0 = \frac{\mu_0 IL}{2\pi B\rho} \frac{\cos \phi_W}{r_W} \quad \text{and} \quad \delta y'_0 = \frac{\mu_0 IL}{2\pi B\rho} \frac{\sin \phi_W}{r_W}$$

For only horizontal or vertical positioning of the wire, there is only an orbit kick in the corresponding plane
 In either side of the IP, powering the wires accordingly (opposite sign and with current following the square root of beta functions ratio), orbit effect (π-bump)
 To be used for calibration purposes



Coupling due to wire

The minimum tune-split due to wire-induced coupling is

$$\delta\nu_{\rm min} = \frac{\mu_0 I L}{4\pi^2 B \rho} \sqrt{\beta_x \beta_y} \frac{\sin 2\phi_W}{r_W^2}$$

- If the wire is positioned in one plane, there is no coupling
- Maximum coupling is induced for $\phi_W = 45^\circ$, giving around 6e-3 tune-shift for wire in **BBC** position
- Global coupling can be cancelled, between wires in the two IPs, if wire is positioned in complementary phase $\phi_W = 135^\circ$, in the opposite IP (and current follows square root of the product of beta functions) ^{12/05/2015} Y. Papaphilippou - HL-LHC LARP 2015 meeting 12



Tune-shift due to wire



- The linear tune-shift induced by a wire is expressed as $\delta\nu_{x,y} = \mp \frac{\mu_0 IL}{8\pi^2 B\rho} \beta_{x,y} \frac{\cos 2\phi_W}{r_W^2}$
- Equal beta functions in both planes chosen for having the same impact in both planes (BBC location)
- Induced tune-shift between wires in two IPs cancelled, if wire is positioned in equal distance but different planes, and integrated current follows beta function change

□ Alternating crossing idea for cancelling BBLR tune-shift

For equal distance of the wire in both planes at the same IP $(\phi_W = 45^\circ)$, tune shift is suppressed (true also for BBLR)

Tune spread due to wire



The first order tune-spread (octupole-like effect) is

- $\begin{pmatrix} \delta\nu_x \\ \delta\nu_y \end{pmatrix} = -\frac{3\mu_0 IL}{16\pi^2 B\rho} \frac{\cos(4\phi_W)}{r_W^4} \begin{pmatrix} \beta_x^2 & -2\beta_x \beta_y \\ -2\beta_x \beta_y & \beta_y^2 \end{pmatrix} \begin{pmatrix} J_x \\ J_y \end{pmatrix}$ • For alternating crossing in optically symmetric IPs, tune-spread adds up (same polarity)
- It can be cancelled for wire angle (or crossing) at $\pi/8$
- Because of triplet optics symmetry, diagonal terms of anharmonicity matrix for BBLR are equal
 - □ True also for the effect of two wires placed symmetrically in either side of the IP
- Ratio of beta functions at wire position can be chosen as to cancel completely tune-spread




The first order resonance driving terms are $\mathcal{H}_{n_x,n_y} \propto \left| \int_0^C \frac{b_n}{r_W^n} \beta_x^{n_x/2} \beta_y^{n_y/2} e^i \left(n_x \mu_x + n_y \mu_y \right) ds \right|$

• For phase advances $\mu_x \approx \mu_y \approx \pm \pi/2$ $\Re \left[e^i \left(\pm (2k+1)\pi/2 \right) \right] \approx 0$ $\Im \left[e^i \left(\pm 2k\pi/2 \right) \right] \approx 0$ $\Re \left[e^i \left(\pm 4k\pi/2 \right) \right] \approx 1$ $\Im \left[e^i \left(\pm (4k-3)\pi/2 \right) \right] \approx \pm 1$ $\Re \left[e^i \left(\pm (4k-2)\pi/2 \right) \right] \approx -1$ $\Im \left[e^i \left(\pm (4k-1)\pi/2 \right) \right] \approx \mp 1$


Due to the IP optics anti-symmetry, the contribution to purely H/V even resonances, from either side, is symmetric

12/05/2015



Optics at wire locations





IR5: upstream+downstream slots available in Xing plane.

High Luminosity

 IR1: only upstream slots available for Xing plane. Need to add a V collimator (TCL) for downstream side (non-IP side of Q4 magnet)

Status of wire-in-jaw collimators



- 4 "wire-in-jaw" collimators ordered from CINEL
 - □ Cost covered by HL-LHC
 - Design finished in late 2014
 - Delivery during 2015, followed by qualification tests
 - □ Installation in winter stop 2015/2016 (vacuum group approval)
 - Cabling to be finalised for 4 individual power supplies
- Full compensation of one beam: 2 collimators/IP
 - Compensation of both beams in the ingoing or outgoing side (2 collimators on the same side in IP1 and IP5) does not provide optimal reduction of tune-spread and resonance driving terms

BBLR Simulations remarks



- All previous simulations studies made with 7 TeV nominal optics using BBTRACK code (U. Dorda, F. Zimmermann, T.Rijoff)
 - \square BBLR kicks lumped at the IP (phase advance of $\pi/2$)
 - No difference found with respect to distributed kicks in "correct" positions
 - □No other effects included (noise, triplet non-linearities, PACMAN), although implemented in the code
- Complementary studies for fixing the experimental set-up
 - □ Simulate machine conditions after LS1 (optics, slightly lower energy then nominal, four wires, slightly modified locations,...)



Wire modelling




A. Patapenka

1

Vector potential for finite straight wire
 Only one longitudinal component
 z-dependent, with central symmetry

$$A_z(x, y, z) = \frac{\mu_0 I}{4\pi} \operatorname{asinh} \left(\frac{z_0 - z}{\sqrt{x^2 + y^2}} \right)$$

Map contructed by integrating the kick over the z-direction



SIXTRACK implementation




Two models in SIXTRACK

Luminosity

A. Patapenka


- □ Existing one debugged see Erdelyi and Sen
- Implementation of a map for an arbitrary 3D vector potential, based on Euler integration method
 - Ability to integrate a generic field coming from a model or magnetic measurements
- Tilts of the wire are treated as coordinate transformations before and after the element
- The two models produce identical results for the wire element





Wire compensation 1IP A. Patapenka

Compensation in IP1 with 1 wire of 175A in the BBC location (nominal 7TeV LHC beam parameters)



Experimental set-up - Train composition

- CERN
- Two trains with unequal number of bunches, to avoid "all" PACMAN
 - Long one in non-compensated beam to cover twice the distance of long range collisions, i.e. at least ((16x2)+1)x2 = 66, neglecting the long-ranges inside D1
 - Usual train with 72 bunches from PS covers 1 LR encounter inside D1
 - New scheme of 80 bunches covers 3 LR encounters inside D1
 - □ "Weak" beam composed by a short train (even single bunch), with maximum half the number of bunches as compared to the other beam, i.e. 36 to 40 bunches
 - Single bunches allow approaching wire in "nominal" separation
- Very short asymmetric trains may be interesting to study only effect in the area of "round" LR encounters (6-7 per IP side), while keeping their number equal for each bunch
- Effect of head on collisions could be suppressed by timing one beam with respect to other by 12.5 ns, while maintaining number of long range collisions

Experimental set-up (cont.)

- Beams should be initially separated in IP2 and 8
- Number of LR may be adjusted depending on efficiency of correction (location and number of wires)
- May need optics adjustment for optimising optics at wire location (need optics validation, may not be possible)
- Separating in 1 IP and colliding in other may be used to test correction efficiency separately
- If effect is weak, may need to reduce crossing angle
- Final set-up should be tested in "running" LHC conditions
- Different configurations need good preparation and sufficient amount of MD time



Main observables



Lifetime (bunch-by-bunch)

- Need simulations to benchmark the experiments, i.e. track distributions with BBLR + compensation (on-going work of G. Campogiani)
- Disentangle BBLR with respect to other effects such as head on, burn-off, vacuum, IBS, noise,... (on going work of F. Antoniou for LHC luminosity modelling)


Tails evolution

- □ Losses on different collimator positions
- □ Halo diagnostics
- Beam transfer function see Kim et al., HB2008
 - Damper may not allow to have any relevant measurement (gating ?)

Orbit, tune, tune-spread (coupling, chromaticity) Last three are difficult to measure, while in collision 12/05/2015 Y. Papaphilippou - HL-LHC LARP 2015 meeting


Modelling distributions

Configuration and action space evolution for nominal LHC, no compensation, for estimating diffusion rates



Modelling distributions

 Configuration and action space evolution for nominal LHC, no compensation, for estimating diffusion rates
 Need to include other diffusion mechanisms





Required instrumentation

- Diagnostics for one beam needed for the test (the one compensated by the wire)
- Beam Current Transformer, tune-monitor, Beam Synchrotron Light monitor (BSRT), BPMs, Schottky, halo diagnostics
- Bunch-by-bunch diagnostics are essential
- For each observable, need to evaluate expected effect and compare with actual performance of instruments
- Need realistic scaling of long-range effect (elliptic beams) and wire for all observables and corresponding simulations

12/05/2015

Wire effect in single beam




- Need to benchmark effect of wire
- Calibrate position and current with observables:
 - □ Orbit, tune, tunes-spread, coupling (alignment), resonance driving terms, effect on distribution (tails)
- Could be done even at injection energy and conditions (only 1 beam)
 - Experimental conditions and instrumentation as for LHC optics measurements
 - BPMs in orbit and TBT mode, BSRT, wire scanners, Q-Kicker, AC-dipole, etc...
 - □ A lot of information can be already gained with existing wires in SPS



Wires at SPS



- Two 60cm long 3-wire compensators installed in the CERN SPS
 - Different "crossing" plane and even @ 45deg
- Movable in vertical by +/-5mm (remote controlled)
- Water cooled
- About equal beta functions in the transverse planes (~50m)



- Separated by a phase advance of 3deg (similar between BBC and long range interactions in LHC)
- Powered with integrated DC current of up to 360A m (~60 LR collisions in LHC)

12/05/2015



Wires at SPS



Set-up re-evaluated


- New power convertor able to pulse in PPM mode Powering H or V wire, with a switch
- □ Step motors verified and controller in good shape
- □ Vacuum integrity to be checked during next technical stop (June 2015)

BBLR 51772


MDs in 2015 for benchmarking wire models
 At SPS flat bottom in parallel MD cycle (single LHC-type bunches)
 Beam brought close to the wire with closed bump (already checked)
 Effect of wire on orbit, tune, tunes-spread, coupling (alignment), resonance driving terms, beam distribution (tails)


12/05/2015

Optics at the SPS wires



Q26 optics (nominal for FT beam) $\Box \beta_x \sim 53m$, $\beta_y \sim 45m$, $D_x \sim -0.65m$ Q20 optics (nominal for LHC beam) $\Box \beta_x \sim 63m$, $\beta_y \sim 55m$, $D_x \sim -0.75m$





- Experimental tune scans in the SPS with the nominal Q26 (left) and Q20 optics (right).
- Color-code indicates the loss rate during a dynamic scan of the fractional tunes, as (averaging over 4 scan directions)
- Study effect of wire in both optics (measure resonance driving terms)

20/11/2014

BBLR study plans – Short term (2015)

- Simulations considering the positions available with present layout, assuming nominal optics (also ATS)
- Simulate effect on PACMAN bunches
- Establish tolerances for positioning of the wire (hor/ vertical alignment and tilt) and geometry (probably small effect)
- Establish observables for demonstrator measurement campaign and develop experimental program
 Tune-shift with amplitude, resonance driving, lifetime
 - (luminosity modelling)
- SPS wire experiments



BBLR study plans – Medium,



Long term (2015-2018) Simulate effect of wire with HL-LHC parameters and flat beams (talk by S. Valishev)

- Compare global vs. local correction, one vs. many wires per beam and IP, wire vs. other methods (electron lens, multipole magnets)
- Particle scattering on wire for heat deposition and damage (collimation/FLUKA team)
- Check alternative crossing scenarios and filling schemes □ Same planes in both IPs, micro-bunches
- Collective effects with wire compensation
 - □ Impact on beam stability due to tune-spread reduction by wire
- Impedance of wire (some results already exist)
- Impact of noise
- Considerations about different implementation of wire (material)
- BBLR modelling (effect of dispersion, longitudinal slicing, non-Gaussian beam distributions,...)





Thank you very much for your attention

