



# BSM Higgs Sectors

— Probing the Uncolored TeV Scale —

MC4BSM 2015  
Fermilab

18 May 2015

David Curtin  
University of Maryland



# BSM Higgs Sectors

## Big Picture Motivations

- Naturalness
  - SUSY
  - pGB
  - uncolored?
- Electroweak Phase Transition
  - Baryogenesis?
- Higgs Portal
  - Dark Matter?
  - *Generic BSM*

## UV Completions & Rest of Theory

## IR Models

- SM+S (mixed/unmixed)
- SM+fermions
- 2HDM
- 2HDM+S
- SILH
- *SM + hidden sectors* [**displaced**]
- ....

## Observables at Current + Future Colliders

- producing extra higgs states (incl. superpartners)
- Exotic Higgs Decays
- Electroweak Precision Observables
- Higgs coupling measurements
- Higgs portal direct production of new states
- Higgs self coupling measurements
- $Zh$  cross section measurements

# BSM Higgs Sectors

## Big Picture Motivations

- Naturalness
  - SUSY
  - pGB
  - uncolored?
- Electroweak Phase Transition
  - Baryogenesis?
- Higgs Portal
  - Dark Matter?
  - *Generic BSM*

3.

UV Completions  
&  
Rest of Theory

## IR Models

2.

- SM+S (mixed/unmixed)
- SM+fermions
- 2HDM
- 2HDM+S
- SILH
- SM + hidden sectors [**displaced**]
- ....

## Observables at Current + Future Colliders

- producing extra higgs states (incl. superpartners)
- Exotic Higgs Decays
- Electroweak Precision Observables
- Higgs coupling measurements
- Higgs portal direct production of new states
- Higgs self coupling measurements
- Zh cross section measurements

1.

BSM Higgs Sectors

# Observables at Current + Future Colliders

## Observables at Current + Future Colliders

100 TeV ILC/TLEP

- producing extra higgs states (incl. superpartners)
- Exotic Higgs Decays
- Electroweak Precision Observables
- Higgs coupling measurements
- Higgs portal direct production of new states
- Higgs self coupling measurements
- Zh cross section measurements



(HL-) LHC: Discovery machine below  $\sim$  TeV.

*Also, it exists.*

Lepton Collider: All about precision.

100 TeV pp: Intensity Frontier experiment for Higgs Sector

*Important exception: direct production of heavy higgs siblings, and of course probing the rest of the theory / UV completion!*

# Production of Heavy States

The Higgs sector could include more scalar states than just the SM higgs. (e.g.  $A/h_2/H^\pm$  in 2HDMs)

These states are produced via DY or variants of SM Higgs production.

Decay to  $ff, VV, Vh$ . Hard decay products and full reconstruction of intermediate state allow for TeV-reach at HL-LHC, and 5-10 TeV reach at 100 TeV collider.

1502.05653 Djouadi, Maiani, Polosa, Quevillon, Riquer

1504.07617 Hajer, Li, Liu, Shiu

In SUSY, Higgsinos or EWinos are part of the Higgs sector. Generally similar reach, but invisible particles in decay make compressed spectra very challenging.

1410.6287 Gori, Jung, Wang, Wells

1412.4789 Bramante, Fox, Martin, Ostdiek, Plehn, Schell, Takeuchi

**No way around a 100 TeV collider to explore at  $O(\text{TeV}+)$  masses!**

# Exotic Higgs Decays

.. may give first or only probe of new physics:

Tiny higgs width  $\rightarrow$  light BSM particles can couple very weakly ( $\sim 0.01$ ) and produce sizable Brs ( $\sim 10\%$ )

**Higgs portal:** BSM physics wants to couple to the higgs via low-dimensional operators.

$$\Delta\mathcal{L} = \frac{\mu}{\Lambda^2} |H|^2 \bar{\psi}\psi \quad \Delta\mathcal{L} = \frac{\zeta}{2} s^2 |H|^2$$

## Hadron colliders are HIGGS FACTORIES

HL-LHC makes  $\sim 10^7$  Higgses  
100 TeV with 3/ab makes  $\sim 10^8$  Higgses.

1405.1095 Falkowski, Vega-Morales

1412.0018 DC, Essig, Gori, Shelton

Probe **Br(h  $\rightarrow$  very conspicuous)** at the  $10^{-8}$  -  $10^{-7}$  level

## Lepton colliders are CLEAN

1310.8361 Snowmass Higgs Working Group Report

1312.4974 Peskin

Probe **Br(h  $\rightarrow$  arbitrarily stealthy)** at the  $10^{-3}$  level

Should probe **Br(h  $\rightarrow$  a little bit conspicuous)** at the  $10^{-5}$  -  $10^{-4}$  level

*Studies Needed!*

Review/Survey: 1312.4992 DC, Essig, Gori, Jaiswal, Katz, T. Liu, Z. Liu, McKeen, Shelton, Strassler, Surujon, Tweedie, Zhong

# Precision Observables

## Higgs couplings to SM particles

1310.8361 Snowmass Higgs Working Group Report  
1312.4974 Peskin

HL-LHC will measure at  $\sim 5\%$  level


ILC with high lumi can go to  $\sim 0.1\%$ , TLEP few x better.

Many BSM theories give  $O(1-10\%)$  deviations!

## Electroweak Precision Observables

1411.1054 Fan, Reece, Wang

$m_W, m_t, m_Z$  uncertainty will be greatly reduced by ILC/TLEP



Experiment	$S$ (68%)	$f$ (GeV)	$T$ (68%)	$m_{\tilde{t}_L}$ (GeV)
ILC	0.012	1.1 TeV	0.015	890 GeV
CEPC (opt.)	0.02	880 GeV	0.016	870 GeV
CEPC (imp.)	0.014	1.0 TeV	0.011	1.1 GeV
TLEP-Z	0.013	1.1 TeV	0.012	1.0 TeV
TLEP-t	0.009	1.3 TeV	0.006	1.5 TeV


Experiment	$\kappa_Z$ (68%)	$f$ (GeV)	$\kappa_g$ (68%)	$m_{\tilde{t}_L}$ (GeV)
HL-LHC	3%	1.0 TeV	4%	430 GeV
ILC500	0.3%	3.1 TeV	1.6%	690 GeV
ILC500-up	0.2%	3.9 TeV	0.9%	910 GeV
CEPC	0.2%	3.9 TeV	0.9%	910 GeV
TLEP	0.1%	5.5 TeV	0.6%	1.1 GeV

**Lepton collider leads the charge, but 100 TeV (or LHC) has good chance of discovering UV physics responsible for deviations!**



# Higgs Portal Observables (without mixing)


What if TeV-scale new physics **ONLY** couples to the Higgs?



Craig, Englert, McCullough, 1305.5251

⇒  $O(0.5\%)$   $\sigma(Zh)$  deviations.  
TLEP could exclude 0.6%


1310.8361 Snowmass Higgs  
Working Group Report  
1312.4974 Peskin



100 TeV with 30/ab collider has  
mass reach of  $\sim$  few 100 GeV  
via VBF  $h^* \rightarrow XX$  production.

1409.0005 DC, Meade, Yu

1412.0258 Craig, Lou, McCullough, Thalapillil



Shift in  $h^3$  coupling.  
100 TeV with 30/ab can  
exclude 10% shift in  $\lambda_3$ .

1412.7154 Barr, Dolan, Englert,  
de Lima, Spannowsky  
[to be released], W.Yao

These *could* be the only signatures. Mass reach of these probes  
in relevant models is only a few 100 GeV at a 100 TeV collider.

**This is sensitivity is enough for very meaningful statements  
about the electroweak phase transition and naturalness.**

BSM Higgs Sectors

IR Models

# SM + Singlet Scalar

$$V_0^{T=0}(H, S) = -\mu^2 (H^\dagger H) + \lambda (H^\dagger H)^2 + \frac{a_1}{2} (H^\dagger H) S + \frac{a_2}{2} (H^\dagger H) S^2 + \frac{b_2}{2} S^2 + \frac{b_3}{3} S^3 + \frac{b_4}{4} S^4.$$

In generality, this scalar mixes with the higgs after EWSB.

heavy Higgs (sibling) production

Exotic Higgs Decays



EWPO

Higgs Couplings

Higgs portal production

$h^3$  measurement

$\sigma(Zh)$  measurement



# SM + Singlet Scalar

$$V_0^{T=0}(H, S) = -\mu^2 (H^\dagger H) + \lambda (H^\dagger H)^2 + \frac{a_1}{2} (H^\dagger H) S + \frac{a_2}{2} (H^\dagger H) S^2 + \frac{b_2}{2} S^2 + \frac{b_3}{3} S^3 + \frac{b_4}{4} S^4.$$

Difficult case: unbroken  $Z_2$  symmetry  $S \rightarrow -S$

heavy Higgs (sibling) production

Exotic Higgs Decays




EWPO

Higgs Couplings

Higgs portal production

$h^3$  measurement

$\sigma(Zh)$  measurement



Need large higgs portal couplings for  $m_S > m_h/2$

I409.0005 DC, Meade, Yu

# 2HDM (+S)

Most commonly consider four discrete types ( $Z_2$  avoids FCNCs). Type II  $\supset$  (N)MSSM

Model	2HDM I	2HDM II	2HDM III	2HDM IV
u	$\Phi_2$	$\Phi_2$	$\Phi_2$	$\Phi_2$
d	$\Phi_2$	$\Phi_1$	$\Phi_2$	$\Phi_1$
e	$\Phi_2$	$\Phi_1$	$\Phi_1$	$\Phi_2$


Generically, Higgs coupling measurements at ILC/TLEP give mass reach  $\sim 0.5 - 1$  TeV.

However, corrections can be much smaller in alignment limit  $\rightarrow$  have to do direct searches!

$$\kappa_V \sim 1 - 0.5\% \left( \frac{400 \text{ GeV}}{M_A} \right)^4 \cot^2 \beta$$

$$\kappa_t \sim 1 - \mathcal{O}(10\%) \left( \frac{400 \text{ GeV}}{M_A} \right)^2 \cot^2 \beta$$

$$\kappa_b = \kappa_\tau \sim 1 + \mathcal{O}(10\%) \left( \frac{400 \text{ GeV}}{M_A} \right)^2.$$



I310.8361 Snowmass Higgs Working Group Report

I207.4835 Craig, Thomas


I305.2424 Craig, Galloway, Thomas

I310.2248 Carena, Low, Shah, Wagner

HL-LHC gives  $\sim$  TeV mass reach for MSSM (type II).

I502.05653 Djouadi, Maiani, Polosa, Quevillon, Riquer

# 2HDM (+S)



Exclusion Potential

**100 TeV** *hatched:*  
**3 & 30/ab** LHC14  
 0.3 & 3/ab

In **MSSM**,  
 HL-LHC reach is  
 $\approx 1$  TeV.

100 TeV collider  
 probes 5-10 TeV.

I504.07617 Hajer, Li, Liu, Shiu

**Exotic Higgs Decays** could also reveal light states! Easy to get in 2HDM+S (i.e. NMSSM-like), but also in 2HDM.

Motivates extending NMSSM-like exotic higgs decay searches to full kinematically allowed mass range, and to consider most general Yukawa-ordered  $h \rightarrow aa \rightarrow 4f$  decays

I412.4779 DC, Essig, Zhong

I412.3385 Bernon, Gunion, Jiang, Kraml

# Strongly Interacting Light Higgs

Low-energy limit of Composite Higgs or RS-like theories. Assume some new 'strong' sector is responsible for EWSB.

Generically, can be any BSM higgs sector with a perturbative SM-like higgs dof, up to corrections that depend on the strong coupling scale.

$$\delta g \sim \frac{v^2}{f^2}$$

**Lepton colliders can exclude  $f \sim 3 \text{ TeV}$**

1411.1054 Fan, Reece, Wang

(expected effect of higgs mixing/coupling deviations at tree-level),  
or  **$f \lesssim 1 \text{ TeV}$**  (generic effect of hadron-zoo at mass scale  $\sim f$  on EWPO, but could be subject to cancellations).

$$S \sim \frac{4\pi v^2}{m_\rho^2} \sim \frac{N}{4\pi} \frac{v^2}{f^2}$$

Can expect to produce EW resonances with similar mass reach as heavy higgs searches, but more model-dependent. (Also top partners, like in SUSY!)

1402.4431 Pappadopulo, Thamm, Torre, Wulzer

BSM Higgs Sectors

# Big Picture Motivations



BSM Higgs Sectors

Big Picture Motivations

*Naturalness*

*See also talks by Raman Sundrum  
Nathaniel Craig  
Ennio Salvioni*

# Solutions to the Hierarchy Problem

A calculable theory of the higgs mass requires top partners to stabilize the weak scale beyond  $O(500 \text{ GeV})$ .

**Classify such theories by top partner spin and gauge charge.**

This organizes the low-energy signatures of naturalness into a clear pattern.

	<i>scalar</i>	<i>fermion</i>
<i>colored</i>	SUSY	CH/RS
<i>EW</i>	Folded SUSY	Quirky Little Higgs
<i>singlet</i>	?	Twin Higgs

hep-ph/0506256 Chacko, Goh, Harnik  
hep-ph/0609152 Burdman, Chacko, Goh, Harnik  
0812.0843 Cai, Cheng, Terning  
1411.7393 Craig, Knapen, Longhi

....

# Solutions to the Hierarchy Problem

A calculable theory of the higgs mass requires top partners to stabilize the weak scale beyond  $O(500 \text{ GeV})$ .

**Classify such theories by top partner spin and gauge charge.**

This organizes the low-energy signatures of naturalness into a clear pattern.

	<i>scalar</i>	<i>fermion</i>
<i>colored</i>	SUSY	CH/RS
<i>EW</i>	Folded SUSY	Quirky Little Higgs
<i>singlet</i>	?	Twin Higgs

Strong production of top partners

EW DY production of top partners. Interesting decays....

DC, Verhaaren [in preparation]

Tree-level Higgs coupling shifts of  $O(v^2/f^2) \sim \text{tuning}$

Exotic Higgs decays to glueballs of mirror QCD

DC, Verhaaren [in preparation]

Higgs Portal Observables

# Solutions to the Hierarchy Problem

A calculable theory of the higgs mass requires top partners to stabilize the weak scale beyond  $O(500 \text{ GeV})$ .

**Classify such theories by top partner spin and gauge charge.**

This organizes the low-energy signatures of naturalness into a clear pattern.

	<i>scalar</i>	<i>fermion</i>
<i>colored</i>	SUSY <i>mt?</i>	CH/RS
<i>EW</i>	Folded SUSY	Quirky Little Higgs
<i>singlet</i>	?	Twin Higgs

Strong production of top partners

EW DY production of top partners. Interesting decays....

DC, Verhaaren [in preparation]

Tree-level Higgs coupling shifts of  $O(v^2/f^2) \sim \text{tuning}$

Exotic Higgs decays to glueballs of mirror QCD

DC, Verhaaren [in preparation]

Higgs Portal Observables

# (Colored) SUSY

*Direct searches for additional Higgs bosons in the MSSM have  $\sim 1$  TeV reach at HL-LHC and  $\sim 5$ - $10$  TeV reach at  $100$  TeV. (see **2HDM**)*

Within the MSSM, a  $125$  GeV Higgs mass requires either very heavy stops (unnatural) or additional tree-level contributions to the Higgs mass:

F-terms (NMSSM etc)  $\rightarrow$  extra singlet scalar  $\rightarrow$  Extra Higgs production  
Exotic Higgs decays!  
EWPO, etc....

D-terms (non-decoupling D-term models)  $\rightarrow$  new gauge group  $\rightarrow$  DY production of BSM gauge bosons at a few TeV!

hep-ph/0309149 Batra, Delgado, Kaplan, Tait

“Higgs tadpoles” (induced EWSB)  $\rightarrow$  additional Higgs doublet  $\rightarrow$  type I 2HDM  
pheno: LHC14 will probe TeV new states

1306.6354 Galloway, Luty, Tsai, Zhao


1411.6023 Chang, Galloway, Luty, Salvinoi, Tsai

*Of course, a  $100$  TeV collider has exquisite reach for colored stops....*

# Composite Higgs Models

Want Lepton colliders to probe Higgs coupling deviations & EWPO

Want 100 TeV to produce vector resonances of strongly coupled sector (as well as top partners)



# Colorless Electroweak Naturalness

Models with uncolored top partners are usually charged under mirror QCD.


The mirror sector has dark glueballs for EW-charged partners, and also *possibly* for SM singlet partners.

These glueballs have  $< \text{km}$  decay lengths.


0911.5616 Juknevich; 0903.0883 Juknevich, Melnikov, Strassler

The higgs can decay to these glueballs via a top partner loop, which can constitute the discovery signature for uncolored naturalness!

1501.05310 Craig, Katz, Strassler, Sundrum



DC, Verhaaren [in preparation]



These glueballs are naturally in the 10-60 GeV mass range!

⇒ **exotic Higgs decays allow the HL-LHC to probe  $\sim 1$  TeV uncolored Partners!**  
**( $\sim 2-3+ \text{TeV}$  @ 100 TeV)**

# Colorless Electroweak Naturalness

Models with uncolored top partners are usually charged under mirror QCD.

The mirror sector has dark glueballs for EW-charged partners, and also possibly for SM-charged partners.

These glueballs

0911.5616 [hep-ph]

The Higgs can be discovered via a top partner discovery

Displaced signatures from exotic Higgs decays through a Hidden Valley are the


**smoking gun** of **Folded SUSY** - type theories of uncolored naturalness!

mirror glueball

mirror glueball

in [in preparation]

the 10



⇒ **exotic Higgs decays allow the HL-LHC to probe ~ 1 TeV uncolored Partners! (~ 2-3+ TeV @ 100 TeV)**



# Neutral (Singlet) Naturalness

**Fermionic top partners** *without* any SM charge *always* lead to tree-level Higgs coupling shifts.  $\Rightarrow$  In known theories, detectable at lepton colliders for partner masses  $\lesssim 1\text{-}2\text{ TeV}$ !

What about SM singlet **scalar top partners**? No theory yet, but might be able to write one down....

In that case, would have to rely on *Higgs Portal Observables* at future colliders:

**$h^* \rightarrow SS$  production** (100 TeV)

**$\sigma(Zh)$  shift** by partner loops (ILC/TLEP)

**triple higgs coupling shift** by partner loops (100 TeV)

Sensitive to singlet scalar top partners at  $\sim 300\text{ GeV}$

If there is a mirror QCD,  $h \rightarrow$ invisible decays at lepton colliders *might* be sensitive to  $\sim 400\text{ GeV}$

**However, the 100 TeV collider can probably access the UV completion of these models directly.**


BSM Higgs Sectors

Big Picture Motivations

# *Electroweak Phase Transition*

# Electroweak Phase Transition


In the early universe at  $T \gg 100 \text{ GeV}$ , interactions with the plasma stabilize the Higgs boson at the origin.



Many reviews, e.g.  
Quiros hep-ph/9901312

Understanding this important part of cosmological history requires understanding the Higgs potential away from our current vacuum.

With some BSM ingredients, the EWPT can be made strongly *first order*.



This results in *bubbles* of true vacuum expanding in the universe. The resulting departure from thermodynamic equilibrium can cause **Electroweak Baryogenesis** if there is a new source of CPV in the plasma.

The Electroweak Phase Transition is very difficult to probe at colliders.

# Achieving a strong EWPT

Need to modify the Higgs potential to get barrier:

$$V_{\text{eff}}(h, T) = V_0(h) + V_0^{CW}(h) + V_T(h, T)$$

## Tree Effects

Add scalars to modify shape of the Higgs potential at tree-level,

## Loop Effects

Add particles whose loop interactions reduce the depth of the Higgs potential well.

## Thermal Effects

Add new *bosons* with large Higgs couplings to the plasma.

# Achieving a strong EWPT

Need to modify the Higgs potential to get barrier:

$$V_{\text{eff}}(h, T) = V_0(h) + V_0^{CW}(h) + V_T(h, T)$$

## Tree Effects

Add scalars to modify shape of the Higgs potential at tree-level,

## Loop Effects

Add particles whose loop interactions reduce the depth of the Higgs potential well.

## Thermal Effects

Add new *bosons* with large Higgs couplings to the plasma.



Mass is  $< 200$  GeV.  
Produce directly,  
modify Higgs couplings.

Cohen, Morrissey, Pierce 1203.2924,  
DC, Jaiswal, Meade 1203.2932

Carena, Nardini, Quiros, Wagner 1207.6330

Katz, Perelstein 1401.1827

# Achieving a strong EWPT

Need to modify the Higgs potential to get barrier:

$$V_{\text{eff}}(h, T) = V_0(h) + V_0^{CW}(h) + V_T(h, T)$$

## Tree Effects

Add scalars to modify shape of the Higgs potential at tree-level,

## Loop Effects

Add particles whose loop interactions reduce the depth of the Higgs potential well.

## Thermal Effects

Add new *bosons* with large Higgs couplings to the plasma.

Do *not* require very light particles.  
Can realize this e.g. in SM+S model.

Many parameters, and many potential Higgs sector experimental observables.

Mass is  $< 200$  GeV.  
Produce correctly,  
modify Higgs couplings.

Cohen, Kaplan, Pierce 1203.2924,  
Datta, Jaiswal, Meade 1203.2932  
Carena, Nardini, Quiros, Wagner 1207.6330  
Katz, Perelstein 1401.1827


**Can a strong EWPT be generally excluded?**

Need to study a model with *minimal signatures* that we can explore completely.

# Minimal stealthy model for a strong EWPT

$$V_0 = -\mu^2 |H|^2 + \lambda |H|^4 + \frac{1}{2} \mu_S^2 S^2 + \lambda_{HS} |H|^2 S^2 + \frac{1}{4} \lambda_S S^4$$

Unmixed SM+S. No exotic higgs decays, no higgs-singlet mixing, no EWPO, ...



Two regions with strong EWPT

Only Higgs Portal signatures:

$h^* \rightarrow SS$  direct production

Higgs cubic coupling

$\sigma(Zh)$  deviation ( $> 0.6\%$  @ TLEP)

100 TeV collider could cover entire parameter space.

TLEP (super ILC) can cover some of parameter space.


Potential complementarity!

1409.0005 DC, Patrick Meade, Tien-Tien Yu

# Minimal stealthy model for a strong EWPT

$$V_0 = -\mu^2 |H|^2 + \lambda |H|^4 + \frac{1}{2} \mu_S^2 S^2 + \lambda_{HS} |H|^2 S^2 + \frac{1}{4} \lambda_S S^4$$

Unmixed SM+S. No exotic higgs decays, no higgs-singlet mixing, no EWPO, ...



## Two regions with strong EWPT

## Only Higgs Portal signatures:

g  
0.6% (@ TLEP)

could cover  
ter space.

TLEP (super ILC) can cover  
some of parameter space.

## Potential complementarily!

## 1409.0005 DC, Patrick Meade, Tien-Tien Yu



# Conclusions

# Conclusions

- The Higgs program provides enormous experimental challenges and opportunities. **Considering non-standard signatures is paramount!**
- The resulting information would allow us to constrain or construct the low-energy Higgs sector, *which could easily be very non-SM-like!*
- This is vital to understand whether nature is **natural**, the **electroweak phase transition / baryogenesis**, and general **BSM** via the agnostic Higgs portal.
- **Both lepton and 100 TeV pp colliders are vital for this effort!**

## Observables at Current + Future Colliders

- producing extra higgs states (incl. superpartners)
- Exotic Higgs Decays
- Electroweak Precision Observables
- Higgs coupling measurements
- Higgs portal direct production of new states
- Higgs self coupling measurements
- Zh cross section measurements

## 100 TeV

## ILC/TLEP



# Conclusions

## **MC opportunity:**

Interface between  
sophisticated SM Higgs Tools (NNLO, NLL, ...)  
and  
generic BSM Higgs Portal models.

c.f. Matthew McCullough

e.g.

1412.0018 DC, Essig, Gori, Shelton

1412.0258 Craig, Lou, McCullough, Thalapillil

1409.0005 DC, Meade, Yu