



Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

Status of SSR1 and SSR2


Leonardo Ristori
P2MAC Meeting
9-10 March 2015



Overview

- 325 MHz section of PIP-II Linac
- SSR1 & SSR2 Cryomodules
- SSR1 development
 - Focusing elements
 - SRF cavities
 - Tuners
 - Couplers
- SSR1 schedule
- SSR1 collaboration with IUAC
- SSR2 design status


PIP-II Superconducting Linac (RDR 2.1.3)



CM type	Cavities per CM	Number of CMs	CM configuration*	CM length (m)	Q_0 at 2K (10^{10})	Surface resistance, (n Ω)	Loaded Q (10^6)
HWR	8	1	8 \times (sc)	5.93	0.5	9.6	2.7
SSR1	8	2	4 \times (csc)	5.2	0.6	14 ($10^{\#}$)	3.7
SSR2	5	7	sccscsc	6.5 [♦]	0.8	14.4	5.8
LB650	3	11	ccc	3.9 [♦]	1.5	12.7	11.3
HB650	6	4	cccccc	9.5 [♦]	2	13	11.5


SSR1 Cryomodule

T. Nicol, Y. Orlov



5.2 m long
8 Cav + 4 Magnets
Bottom-supported elements
with warm strongback



SSR2 cryomodule



6.5 m long
5 Cav + 3 Magnets

SSR1 CAVITY-MAGNET STRING


- 2 versions of cavities (A & B)
- 4 Solenoids+BPM
- Vacuum manifold
- 13 interconnecting bellows (4 types)



Focusing Elements


I. Terechkin

Lens strength ($T \cdot m$)	4
Steering dipole strength ($T \cdot m$)	$2.5 \cdot 10^{-3}$
Insertion length, max. (mm)	160
Ferromagnetic shielding	NO
Magnetic field on Cavity, max. (μT)	$0.5 \cdot Q_0$ criterion
Transverse misalignment (mm)	0.5 RMS
Angular misalignment (mrad)	1 RMS




Axial Field: Measured vs Predicted


Excellent agreement between predicted and measured performances



Quench Performance at 4 K and 2 K




Cavity Q degradation predicted vs measured



SECTION A-A

Outer can is not supplied by Cry

Effects of magnetic field trapping during quenching



Solenoid installed on SSR1 during VTS tests

Focusing Elements

I. Terechkin


Production completed, cold tests next month

Prototype FL

1. Prototype lens' cold mass procured and tested at 2 K
2. The lens assembled and re-tested
3. Position of magnetic axis was measured by the vendor and at Fermilab: $\Delta R < 0.2$ mm; $\Delta\alpha < 0.7$ mrad



Field Map & Level lines (T) Contour: Magnetic flux density norm (T)





Maximum field on the surface of the cavity is below 5 G.

Quench protection studies

Voltage to the ground in the main coil Temperature in quenching bucking coil


Production FL

1. Four production lenses' cold masses procured and tested at 4 K by the vendor.
2. The lenses have been prepared for the final performance test in the VTS at 2 K.








SSR1, SSR2 – Main Requirements

	SSR1	SSR2
Frequency	325 MHz	
Operation	Pulsed / CW	
β_{OPT}	0.222	0.475
Gain/cav	2 MeV	5 MeV
Q_0 at 2K	$> 0.6 \cdot 10^{10}$	$> 0.8 \cdot 10^{10}$
B_{peak}	58.1 mT	64.5 mT
E_{peak}	38.4 MV/m	40 MV/m
Surface Res	14 n Ω	14 n Ω
L_{EFF} ($\beta\lambda$)	205 mm	438 mm
G	84 Ω	115 Ω
R/Q	242 Ω	296 Ω
LFD sensitivity	$< 5 \text{ Hz}/(\text{MV}/\text{m})^2$	
Tuning constant	40 N/kHz	90 N/kHz
LHe Sensitivity	$< 25 \text{ Hz}/\text{torr}$	



SSR1










Figure 6: Development of multipacting in time at accelerating gradient of 7 MV/m.



Lorenz-Force Detuning studies


The LFD factor of SSR1 was studied with various boundary conditions.
 In working conditions the predicted LFD factor is less than $-3 \text{ Hz}/(\text{MV}/\text{m})^2$
 The requirement is $< 5 \text{ Hz}/(\text{MV}/\text{m})^2$

Prototype




Spring Const [kN/mm]	LFD [Hz/(MV/m) ²]
∞	-1.69
4000	-1.69
400	-3.38
40	-5.07
0	-7.6

Production



Spring Const [kN/mm]	LFD [Hz/(MV/m) ²]
∞	-2.74
4000	-2.95
200	-4.63
100	-4.85
40	-5.27
0	-5.48



SSR1- Sensitivity to He pressure variations

D. Passarelli

SSR1 must operate within a small bandwidth ± 20 Hz


Pressure of L_{He} can vary by ± 0.5 Torr in the cryomodule

A self-compensating design was developed allowing low sensitivity


Despite non-negligible deformations (see picture), net shift is very low thanks to Slater's Theorem

Bare cavity ~ 600 Hz/Torr, with He vessel \sim 10 Hz/torr

Ease of tuning 39 N/kHz (bare), 40 N/kHz* (with He vessel)



* It is possible to reduce sensitivity without increasing rigidity





- Deformations in high E and B regions balance out resulting in a small frequency shift (Slater's Theorem)

Harmonic Analysis – SSR1

L. Ristori


Oscillating force $f(x,y,z)$



Results					
Minimum	0. m				
Maximum	0.14647 m	0.16846 m	0.29507 m	0.41893 m	0.41125 m
Minimum Occurs On	Part 33				
Maximum Occurs On	Part 25	Bellows	ssr1_rf	Bellows	
Information					
Frequency	114.77 Hz	127.92 Hz	276.87 Hz	326.31 Hz	378.96 Hz

Processing/Testing steps (ANL, FNAL)

1. Inspection – RF & Optical
2. BCP 120-150 μm (flip half-way)
3. HPR
4. 600 $^{\circ}\text{C}$, 10 h (< 5 $^{\circ}\text{C}/\text{min}$ ramp rate)
5. RF Tuning
6. BCP 20-30 μm
7. HPR (horiz + vert)
8. Assemble
9. Evacuate + 120 $^{\circ}\text{C}$, 48 h
10. Vertical Test
11. Helium Vessel Dressing
12. RF Tuning
13. BCP 20-30 μm
14. HPR
13. Assemble
14. Evacuate + 120 $^{\circ}\text{C}$, 48 h
15. Horizontal Test
16. Ready for String



Status of SSR1 cavities

OPERATION -->	Deep drawing	Sub-assy EBW	Freq trimming	Final EBW	Delivery to FINAL	IB4 Visual QC	IB4 Dimensional QC	IB4 RF QC	IB4 Leak QC	ANL Bulk BCP	ANL HPR	MP9 600 C Bake	IB4 RF Tune	ANL Light BCP	ANL HPR + Prep for VTS	MP9 120 C Bake	VTS (IB1) VTS Tests	ROARK Ring EBW	IB4 RF Tune	MEYER TOOL Jacketing	IB4 Visual QC	IB4 Dimensional QC	IB4 RF QC	IB4 Leak QC	IB4 RF Tune	ICB Flange Polishing	ICB Thread Maintenance	ANL Light BCP	ANL HPR + Prep for STC	MP9 120 C Bake	STC (MOB) STC Tests	
TRAVELER # -->	-	-	-	-	-	333990	333884	464013	464012	333862	464022	464116	464121																			
LINKS TO DETECTOR (ONSITE ACCESS ONLY)	Leonardo	Leonardo	Leonardo	Leonardo	Leonardo	Donato	Donato	Paolo Mohamed		Brent	Margherita		Paolo Mohamed	Brent	Brent	Margherita	Anisa Sukhanov Sengalskero	Leonardo	Paolo Mohamed	Donato	Donato	Donato	Paolo Mohamed			Paolo Mohamed	Damon	Damon	Brent	Brian	Margherita	Andy, Joe
S103 travelers																																
S104 travelers																																
S105 travelers					no estimate																type B											
S106 travelers					8-Jan-14												20 MV/m				type A											
S107 travelers					4-Nov-11												22 MV/m				type A					skipped	skipped					in proc.
S108 travelers					4-Nov-11												21 MV/m				type A	in proc.										
S109 travelers					19-Dec-11												20 MV/m				type A	in proc.										
S110 travelers					19-Dec-11												17 MV/m				type A											
S111 travelers					31-Dec-12												19 MV/m				type B											
S112 travelers					10-Dec-12												17 MV/m				type B											
S113 travelers					10-Dec-12												19 MV/m				type B											
S114 travelers					31-Dec-12												21 MV/m				type B											
S1H-RK-115	in proc.				no estimate																											

9 of 10
Delivery
(Bare Cavity)

9 of 10
Cold Test
(Bare Cavity)



3 of 10
Jacketing

1 of 10
Cold Test
(Jacketed Cavity)

- Most of the 10 production cavities are in the jacketing stage
- S107 is leading the group, 2nd test in STC to qualify prototype coupler and tuner
- S106 and S105 are trailing due to repairs


Vertical Test Stand (VTS)

Successful qualification of production cavities for PXIE cryomodule





Spoke Test-Cryostat (STC) – S107 Run 1

A. Hocker, A. Sukhanov



Sep-Oct 2014
 Successful cold tests of first production
 SSR1 (S107) and piezo encapsulations






Parameter	Req.
Coarse range	> 135 kHz
Fine range	> 1 kHz
Coarse resol.	< 20 Hz




Piezo encapsulations include bellows for retainment


Alignment system for main arms



Installation of cartridge




Cartridge with motor and piezos




Couplers

- We have 3 prototypes
 - 2 installed on RF test stand, 1 installed on first production cavity in STC
- Design was changed to address several issues
 - upgrade to aluminum seals, increase thickness of electro-deposited bellows,...
- All components for 10 production couplers have been ordered
 - cold-ends are needed for qualification of cavities


325 MHz Test Stand




325 MHz coupler anatomy




Prototype couplers



Warm Outer conductor
Electro-deposited bellows
(Cu-Ni layers)



Warm Inner conductor






Cold-end assembly




RF test stand

Preparations for Run 2 – Installation of prototype coupler



- All work done at MP9
- Unity coupler was replaced with prototype high-power coupler



S107 – Run 2


Prototype tuner

mascot
"Pip"




Prototype coupler


Other cryomodule components received as of today..



Vacuum vessel



Focusing Elements




Support Posts



Strong-back


SSR1 Cryomodule Schedule

- String assembly rehearsal
 - July - Aug 2015
- Cav. qualifications
 - Nov 2015 - Apr 2016
- String assembly
 - May - July 2016
- Cold mass assembly
 - Aug - Nov 2016
- Cryomodule assembly
 - Oct 2016 - May 2017




SSR1 - Collaboration with IUAC (New Delhi) – P.N. Prakash


- IUAC is developing 2 SSR1 cavities
- Slightly different process with EP components (instead of BCP)
- Interesting to compare results
- Delivery this year



Most severe multipacting take place near transition of cylindrical part to end walls. Several design options of this transition was considered. Most significant improvement was achieved after introducing additional step in the transition area.



Modification of this transition reduce multipacting in operating range of cavity fields.



Parameters	SSR2 v1	SSR2 v2.6
Optimal beta	0.471	0.475
E _{peak} /E _{acc}	3.45	3.69
B _{peak} /E _{acc} [mT/(MV/m)]	6.107	5.95
G [Ohm]	112.98	114.9
R/Q [Ohm]	289.94	295.6

Secondary Emission Yield (SEY) significantly reduced in the operating gradient range of 5-12 MV/m. Comparison with SSR1 cavity demonstrates that multipacting in the modified SSR2 cavity version 2.6 can be processed away easier than in SSR1 cavity.

Summary

- Production of SSR1 cryomodule has begun
 - All bare cavities tested successfully
 - 1st Jacketed cavity tested successfully
 - Prototype coupler and prototype tuner under testing
 - All bare solenoids tested successfully
 - Large components received
- SSR1 cryomodule estimated to be completed in May 2017
- IUAC will deliver (2) SSR1 cavities to FNAL
- Design of SSR2 recently changed to address MP



Thank you ...

Backup Slides

SSR1 Prototypes – VTS tests





S101 – 4th test



- During cool down, a 7 hr hold at 100 K produced a large Q0 drop, confirming **Q disease**.
- Subsequently baked SSR1-01 at 600 C for 10 hours at Jlab.

S102 – 1st test

- Effects of Q disease should not appear on first cooldown.
- X-rays increase at MP barriers, then disappear after punch through.



SSR1 Prototype – STC Tests



- Assembly procedure
- Meeting the technical specification
- Feature of interest

SSR1 Tuner: Requirements and data

<i>Parameter</i>	<i>Value</i>	<i>Notes</i>
Total Frequency Range	> 135 kHz	From FRS
Frequency Resolution of stepper motor	< 20 Hz	From FRS
Piezo Frequency Range	> 1 kHz	From FRS
Tuner Passive spring constant	30 kN/mm	Derives from df/dP requirement
Sensitivity of end-wall	540 kHz/mm	Simulation/Experimental
Cavity wall spring constant (K_{cav})	30 kN/mm	Simulation/Experimental


<i>Parameter</i>	<i>Value</i>	<i>Notes</i>
Stepper motor max force	± 1300 N	Symmetrical
Stepper motor resolution*	0.1 μ m (100 nm)	At interface with 2 nd lever
Piezo stroke @ RT	64 μ m \pm 2%	Measured
Piezo stroke @ operating T	15 μ m (25% of RT)	
Piezo max rated force	3360-5040 N	4200 N \pm 20% (blocking force)
Piezo max operating force	2688 N	3360 \cdot 80%

<i>Parameter</i>	<i>Value</i>	<i>Notes</i>
Motor Travel at beam pipe	> 0.25 mm	135/540 kHz
Piezo Travel at beam pipe	> 1.85 μ m	1/540 kHz
Maximum Force at beam pipe	7500 N	0.25 mm \cdot 30000 N/mm
Motor Resolution at beam pipe	< 37 nm	20/540000 mm
Motor Tuning Efficiency (T_e)	< 37 %	37/100 nm
Motor Mechanical Advantage (M)	> 5.8	7500/1300 N, picked 6
Piezo Tuning Efficiency (T_e)	> 12 %	1.85/15 μ m
Piezo Mechanical Advantage (M)	> 1.4	0.5* \cdot 7500/2688 N, picked 2
Piezo Elastic Efficiency (E)	> 24 %	2 \cdot 12 % ($T_e \cdot M$)

ASME Pressure Rating


D. Passarelli

The table summarizes the results obtained by simulations performed following the Div 2, Part 5 directions. It **shows** that the desired MAWP is achieved both at RT and CT.




Jacketing operations

D. Passarelli, M. Hassan, P. Berrutti



Thermal cameras insertion tubes (above)



Welding inch-by-inch on 6 mm thick steel

Large fixtures needed to control warping



Screenshot of remote connection from FNAL

