

# SLAC Proposal for PX RF Systems

Chris Adolphsen



# SLAC Interests in PX L-band RF System

- Modulator charging supply – develop 80% main for multiple modulators plus 20% individual supplies
- Modulators – Marx alternative and baseline modifications
- Klystrons – Multi-beam klystron long-term testing (Toshiba, CPI, ..) and sheet beam and other alternatives
- RF Distribution System – adapt version being developed for NML cryomodules
- Intra-pulse amplitude and phase shifter – develop less expensive version
- LLRF – develop control algorithms based on FLASH experience (but probably not hardware)
- Couplers – see earlier talk


# XFEL High Power RF Status

S. Choroba


## RF High Power Source

### Horizontal MBK prototypes

- Horizontal versions of MBKs by all 3 vendors are under construction (THALES, TOSHIBA, CPI)
  - First klystron has been tested at DESY (Toshiba, December 07 to February 08)
- TOSHIBA E3736H  
THALES TH1802



- #6 passed acceptance test at Thales, **passed acceptance test at DESY**  
**(10MW,  $\eta=61\%$ )**
- #7 passed acceptance test at Thales, **passed acceptance test at DESY**  
**(10.5MW on matched load,  $\eta=62\%$ )**
- 1 TOSHIBA E3736 at DESY
  - 10.4MW, 1.5ms, 10Hz, 66%
  - 750h, ~80% at full power
  - **will be used at the modulator test stand in Zeuthen**




## Modulator

### Qualification of additional vendors


#### Bouncer Modulator by Imtech/Vonk

- Bouncer Type, as specified by DESY
  - 12kV HVPS
  - Bouncer 300uH/4.6kA
- 7st IGBT main switch
- Digital Regulation Circuit
- Analog In- and Outputs
- Well known and tested principle
- delivery time: 12 month



#### PSM Modulator by Thomson BM

- Different Type:
  - 12kV/2kA w. transformer
  - Pulse Width Modulation
  - 24 switching stages in series
  - FPGA based control
  - 2 stages for redundancy
- Slew rate and pulse shape controllable
- detailed description available, principle already successfully tested (worldwide, i.e. W7/X)
- delivery time: 14 month



# FNAL Pulse Transformer Modulator Layout



Capacitor Banks



IGBT Redundant Switch

Bouncer Choke

# Development Status of the ILC Marx Modulator

Craig Burkhart

## P1-Marx Status

- Developmental Testing in B015 Completed
  - Operational Testing
    - Full voltage (120 kV), current (140 A) and pulse length (1.6 ms) with coarse flattening
    - Full PRF (5 Hz)
    - Near full power (135 kW), load limit ~100 kW, HVPS limit ~120 kW
    - Several shifts without intervention
  - Arc-down Testing (Simulated Klystron Arc)
  - Integrated into “Sealed” Enclosure
- Install in L-Band Test Station in ESB for Extended Life Tests
  - Marx Control System Upgrades: EPICS interface
  - L-band Test Stand Interlocks and Control
- Improve Output Voltage Regulation to  $\pm 0.5\%$ 
  - Vernier Regulator

## Normal Operational Testing



- Coarse Pulse Flattening
  - 16 Cells: 11 prompt, 5 delayed
  - 0.86 k $\Omega$  water load
- Efficiency Measurement
  - Total power efficiency: 97%
  - Usable (RF) efficiency: 92%




***DTI Marx Modulator for ILC (DOE SBIR)***

- Specs: 120-150 kV, 120-150 A, 1.5 ms, 5 Hz
- Marx Topology used to beat cap droop
  - Initially erect pulse with optimized Marx, using twenty modules at 6.0 kV each
  - Maintain flattop by sequencing in additional modules: sixteen at 900 V each
- Total system: 170 kJ to deliver 30 kJ pulse -  $\pm 0.5\%$ 
  - electrolytic capacitors used for lower volume
  - N+1 redundancy on caps and switches, with internal diags
- Internal Buck Regulator at prime input voltage (6 kV)
  - no external power supply, runs off unregulated DC

## Marx Program Status Summary

- SLAC P1-Marx
  - Developmental Testing: Complete
  - Initial ESB Operation: 11/08
  - Integration into L-Band Station: Early '09
  - Output Regulation ( $\pm 0.5\%$ ): 3/09
- SBIRs
  - Complete '09
  - Hardware to SLAC: FY10
- SLAC P2-Marx
  - Initial Design/Components Ordered: 12/09
  - 1<sup>st</sup> Cell Assembly & Testing: FY09-Q2&3
  - Multi-Cell Testing: FY09-Q4
  - Final Design/Components Ordered: FY10-Q1
  - Cell Assembly: FY10-Q2
  - Modulator Testing: FY10-Q3&Q4

# SLAC/KEK Toshiba 10 MW MBK





6-Beam  
Gun



# Test Results at Toshiba


Efficiency and Output Power -vs- Beam Voltage



Effect of a Mismatch  
(VSWR = 1.2):  
Output Power -vs-  
Phase of Mismatch


# New Station Nearing Completion

- In early 2009, the Marx Modulator will be used to power the 10 MW Toshiba MBK for long-term evaluation.
- Built oil tank to support the MBK, a water load, and a filament PS transformer.
- Water load can dissipate the full output power of the modulator in the absence of a klystron



# LSBK Development Status

Erik Jongewaard



## LSBK Program Plan


### Beam, RF and Interaction Status

- Build a flexible beam test diode to verify 3-D gun simulations.
  - Beam profile measurement capability for electrostatic and magnetic focusing cases
  - Modular design to allow quick modifications and component changes
- In parallel develop a klystron to be fabricated immediately after the beam test diode.

- Electron gun:
  - Simulations complete
- Beam Transport:
  - 3D magnetics design complete for diode
  - Klystron magnetics in progress
- RF circuit:
  - Cavity loading design complete
- RF-Beam Interaction:
  - TE mode discovered, studies underway for suppression

### Mechanical Design Status



- Electron gun:
  - Three cathodes in house
  - FE machining in progress
  - Assembly beginning
- Anode assembly:
  - Brazed assemblies in final machining
- Beam diagnostic:
  - Sub assembly brazing complete
  - Assembly of vacuum chamber beginning
- Klystron design on hold for TE mode resolution



# Distributed RF Source (DRFS) Scheme



One Klystron feeds power to a few cavities.

S Fukuda



Total amount  
X 26 X 650  
=16900

BCD	DESY	Shallow Tunnel	RF Cluster	DRFS



## Likely Plan

- There are several merits in DRFS.
- Complete single tunnel scheme and simple configuration. (Cost benefit is expected)
  - Klystron failure doesn't give a serious effect to beam operation since failures are scattered. (cf. BCD, RF Cluster)
  - Adoption of MAK leads to the cheap HLRF system and introduction of power handling is possible for klystron.
  - Direct connecting of about 60kV to klystron eliminates pulse transformer and use of huge insulation oil.
  - LLRF control is easy and vector sum of 2 cavities are better than BCD plan.
  - By coupling two cavities with same performance, circulators are possibly eliminated.
  - There are lots of advantages for the operation and control.

- Circulator elimination by power feeding to 2 cavities from one klystron. Output power is 732kW.
- Modulated Anode Klystron (MAK) is adopted.
- Anode modulation pulser does not need the high power and cost efficient pulser is manufactured.
- DC Power Supply is common for 26 cavities and voltage drop during the pulse is compensated with appropriate circuits at the level that LLRF can feed back.

**Cost estimates being made**

# HLRF Interlock Module and ATCA\* Platform R&D Plan


Ray Larsen

## Summary Status & Plans


- VME Interlock System
  - F3 FPGA based test stand interlock system in test, hardware installation continuing, interlock software nearing completion
- VME-ATCA Adapter
  - Board loading underway; will need IPMI, driver software development to complete
  - Reference design for future AMC carrier board
  - Future: Implement ATCA adapter version of test stand interlocks
- AMC's in MicroTCA promising for future controls upgrade
  - Commercial AMC, IP products can perform most SLAC linac controls functions
  - Collaborating with DESY to get fast ADC Firmware
  - Plan initial experimental tests in FY 09
- *Future:*
  - *Port controls designs directly to generic AMC FPGA modules with front-end plug-in options*
  - *optimize use of xTCA infrastructure over more payload modules*

# Fast Fault Finder

- Replaces PLC and NIM logic to protect klystron (the modulator has its own interlock system)
- All signals, fast (e.g., rf or light) or slow (e.g., flow or PS current), are pre-conditioned to the same voltage range and sampled by a 20 MHz, 12 bit ADC and sent to a FPGA to generate fast ( $< 1 \mu\text{s}$ ) or slow ( $< 1 \text{ms}$ ) fault signals based on high/low thresholds of individual channels or channel differences.
- Currently, four VME boards (4 fast, 10 slow channels each) are being tested.



# ILC Baseline RF Distribution System




Fixed Tap-offs

Circulators

3-Stub Tuners

# ILC Alternative RF Distribution System

Currently Building This Version for FNAL Cryomodules



Variable Tap-offs (VTOs)

3 dB Hybrids

Phase Shifters




# ELECTRONICALLY ADJUSTABLE E-H TUNER

MICROWAVE INPUT POWER  
from Klystron and Circulator

Attractive Price  
Quote from AFT  
( $\ll$  Klystron)

## E-H TUNER

ELECTRONIC TUNING  
WITH BIASED FERRITE




FERRITE LOADED  
SHORTED STUBS  
CHANGE ELECTRICAL  
LENGTH DEPENDING ON  
DC MAGNETIC BIAS.

**TWO COILS** PROVIDE INDEPENDENT  
**PHASE AND AMPLITUDE** CONTROL OF CAVITIES

# AFT E/H Tuner Prototype

Minimum Insertion Loss	< 0.2	dB
Amplitude Modulation	0 to -3dB	dB
Insertion Loss Modulation	0.2 to 3.2	dB
Differential Phase Modulation	-45 to +45	°
Response Time	30 $\mu$ s	for 63%


Cost Each in Quantity Estimated to be 30 k\$ (WG) + 15 k\$ (PS) + Second 8 k\$ Circulator



# TTF/FLASH 9mA Experiment

## Recent Machine Studies and Results

John Carwardine, Gustavo Cancelo, Nick Walker




10 MeV over 550 bunches  
(~1%)  
(~4 MeV over 1<sup>st</sup> 500)

Stable operation with 450 bunches

- Several hours of data
- Currently under analysis

Long bunch trains (~2.5 nC/bunch)

- 550 bunches at 1MHz
- 300 bunches at 500KHz
- 890 MeV linac energy





All modules (RF) running with  
800us flat-top and 1GeV total

Increase from 450 to 550 bunches  
eventually caused vacuum event

# FLASH Beam-OFF Cavity Probe Signal Analysis

Correlation of Jitter Amplitude RMS & Detuning RMS  
for the 24 Cavities in ACC 4-6



# RF Control Models & Simulators

## (Goal: A Common Matlab Model)


Gustavo Cancelo  
Brian Chase



### Models and Simulators

- Accepted model for the cavities (Tesla)
  - Dependent on dressed cavity
- Model for HLRF is dependent
  - Drive amplifier
  - Modulator type and specific
  - klystron (3 types)
  - Distribution scheme
- Model for LLRF is dependent
  - Design variations
  - Distribution scheme
- Present simulator features:
  - Cavity, klystron response, Q, etc.
  - Drive amp response, receive
- Goal: A common Matlab simulator
  - We are fairly close

### RF block diagram and equivalent LLRF Control diagram



11/19/08

LCWS08



# Elements of a PX RF System R&D Program

- Continue ILC efforts on ACD modulators, klystrons and rf distribution systems
- Do long term testing of baseline klystrons (acquire CPI version ?) in parallel with XFEL mod/kly test and industrialization program
- Assess implications of doubling pulse length and pulse rate on rf sources
- Develop affordable fast phase/amplitude shifter for the low energy end of the linac (full linac ?). Also measure power limits of rf distribution components.
- Examine other rf source possibilities (e.g. one source per cavity) that are not driven by large scale of ILC and that may have higher average power capabilities
- Better understand the implications of the  $\beta < 1$  proton beam for the cavity gradient regulation
- Increase efforts on understanding cavity perturbations in FLASH and the control algorithms required to keep the beam energy stable.