



Outline



- Role of Project X
- Project X Reference Design
- Beam Configurations
- Project Status and Timeline

Project X website: http://projectx.fnal.gov




Fermilab Strategic Plan



Fermilab is the sole remaining U.S. laboratory providing facilities in support of accelerator-based Elementary Particle Physics. Fermilab is fully aligned with the strategy for U.S. EPP developed by HEPAP/P5.

⇒ The Fermilab strategy is to mount a world-leading program at the intensity frontier, while using this program as a bridge to an energy frontier facility beyond LHC in the longer term.

Project X is the key element of this strategy





Mission Elements



- A neutrino beam for long baseline neutrino oscillation experiments
 - 2 MW proton source at 60-120 GeV
- High intensity, low energy protons for kaon, muon, and neutrino based precision experiments
 - Operations simultaneous with the neutrino program
- A path toward a muon source for possible future Neutrino Factory and/or a Muon Collider
 - Requires ~4 MW at ~5-15 GeV
- Possible missions beyond EPP
 - Standard Model Tests with nuclei and energy applications





Concept Evolution




- Three Project X configurations have been developed, in response to limitations identified at each step:
 - Initial Configuration-1 (IC-1)
 - 8 GeV pulsed linac + Recycler/MI
 - Fully capable of supporting neutrino mission
 - Limited capabilities for rare processes
 - Initial Configuration-2 (IC-2)
 - 2 GeV CW linac + 2-8 GeV RCS + Recycler/MI
 - Fully capable of supporting neutrino mission
 - 2 GeV too low for rare processes (Kaons)
 - Ineffective platform for Neutrino Factory or Muon Collider
 - Reference Design
 - 3 GeV CW linac + 3-8 pulsed linac + Recycler/MI
 - Ameliorates above deficiencies



Reference Design







Reference Design Capabilities



- 3 GeV CW superconducting H- linac with 1 mA average beam current.
 - Flexible provision for variable beam structures to multiple users
 - CW at time scales >1 μ sec, 10% DF at <1 μ sec
 - Supports rare processes programs at 3 GeV
 - Provision for 1 GeV extraction for nuclear energy program
- 3-8 GeV pulsed linac capable of delivering 300 kW at 8 GeV
 - Supports the neutrino program
 - Establishes a path toward a muon based facility
- Upgrades to the Recycler and Main Injector to provide ≥ 2 MW to the neutrino production target at 60-120 GeV.
- ⇒ Utilization of a CW linac creates a facility that is unique in the world, with performance that cannot be matched in a synchrotron-based facility.



Project X Functional Requirements



Requirement	Description	Value			
L1	Delivered Beam Energy, maximum	3 GeV (kinetic)			
L2	Delivered Beam Power at 3 GeV	3 MW			
L3	Average Beam Current (averaged over >1 μsec)	1 mA			
L4	Maximum Beam Current (sustained for <1 μ sec)	5 mA			
L5	The 3 GeV linac must be capable of delivering correctly formatted beam to a pulsed linac, for acceleration to 8 GeV				
L6	Charge delivered to pulsed linac	26 mA-msec in < 0.75 sec			
L7	Maximum Bunch Intensity	1.9 x 10 ⁸			
L8	Minimum Bunch Spacing	6.2 nsec (1/162.5 MHz)			
L9	Bunch Length	<50 psec (full-width half max)			
L10	Bunch Pattern	Programmable			
L11	RF Duty Factor	100% (CW)			
L12	RF Frequency	162.5 MHz and harmonics thereof			
L13	3 GeV Beam Split	Three-way			
P1	Maximum Beam Energy 8 GeV				
P2	The 3-8 GeV pulsed linac must be capable of delivering correctly formatted beam for injection into the Recycler Ring (or Main Injector).				
Р3	P3 Charge to fill Main Injector/cycle 26 mA-msec in <0.75 sec				
P4	Maximum beam power delivered to 8 GeV	300 kW			
P5	Duty Factor (initial)	< 4%			

SBNW11-S. Holmes



Project X Functional Requirements



Requirement	Description Value				
M1	Delivered Beam Energy, maximum 120 GeV				
M2	Delivered Beam Energy, minimum	60 GeV			
M3	Minimum Injection Energy	6 GeV			
M4	Beam Power (60-120 GeV)	> 2 MW			
M5	Beam Particles	Protons			
M6	Beam Intensity	1.6 x 10 ¹⁴ protons per pulse			
M7	Beam Pulse Length	~10 µsec			
M8	Bunches per Pulse	~550			
M9	Bunch Spacing 18.8 nsec (1/53.1 MHz)				
M10	Bunch Length	<2 nsec (fullwidth half max)			
M11	Pulse Repetition Rate (120 GeV)	1.2 sec			
M12	Pulse Repetition Rate (60 GeV)	0.75 sec			
M13	Max Momentum Spread at extraction	2 x 10 ⁻³			
I1	The 3 GeV and neutrino programs must operate simultaneously				
12	Residual Activation from Uncontrolled Beam Loss in areas requiring	<20 mrem/hour (average)			
	hands on maintenance.	<100 mrem/hour (peak) @ 1 ft			
13	Scheduled Maintenance Weeks/Year	8			
14	3 GeV Linac Operational Reliability 90%				
15 16	0-120 GeV Operational Reliability 85%				
U1	Facility Lifetime 40 years Provisions should be made to support an ungrade of the CW lines to support an average surrent of 4 mA				
U2	Provisions should be made to support an upgrade of the CW linac to support an average current of 4 mA. Provisions should be made to support an upgrade of the Main Injector to a delivered beam power of ~4 MW at 120 GeV.				
U3	Provisions should be made to deliver CW proton beams as low as 1 GeV.				
U4	Provision should be made to deliver CW proton beams as low as 1 GeV. Provision should be made to support an upgrade to the CW linac such that it can accelerate Protons.				
U5	Provisions should be made to support an upgrade to the CW infact such that it can accelerate Protons. Provisions should be made to support an upgrade of the pulsed linac to support a duty factor or 10%.				
U6	Provisions should be made to support an upgrade of the CW linac to a 3.1 nsec bunch spacing.				
	The second second and the support and upplicate of the own induction of the	- 1.000 0 a opaonigi			

SBNW11-S. Holmes



Pulsed Linac



- The Reference Design utilizes a superconducting pulsed linac for acceleration from 3 to 8 GeV
- ILC style cavities and cryomodules
 - 1.3 GHZ, β=1.0
 - 28 cryomodules (@ 25 MV/m)
- ILC style rf system
 - 5 MW klystron
 - Up to four cryomodules per rf source
- Must deliver 26 mA-msec to the Recycler every 0.75 sec. Options:
 - 1 mA x 4.4 msec pulses at 10 Hz
 - Six pulses required to load Recycler/Main Injector
 - 1 mA x 26 msec pulses at 10 Hz
 - One pulse required to load Main Injector



Performance Goals



Linac

Particle Type

Beam Kinetic Energy

Average Beam Current

Linac pulse rate

Beam Power

Beam Power to 3 GeV program

Pulsed Linac

Particle Type

Beam Kinetic Energy

Pulse rate

Pulse Width

Cycles to MI

Particles per cycle to MI

Beam Power to 8 GeV


Main Injector/Recycler

Beam Kinetic Energy (maximum)

Cycle time

Particles per cycle


Beam Power at 120 GeV





Siting





SBNW11- S. Holmes



Beam Configurations 3 GeV Operating Scenario





1 μsec period at 3 GeV

Muon pulses (16e7) 81.25 MHz, 100 nsec @ 1MHz Kaon pulses (16e7) 20.3 MHz Nuclear pulses (16e7) 10.15 MHz

700 kW 1540 kW 770 kW

Ion source and RFQ operate at 4.2 mA 75% of bunches are chopped @ 2.5 MeV ⇒ maintain 1 mA over 1 μsec





13



Beam Configurations Low Energy Neutrinos



- CW linac naturally produced a high duty factor beam
 - Low duty factor can be created utilizing the chopper, resulting in a beam power of 3 MW × DF
 - ⇒ Creating a high power/low duty factor beam will require an accumulator ring
- Requirements (as I currently understand them):

Beam Energy 3-8 GeV

Beam power 400 kW

- Duty Factor $<1 \times 10^{-3}$

Bunch structure not required



Beam Configurations Low Energy Neutrinos



Accumulator Ring Concepts

Accumulation Ring	A	4	E	3
Energy	3	GeV	3	GeV
Circumference	200	m	200	m
Injection Current	1	mA	1	mA
Injection Time	1	ms	0.2	ms
Np	6.0E+12		1.2E+12	
Injected Turns	1500		300	
Extraction Pulse	0.67	μsec	0.67	μsec
Cycle Time	7.5	msec	1.5	msec
Duty Factor	8.9E-05		4.4E-04	
Average Current	0.13	mA	0.13	mA
Beam Power	400	kW	400	kW
Normalized Emittance (95%)	40	π mm-mr	40	π mm-mr
Bunching Factor	0.5		0.5	
Laslett Tune Shift	-0.01		0.00	

Issues

- Injection
- Extraction



Status and Timeline



- Pre-conceptual design and R&D activities are well supported
 - Reference Design Report released fall 2010
 - Substantial R&D efforts on
 - sc accelerating structures
 - linac front end and chopper
 - rf sources
 - H- injection
- Approval of CD-0 ("Mission Need") is under discussion with DOE
 - DOE-sponsored Intensity Frontier Physics Workshop being planned for October



Status and Timeline



Working timeline

CD-0	FY2012	Mission Need
CD-1	FY2013	Alternative Selection and Cost Range
CD-2	FY2014	Performance Baseline
CD-3	FY2016	Start of Construction
CD-4	FY2021	Start of Operations, Project Complete



Collaboration



- A multi-institutional collaboration has been established to execute the Project X RD&D Program.
 - Organized as a "national project with international participation"
 - Fermilab as lead laboratory
 - International participation established via bi-lateral MOUs.
 - Collaboration MOUs for the RD&D phase outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL ORNL/SNS BARC/Mumbai

BNL MSU IUAC/Delhi

Cornell TJNAF RRCAT/Indore

Fermilab SLAC VECC/Kolkata

LBNL ILC/ART

 Initial discussions have taken place on execution of the construction phase.

SBNW11- S. Holmes



Summary



- Project X is central to Fermilab's strategy for development of the accelerator complex over the coming decade
- A Reference Design has been developed that would support a worldleading Intensity Frontier program at Fermilab over several decades:
 - 5 MW of total beam power available
 - 3 MW to the rare processes program
 - 2 MW to the neutrino program over 60-120 GeV
 - Flexible provision for variable beam formats to multiple users
 - Concepts for supporting short baseline neutrinos identified
- The CW linac is unique for this application, and offers capabilities that would be hard/impossible to duplicate in a synchrotron
- R&D program underway with very significant investment in srf infrastructure and development
- Project X could be constructed over the period ~2016 2020
 - Will be constructed as a national project with international participation



Backup





R&D Program



- The primary elements of the R&D program include:
 - Development of a wide-band chopper
 - Capable of removing bunches in arbitrary patterns at a 162.5 MHz bunch rate
 - Development of an H- injection system
 - Require between 4.4 26 msec injection period, depending on pulsed linac operating scenario
 - Superconducting rf development
 - Includes six different cavity types at three different frequencies
 - Emphasis is on Q₀, rather than high gradient
 - Typically 1.5E10, 15 MV/m (CW)
 - 1.0E10, 25 MV/m (pulsed)
 - Includes appropriate rf sources
 - Includes development of partners
- Goal is to complete R&D phase by 2015



SRF Linac Technology Map



β=0.11	β=0).22	β=0.4	β=0.61	β=0.9	β=1.0
<u> </u>			- CW -			← Pulsed →
	325 2.5-16	MHz 0 MeV			MHz 3 GeV	1.3 GHz 3-8 GeV
Section		Freq	Energy (Me	V) Cav/mag	/CM	Type
SSR0 (β _G :	=0.11)	325	2.5-10	18 /18	/1 S	SR, solenoid
SSR1 (β_{G} :	=0.22)	325	10-42	20/20/	2 S	SR, solenoid
SSR2 (β _G :	=0.4)	325	42-160	40/20/	/4 S	SR, solenoid
LB 650 (β_{G} =0.61)	650	160-460	36 /24	/6 5-cell	elliptical, doublet
HB 650 ($(\beta_G=0.9)$	650	460-3000	160/40/	/20 5-cell	elliptical, doublet
ILC 1.3 ([3 _c =1.0)	1300	3000-8000) 224 /28	/28 9-cel	l elliptical, quad



Joint PX/NF/MC Strategy



- Project X shares many features with the proton driver required for a Neutrino Factory or Muon Collider
 - NF and MC require ~4 MW @ 10± 5 GeV
 - Primary issues are related to beam "format"
 - NF wants proton beam on target consolidated in a few bunches; Muon Collider requires single bunch
 - Project X linac is not capable of delivering this format



⇒ It is inevitable that a new ring(s) will be required to produce the correct beam format for targeting.



Project X Accelerator Requirements: **Rare Processes**



	Proton Energy (kinetic)	Beam Power	Beam Timing
Rare Muon decays	2-3 GeV	>500 kW	1 kHz – 160 MHz
(g-2) measurement	8 GeV	20-50 kW	30- 100 Hz.
Rare Kaon decays	2.6 – 4 GeV	>500 kW	20 – 160 MHz. (<50 psec pings)
Precision K ⁰ studies	2.6 – 3 GeV	> 100 μA (internal target)	20 – 160 MHz. (<50 psec pings)
Neutron and exotic nuclei EDMs	1.5-2.5 GeV	>500 kW	> 100 Hz