

# MICE Cavity Instrumentation

Peter Lane

*Illinois Institute of Technology*

MAP Winter Meeting

December 6th, 2014

SLAC, Menlo Park CA, USA

# What's in there?

- Part I: Instrumentation List and Photos
- Part II: Non-Acoustic Instrumentation Signal Data
- Part III: Acoustic Instrumentation Signal Data

# Part I

## Instrumentation List and Photos


# Cooling Water Lines

- Pressure
- Temperature
- Flow rate

# Vacuum


- Hot Cathode Gauge (HCG)
  - Cavity through top hat
  - Cavity at bottom port
  - Vacuum vessel
  - Left and Right RF couplers
  - Wall manifold
- Vessel Full Range Gauge (FRG)
- Left/Right Coupler Cold Cathode Gauges (CCG)
- Wall manifold Pirani gauge

# Coupler and Vessel Gauges



# Wall Manifold Gauges

Pirani




HCG

# RF System

- Cavity field through top hat.
- Forward/Reflected power on couplers
- Coupler light through view port windows.
- Coupler electron current
- Coax air pressure
- Tuner Push/pull pressure



# Coupler RF Pickups



# Radiation


- Breakdown light in cavity through top hat.
- Plastic scintillators + PMT (X-ray rate)
- NaI crystal scintillator + PMT (X-ray spectrum)
- “Chipmunk” ionization chamber detector (X-ray dose rate)



# X-Ray Detectors

Plastic  
Scintillators

Nal  
Scintillator



"Chipmunk"  
Ionization Chamber  
Detector


# Temperature

- Thermocouples
  - 12 on cavity body
  - 1 on vessel cylinder
  - 2 on cover plates

# Acoustics


- 24 piezo microphones on cavity body
  - For localization of breakdown.

# Cavity Body Instrumentation





# Various Vessel Feed-Throughs




# Part II



Non-Acoustic Instrumentation  
Signal Data





# Normal RF Pulse Control Signals



# Modulator Trip (False Spark) Control Signals



# Cavity Breakdown Control Signals



# Normal RF Pulse Radiation

Nal Crystal



Plastic  
Scintillator  
Paddle

Cavity Light

Fiber 1

Fiber 2

Probe  
Voltage




# Modulator Trip (False Spark) Radiation

Nal Crystal

Plastic  
Scintillator  
Paddle


Cavity Light



Fiber 1

Fiber 2

Probe  
Voltage



# Cavity Breakdown Radiation

Nal Crystal


Plastic  
Scintillator  
Paddle

Cavity Light

Fiber 1

Fiber 2



Probe  
Voltage




# Part III

## Acoustic Signal Data

# Cavity Breakdown Acoustics (RF Hammer + Spark)



Probe  
Voltage






Normal RF Pulse



# RF Hammer Subtraction

- RF Hammer
  - Normal force on inner cavity walls due to the RF pulse
- Subtraction
  - Compute a rolling average of normal RF pulse signals
  - Subtract from spark signal
- Very effective on HPRF cavity signals, but...
  - HPRF acoustic wavefront is after the end of the RF pulse
    - 10x shorter RF pulse
  - HPRF spark dwarfed RF hammer (opposite case)

# Cavity Breakdown Acoustics (Minus RF Hammer)



Probe Voltage

Normal RF Pulse

# Making Sense of the Acoustics

- Larger energy capacity should mean louder sparks
  - Verify end-to-end functionality of mics and DAQ
- Test whether large noise is acoustic
  - Leave unadhered microphones in vacuum vessel
- More experience needed
  - Microphones going on the modular cavity soon
  - Will instrument the HPRF cavity again as well