


Current status of MRD DAQ

Yasuhiro Nakajima

14 September 2006

SciBooNE Collaboration Meeting


DAQ design overview



AMP/Splitter

- AMP: LeCroy 612 PMT Amplifier
 - For 10 stage PMT
 - x10 Amp.
 - 2 output / channel, 12 channel / module (NIM module)
 - Total ~100 ch → 1 NIM crate
 - Amplification time: ~20 ns → compensated by cable length
- Splitter: Passive splitter
 - For 14 stage PMT
 - Total ~250 ch
 - We have to create that

DAQ design overview



ADC

- LeCroy 4300B ADC
- 11 bit, 0.25 pC/channel
- Designed for gate width < 500 ns, while we need 2 μ sec.
 - Pedestal values of some channels goes to negative w/ 2 μ sec gate \rightarrow Fixed!!!
- Succeed to operate 1 module with positive pedestal value.
- PREP has enough number of modules for us.
- There seems no problem so far. Use 4300B for MRD.


Manual at PREP website

Residual Pedestal: Minimum 1 pC and maximum 13 pC for a gate width from 50 to 500 nsec and all inputs open.
Adjustable with an internal potentiometer for gate width
 > 500 nsec. Subtracted from data by CAMAC command.

TDC


- LeCroy 3377 TDC
- Multi hit TDC
- Data size
 - Single word mode: 10 bit
 - Double word mode: 16 bit
- Timing resolution: 0.5-4.0 ns (we can choose)
- Current plan:
 - single word (10 bit), 2.0 ns resolution, 2 μ sec full scale.
 - common stop
- We have 16 modules on hand (we need 13 modules.)
- 1 module is tested and successfully operated.

DAQ design overview




Cosmic trigger

- 2 independent trigger : trigger A, trigger B
 - trigger A(B) will be used for evaluate performance of the counters participating trigger B(A).
 - Will be switched for each cycle.
- Design not fixed
- Current design:



Trigger decision time, delay cable length



- 82 ns from first discriminator to ADC gate input
- + 20 ns: ADC gate should precede the analog signal
- + 10~20 ns: fluctuation of signal timing due to light propagation in scintillator and muon time of flight.
- Total ~122 ns
- We need 25~30m (125~150ns) delay cable for each channel.

Summary and To do

- We have almost all modules we need.
- Splitter
 - Use AMP for 10-stage tube and passive splitter for 14-stage tube.
 - To do: create splitter for ~250 channel
- ADC/TDC
 - ADC: LeCroy 4300B, TDC: LeCroy 3377 (CAMAC modules)
 - Succeeded to operate 1 module
 - To do: check all modules and test DAQ speed with full setup
- Cosmic trigger
 - Basically coincidence of first and last layer: needs ~120 nsec.
 - To do: Create/Correct 25~30m delay cable for every channel.